Table 2, Summary of Compliance Requirements

DeSoto County Generating Company, LLC — Final Permit No. 0270016-009-AV

DeSoto County Energy Park — Facility ID No. 0270016

This table summarizes information for convenience purposes only. This table does not supersede any of the terms or conditions of this permit.

E.U. ID No.	Brief Description
001	Nominal 170 MW Simple Cycle Turbine
002	Nominal 170 MW Simple Cycle Turbine

Pollutant Name or Parameter	Fuel(s)	Compliance Method	Testing Time Frequency	Frequency Base Date *	Min. Compliance Test Duration	CMS**	See permit condition(s)
NOx	All	CEMS	Continuous		24-hour block avg.	Yes	II.A.19., 20. & 22. and 26.-35.
NOx	All	EPA Method 20	Annual/Concurrent with RATA		3 1-hour test runs		III.A.26.-35.
SO_2 % Sulfur	All	Fuel Sampling & Analysis - ASTM Methods	Daily / Transfer				III.A.23. & 24. and 26.-35.
PM/PM_{10}	All	VE serves as surrogate	None		N/A		III.A.15. & 26.-35.
VE	All	EPA Method 9	Annual		30-minutes	No	III.A.26.-35.
VOC	All	EPA Method 18, 25 and/or 25A	Initial only		3 1-hour test runs	No	III.A.26.-35.
CO	All	EPA Method 10	Renewal		3 1-hour test runs	No	III.A.26.-35.
O_2	All		N/A		N/A	Yes	III.A.41.

Notes:

* The frequency base date is established for planning purposes only; see Rule 62-297.310, F.A.C.

**CMS [=] continuous monitoring system