Table 2-1, Summary of Compliance Requirements

OWENS CORNING ROOFING AND ASPHALT, LLC
JACKSONVILLE PLANT

PROPOSED Permit No.: 0310050-017-AV
Facility ID No.: 0310050

This table summarizes information for convenience purposes only. This table does not supersede any of the terms or conditions of this permit.
***Notes: The frequency base date is established for planning purposes only; see Rule 62-297.310, F.A.C.
**CMS [=] continuous monitoring system

EU ID No.	Pollutant Name or Parameter	Fuel(s)	Compliance Method	Testing Time Frequency	Frequency Base Date ***	Min. Compliance Test Duration	CMS**	See permit condition(s)
# 001	PM		EPA RM 5	Upon Request		3 Runs		III, 001, 9. and 10.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 001, 7. and 8.
# 002	PM		EPA RM 5	Upon Request		3 Runs		III, 002, 8. and 9.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 002, 6. and 7.
# 003	PM		EPA RM 5	Upon Request		3 Runs		III, 003, 9. and 10.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 003, 7. and 8.
# 004	PM		EPA RM 5	Upon Request		3 Runs		III, 004, 9. and 10.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 004, 7. and 8.
# 012	PM		EPA RM 5A	Annually	11/1/2012	3 Runs		III, 012, 10. and 11.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 012, 12. and 13.
	Temperature			Continuously			Yes	III, 012, 15. and 18.
# 015	VE (Incinerator)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 015, 6. and 7.
	VE (CECO filter)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 015, 6. and 8.
	Temperature			Continuously	11/1/2012		Yes	III, 015, 9. and 10.
# 021	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 021, 7. and 8.
* # 028	PM		EPA RM 5	Upon Request		3 Runs		III, 028, 9. and 10.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 028, 7. and 8.
* # 029	PM		EPA RM 5	Upon Request		3 Runs		III, 029, 9. and 10.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 029, 7. and 8.
# 030	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 030, 6. and 7.
# 031	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 031, 6. and 7.
# 034	PM		EPA RM 5A	Annually	11/1/2012	3 Runs		III, 034, 12 and 13.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 034, 10. and 11.
	Temperature			Continuously			Yes	III, 034, 15
	Pressure drop			Continuously			Yes	III, 034, 16
# 037	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 037, 5. and 6.
# 038	VE (Incinerator)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 038, 6. and 7.
	VE (CECO filter)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 038, 6. and 8.
#039	VE (Incinerator)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 039, 6. and 7.
	VE (CECO filter)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 039, 6. and 8.
#040	VE (Incinerator)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 040, 6. and 7.
	VE (CECO filter)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 040, 6. and 8.
	Temperature			Continuously	11/1/2012		Yes	III, 040, 8.
# 042	PM		EPA RM 5	Upon Request		3 Runs		III, 042, 9. and 10.
	VE		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 042, 7. and 8.
# 043	VE (Incinerator)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 043, 7. and 8.
	VE (CECO filter)		EPA RM 9	Annually	11/1/2012	30 Minutes		III, 043, 7. and 9.

* See Appendix CAM for more monitoring information

0310050-017sum2-AV.xls