Compliance Plan CP-3
White Springs Agricultural Chemicals, Inc.
Suwannee River/Swift Creek Complex
Facility ID No.: 0470002
Title V Revision 0470002-077-AV
Hamilton County

All of the applicable requirements of Construction Permit Nos. 0470002-061-AC and 0470002-069-AC are incorporated into Title V Revision No. 0470002-075-AV. All construction has been completed for this project. Testing and the submission of testing reports remain outstanding.

The Permittee shall conduct all testing required by Construction Permit Nos. 0470002-061-AC and 0470002-069-AC and comply with the following conditions regarding the testing requirements:

Construction Permit No. 0470002-061-AC-

1. EU is shut down and will be tested upon startup, as per permit condition.

Construction Permit No. 0470002-069-AC-

2. **Initial Compliance Tests.** The emissions unit shall be tested to demonstrate initial compliance with the emissions standards for **Fluoride**. The initial tests shall be conducted within 60 days after achieving permitted capacity, but not later than 180 days after initial operation of the unit.

   [Rules 62-4.070(3) and 62-297.310(7)(a)1, F.A.C.]

3. **Operating Rate During Testing**. Unless otherwise stated in the applicable emission limiting standard rule, testing of emissions shall be conducted with the emissions unit operation at permitted capacity as defined below. Permitted capacity is defined as 90 to 100 percent of the maximum operation rate allowed by the permit. If it is impractical to test at permitted capacity, an emissions unit may be tested at less than the minimum permitted capacity; in this case, subsequent emissions unit operation is limited to 110 percent of the test load until a new test is conducted. Once the unit is so limited, operation at higher capacities is allowed for no more than 15 consecutive days for the purpose of additional compliance testing to regain the authority to operate at the permitted capacity.

   [Rule 62-297.310, F.A.C.]

4. The Permittee shall meet all of the notifications, testing and reporting requirements of Rule 62-297, F.A.C.

5. Once the Permittee successfully demonstrates compliance with this Compliance Plan CP-3, compliance demonstrations shall resume in accordance with the specific conditions of the Title V Permit.