United States Gypsum Company

FACILITY ID NO.: 0310072
DUVAL COUNTY
AIR CONSTRUCTION PERMIT
DRAFT PERMIT NO.: 0310072-019-AC

PERMITTING AND COMPLIANCE AUTHORITY
ENVIRONMENTAL AND COMPLIANCE DEPARTMENT
ENVIRONMENTAL QUALITY DIVISION
407 NORTH LAURA STREET
THIRD FLOOR
JACKSONVILLE, FL 32202
TELEPHONE: (904) 255-7100
FAX: (904) 588-0518

Air Construction Permit
DRAFT Permit No.: 0310072-019-AC

Table of Contents

Section **Page Number**

Placard Page 1

I. Facility Information ..... 2 - 3
- A. Facility and Project Description
- B. Summary of Emission Unit (EU) Identification (ID) Nos. and Brief Descriptions
- C. Relevant Documents

II. Facility Wide Conditions ..... 3 - 7

III. Emission Units and Descriptions ..... 7 - 10

EU ID No.	**Brief Description**
062	No. 3 Board Plant Starch Storage Bins
111	No. 3 Board Plant Starch Receiver/Refill Bin

Permittee:
United States Gypsum Company
6825 Evergreen Ave.
Jacksonville, FL 32208-4996

DRAFT Permit No.: 0310072-019-AC
Facility ID No.: 0310072
SIC No.: 32
Project: Air Construction Permit
Facility Modification

This permit is for the modification of the gypsum wallboard manufacturing facility to replace the dust collector for Emission Unit (EU) No. 062 (No. 3 Board Plant Starch Storage Bins) and to add a dust collector to the existing No. 3 Board Plant Starch Receiver/Refill Bin (new EU No. 111) at the United States Gypsum Company, located at 6825 Evergreen Ave., Jacksonville, Duval County, Florida, 32208-4996. UTM Coordinates: Zone 17, 438.9 km East and 3361.2 km North; Latitude: 30^0 22' 52" North and Longitude: 81^0 38' 07" West.

This permit is issued under the provisions of Chapter 403, Florida Statutes (FS) and Florida Administrative Code (FAC) Chapters 62-4, 62-204, 62-210, 62-212, 62-213, 62-296, and 62-297. The above named permittee is hereby authorized to perform the work or operate the facility shown on the application and approved drawing(s), plans, and other documents, attached hereto or on file with the Environmental and Compliance Department, Environmental Quality Division (Permitting Authority) in accordance with the terms and conditions of this permit.

Title V Air Operation Permit Revision Application Due Date:
Expiration Date:

Environmental and Compliance Department
Environmental Quality Division

Robert Steven Pace, P.E.
Air Quality Branch Manager

RSP/GHB

Section I. Facility Information

Subsection A. Project and Facility Description

The purpose of this air construction permit is to replace the dust collector for Emission Unit (EU) No. 062 (No. 3 Board Plant Starch Storage Bins) and to add a dust collector to the existing No. 3 Board Plant Starch Receiver/Refill Bin (new EU No. 111).

This facility consists of a manufacturing plant for the production of gypsum wallboard. Gypsum ore is received at the plant by ship or barge and unloaded into stockpiles. Gypsum ore is then conveyed to the crushing and conveying system. Crushed ore is dried and then conveyed to the landplaster system where the crushed gypsum is further ground in the Raymond mills. The finely ground and dried gypsum (known as landplaster) is conveyed to the stucco production area where the landplaster is introduced into calcining kettles which by indirect heating drives off the chemically bound water from the landplaster which turns it into a product called stucco. Stucco is then dry mixed with other additives and introduced to the pin mixer where water is added to the mix. The liquid stucco mix is then introduced between two sheets of paper (or glass mat) in the wallboard forming machine to form wallboard. The wet wallboard is dried on the conveying line at the wallboard dryer, cut, end-trimmed and stacked for distribution.

The facility also consists of a joint treatment compounds manufacturing operation using the major raw materials calcium carbonate, perlite, clay, and mica. These materials are delivered by railcar and stored in silos (EU Nos. 101 through 105). Raw materials from these silos are processed through the Wet and Dry Premixer System (EU 106) where the dry raw materials are mixed in dry premixers and then transferred to wet mixers where liquid additives are added to produce a paste. The paste proceeds from the wet mixers to the Joint Treatment Pail Fill Stations. Small quantities of other dry raw materials are added to the Dry Premixers from the Joint Treatment Bag Dumpstation (EU 107). These final products are shipped out for consumer use and are not used to manufacture wallboard. There are no crushers or grinding operations associated with the production of joint treatment compounds and this operation is not connected by conveyor to the crusher, screening operation nor grinding mills in the wallboard manufacturing operation, therefore the EUs (101-107) associated with the manufacture of joint treatment compounds are not subject to the provisions of New Source Performance Standards (NSPS), 40 Code of Federal Regulation (CFR) 60, Subpart OOO, Standards of Performance for Non-Metallic Mineral Processing Plants.

The facility is a major source of air pollution because the potential emissions of at least one regulated air pollutant is greater than 100 tons per year pursuant to Chapter 62-210, FAC, and Rule 2.301, Jacksonville Environmental Protection Board (JEPB).

The facility is subject to the provisions of New Source Performance Standards (NSPS), 40 Code of Federal Regulation (CFR) 60, Subpart OOO, Standards of Performance for Non-Metallic Mineral Processing Plants, and Subpart UUU, Standards of Performance for Calciners and Dryers in Mineral Industries, 40 CFR 60, Subpart A, General Conditions, and Particulate Matter (PM) Reasonably Available Control Technology (RACT) requirements. The facility is currently minor for purposes of Prevention of Significant Deterioration (PSD) purposes and will remain minor, post modification, for PSD. A facility wide emission limit has been established for PM and VOC of less than 250 tons per year each. The facility has established a facility wide emission limit for HAPs of less than 10 tons per year for any single HAP and less than 25 tons per year for total HAPs classifying it as a minor source of HAPs.

Subsection B. Summary of Emission Unit (EU) ID Nos. and Brief Descriptions

EU ID No.	Brief Description
062	No. 3 Board Plant Starch Storage Bins
111	No. 3 Board Plant Starch Receiver/Refill Bin

Subsection C. Relevant Documents

Air construction permit application received July 15, 2011

Section II. Facility Wide Conditions

Subsection A. General Conditions

1. The terms, conditions, requirements, limitations, and restrictions set forth herein are "Permit Conditions" and are binding and enforceable pursuant to Sections 403.141, 403.727, or 403.859 through 403.861, Florida Statutes. The permittee is placed on notice that the Permitting Authority will review this permit periodically and may initiate enforcement action for any violation of these conditions.

2. This permit is valid only for the specific process and operations applied for and indicated in the approved drawings or exhibits. Any unauthorized deviation from the approved drawings, exhibits, specifications, or conditions of this permit may constitute grounds for revocation and enforcement action by the Permitting Authority.

3. As provided in subsections 403.087(6) and 403.722(5), Florida Statutes, the issuance of this permit does not convey any vested rights or any exclusive privileges. Neither does it authorize any injury to public or private property or any invasion of personal rights, nor any infringement of federal, state, or local laws or regulations. This permit is not a waiver of or approval of any other Permitting Authority permit that may be required for other aspects of the total project which are not addressed in this permit.

4. This permit conveys no title to land or water, does not constitute State recognition or acknowledgement of title, and does not constitute authority for the use of submerged lands unless herein provided and the necessary title or leasehold interests have been obtained from the State. Only the Trustees of the Internal Improvement Trust Fund may express State opinion as to title.

5. This permit does not relieve the permittee from liability for harm or injury to human health or welfare, animal, or plant life, or property caused by the construction or operation of this permitted source, or from penalties therefore, nor does it allow the permittee to cause pollution in contravention of Florida Statutes and Permitting Authority rules, unless specifically authorized by an order from the Permitting Authority.

6. The permittee shall properly operate and maintain the facility and systems of treatment and control (and related appurtenances) that are installed and used by the permittee to achieve compliance with the conditions of this permit, as required by Permitting Authority rules. This provision includes the operation of backup or auxiliary facilities or similar systems when necessary to achieve compliance with the conditions of the permit and when required by Permitting Authority rules.

7. The permittee, by accepting this permit, specifically agrees to allow authorized Permitting Authority personnel, upon presentation of credentials or other documents as may be required by law and at reasonable times, access to the premises where the permitted activity is located or conducted to:
    a. Have access to and copy any records that must be kept under conditions of the permit;
    b. Inspect the facility, equipment, practices, or operations regulated or required under this permit; and
    c. Sample or monitor any substances or parameters at any location reasonably necessary to assure compliance with this permit or Permitting Authority rules.

    Reasonable time may depend on the nature of the concern being investigated.

8. If, for any reason, the permittee does not comply with or will be unable to comply with any condition or limitation specified in this permit, the permittee shall immediately provide the Permitting Authority with the following information:
   a. A description of and cause of noncompliance; and
   b. The period of noncompliance, including dates and times; or, if not corrected, the anticipated time the noncompliance is expected to continue, and steps being taken to reduce, eliminate, and prevent recurrence of the noncompliance. The permittee shall be responsible for any and all damages which may result and may be subject to enforcement action by the Permitting Authority for penalties or revocation of this permit.

9. In accepting this permit, the permittee understands and agrees that all records, notes, monitoring data and other information relating to the construction or operation of this permitted source which are submitted to the Permitting Authority may be used by the Permitting Authority as evidence in any enforcement case involving the permitted source arising under the Florida Statutes or Permitting Authority rules, except where such use is prescribed by Sections 403.111 and 403.73, Florida Statutes. Such evidence shall only be used to the extent it is consistent with the Florida Rules of Civil Procedure and appropriate evidentiary rules.

10. The permittee agrees to comply with changes in Permitting Authority rules and Florida Statutes after a reasonable time for compliance; provided, however, the permittee does not waive any other rights granted by Florida Statutes or Permitting Authority rules.

11. This permit is transferable only upon Permitting Authority approval in accordance with Rules 62-4.120 and 62-730.300, FAC, as applicable. The permittee shall be liable for any noncompliance of the permitted activity until the transfer is approved by the Permitting Authority.

12. This permit or a copy thereof shall be kept at the work site of the permitted activity.

13. This permit also constitutes:
    ( ) Determination of Best Available Control Technology (BACT)
    ( ) Determination of Prevention of Significant Deterioration (PSD)
    ( ) Certification of Compliance with State Water Quality Standards (Section 401, PL 92-500)
    (X) Compliance with New Source Performance Standards

14. The permittee shall comply with the following:
    a. Upon request, the permittee shall furnish all records and plans required under Permitting Authority rules. During enforcement actions, the retention period for all records will be extended automatically unless otherwise stipulated by the Permitting Authority.
    b. The permittee shall hold at the facility or other location designated by this permit, records of all monitoring information (including all calibration and maintenance records and all original strip chart
    recordings for continuous monitoring instrumentation) required by this permit, copies of all reports required by this permit, and records of all data used to complete the application for this permit. These materials shall be retained at least three years from the date of the sample, measurement, report, or application unless otherwise specified by Permitting Authority rule.
    c. Records of monitoring information shall include:
       1. The date, exact place, and time of sampling or measurements;
       2. The person responsible for performing the sampling or measurements;
       3. The date(s) analyses were performed;
       4. The person responsible for performing the analyses;
       5. The analytical techniques or methods used;

6. The results of such analyses.

15. When requested by the Permitting Authority, the permittee shall within a reasonable time furnish any information required by law which is needed to determine compliance with the permit. If the permittee becomes aware that relevant facts were not submitted or were incorrect in the permit application or in any report to the Permitting Authority, such facts or information shall be corrected promptly.
[Rule 62-4.160, FAC, and Rule 2.1401, Jacksonville Environmental Protection Board (JEPB)]

Subsection B. Specific Conditions

1. Permittee shall notify the Permitting Authority fifteen (15) days prior to EU testing.
[Rule 62-297.310(7)(a)(9), FAC, and Rule 2.1201, JEPB]

2. Copies of the test report(s) shall be filed with the Permitting Authority within forty-five (45) days of completion of testing.
[Rule 62-297.310(8)(b), FAC, and Rule 2.1201, JEPB]

3. Stack sampling facilities shall comply with the requirements of 40 CFR 60.8(e), Rule 62-204.800, FAC, Rule 62-297.310(6), FAC, Rule 2.201, JEPB, and Rule 2.1201, JEPB.

4. Testing of emissions shall be conducted with the EU operating at permitted capacity. Permitted capacity is defined as 90-100 percent of the maximum operating rate allowed by the permit. If it is impracticable to test at permitted capacity, then EU may be tested at less than capacity; in this case subsequent EU operation is limited to 110 percent of the test load until a new test is conducted. Once the EU is so limited, then operation at higher capacities is allowed for no more than 15 consecutive days for the purposes of additional compliance testing to regain the permitted capacity in the permit.
[Rule 62-297.310(2), FAC, and Rule 2.1201, JEPB]

5. Any revision(s) to a permit (and application) shall be submitted to and approved by the Permitting Authority prior to implementing.
[Rule 62-4.080(2), FAC, and Rule 2.1401, JEPB]

6. Permittee shall submit an annual operation report to the Permitting Authority for this (these) emission unit(s) on the form(s) supplied for each calendar year on or before April 1.
[Rule 62-210.370(3), FAC, and Rule 2.301, JEPB]

7. The construction/modification shall reasonably conform to the plans and schedule submitted in the application. If the permittee is unable to complete construction on schedule, the Permitting Authority must be notified in writing sixty (60) days prior to the expiration of the construction permit. A new schedule and request for an extension of the construction permit must be submitted.
[Rule 62-4.080(3), FAC, and Rule 2.1401, JEPB]

8. To obtain a permit to operate, the permittee must demonstrate compliance with the conditions of the construction permit and submit a complete application for a Title V Air Operation Permit Revision with compliance records and test results, to the Permitting Authority, at least 90 days prior to the expiration date of the construction permit, but no later than 180 days after commencing operation. An applicant making timely and complete application for an operation permit shall continue to operate the source under the authority and provisions of any existing valid permit until the conclusion of proceedings associated with its permit application or until the new permit becomes effective, whichever is later, provided the applicant complies with all the provisions of subparagraphs 62-213.420(1)(b)3., FAC.

[Rule 62-213.420(1)(a) and (b)2., FAC and Rule 2.501, JEPB]

9. The permittee shall submit all compliance related notifications and reports required of this permit to:
Environmental and Compliance Department
Environmental Quality Division
407 North Laura Street, Third Floor
Jacksonville, FL 32202
Telephone: (904) 255-7100
Fax: (904) 588-0518

10. General Pollutant Emission Limiting Standards. Objectionable Odor Prohibited.
The permittee shall not cause, suffer, allow, or permit the discharge of air pollutants, which cause or contribute to an objectionable odor in accordance with Rule 62-296.320(2), FAC, and Rule 2.1101, JEPB.

11. The facility shall be subject to City of Jacksonville Ordinance Code, Title X, Chapter 360 [Environmental Regulation], Chapter 362 [Air and Water Pollution], Chapter 376 [Odor Control], and JEPB Rule 1 [Final Rules with Respect to Organization, Procedure, and Practice].

12. The facility shall be subject to JEPB Rule 2, Part Nos. I through VII, and Part Nos. IX through XIV.

13 Excess emissions resulting from startup, shutdown, or malfunction of any emission unit shall be permitted providing (1) best operational practices to minimize emissions are adhered to and (2) the duration of excess emissions shall be minimized but in no case exceed two hours in any 24 hour period unless specifically authorized by the Permitting Authority for longer duration. Excess emissions which are caused entirely or in part by poor maintenance, poor operation, or any other equipment or process failure which may reasonably be prevented during startup, shutdown, or malfunction shall be prohibited. In the case of excess emissions resulting from malfunctions, each owner or operator shall notify the Permitting Authority in accordance with
Rule 62-4.130, FAC and Rule 2.1401, JEPB. A full written report on the malfunctions shall be submitted to the Permitting Authority in a quarterly report, if requested by the Permitting Authority.
[Rule 62-210.700, FAC, and Rule 2.201, JEPB]

14. No person shall cause, let, permit, suffer or allow the emissions of unconfined particulate matter emissions from any activity, including vehicular movement; transportation of materials; construction, alteration, demolition or wrecking; or industrially related activities such as loading, unloading, storing or handling; without taking reasonable precautions to prevent such emissions. Reasonable precautions include the following:
a. Paving and maintenance of roads, parking areas and yards.
b. Application of water or chemicals to control emissions from such activities as demolition of buildings, grading roads, construction, and land clearing.
c. Application of asphalt, water, oil, chemicals or other dust suppressants to unpaved roads, yards, open stock piles and similar activities.
d. Removal of particulate matter from roads and other paved areas under the control of the owner or operator of the facility to prevent re-entrainment, and from buildings or work areas to prevent particulate from becoming airborne.
e. Landscaping or planting of vegetation.
f. Use of hoods, fans, filters, and similar equipment to contain, capture and/or vent particulate matter.
g. Confining abrasive blasting where possible.
h. Enclosure or covering of conveyor systems.

[Rule 62-296.320(4)(c), FAC, and Rule 2.1101, JEPB]

15. Maximum allowable facility wide emissions of particulate matter (PM), particulate matter less than 10 micronsin aerodynamic diameter (PM_{10}), and of volatile organic compounds (VOC) shall be limited to 249.9 Tons per year (TPY) for each pollutant.
[Permit No.0310072-015-AC, Rule 62-4.070(3), FAC, Rule 62-212.400(12), FAC, Rule 2.1401, JEPB and Rule 2.401, JEPB]

16. Maximum allowable facility wide emissions of Hazardous Air Pollutants (HAP) are restricted to less than 10 TPY for any single HAP and to less than 25 TPY for total HAP(s). Tons per year shall be designated as any 12 consecutive month period.
[Permit No.0310072-015-AC, Rule 62-4.070(3), FAC, and Rule 2.1401, JEPB]

17. Source Obligation:

(a) At such time that a particular source or modification becomes a major stationary source or major modification (as these terms were defined at the time the source obtained the enforceable limitation) solely by virtue of a relaxation in any enforceable limitation which was established after August 7, 1980, on the capacity of the source or modification otherwise to emit a pollutant, such as a restriction on hours of operation, then the requirements of subsections 62-212.400(4) through (12), F.A.C., shall apply to the source or modification as though construction had not yet commenced on the source or modification.

(b) At such time that a particular source or modification becomes a major stationary source or major modification (as these terms were defined at the time the source obtained the enforceable limitation) solely by exceeding its projected actual emissions, then the requirements of subsections 62-212.400(4) through (12), F.A.C., shall apply to the source or modification as though construction had not yet commenced on the source or modification.

[Rule 62-212.400(12), FAC and Rule 2.401, JEPB]

Section III. Emission Units and Conditions

Emission Unit No. 062-No. 3 Board Plant Starch Storage Bins

Emission Unit Description: Stucco material storage

Particulate Matter (PM) control device: SENECA Baghouse, Model 24-FMBV-100 (Special)

Essential Potential to Emit (PTE) Parameters

1. The estimated maximum process rate is 25 TPH.
[Rule 62-296.700(4), FAC, and Rule 2.1101, JEPB]

2. The estimated maximum air flow rate is 1,200 dscfm.
[Rule 62-296.700(4), FAC, and Rule 2.1101, JEPB]

3. This EU shall be allowed to operate continuously; i.e.: 8760 hours per year.
[Rule 62-210.200(PTE), FAC, and Rule 2.301, JEPB]

Emission Limitations and Standards

4. 40 CFR 60, Subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants and 40 CFR 60, Subpart A, General Provisions, shall apply to this emission unit.
5. Reasonably Available Control Technology (RACT) requirements including **Specific RACT Emission Limiting Standards for Stationary Emissions Units** [Rule 62-296.700(3), FAC, and Rule 2.1101, JEPB]**; Maximum Allowable Emission Rates** [Rule 62-296.700(4), FAC, and Rule 2.1101, JEPB]; **Circumvention** [Rule 62-296.700(5), FAC, and Rule 2.1101, JEPB], and **Operation and Maintenance Plan** [Rule 62-296.700(6), FAC, and Rule 2.1101, JEPB] shall apply to this emission unit.

6. PM emissions shall be limited to 0.015gr/dscf [0.15 lbs/hr and 0.68 TPY].
[Permit No. 0310072-015-AC, Rule 62-296.711, FAC, and Rule 2.1101, JEPB]

7. VE shall be limited to 5 % opacity.
[40 CFR 60.672, Rule 62-204.800(8), FAC, Rule 62-296.711, FAC, Rule 2.1101, JEPB, and Rule 2.201, JEPB]

Test Methods and Procedures

8. Testing for demonstration of compliance shall be performed in accordance with EPA Reference Method 9 (as described in 40 CFR 60, Appendix A), and the procedures in 40 CFR 60.11, for the visual determination of opacity.
[40 CFR 60.675, Rule 62-204.800(8), FAC, Rule 62-296.711, FAC, Rule 2.1101, JEPB, and Rule 2.201, JEPB]

9. Initial VE compliance testing on the new baghouse shall be conducted within 60 days after achieving the maximum production rate at which the emission unit will be operated, but no later than 120 days after initial start-up. VE testing shall be conducted for a minimum period of 30 minutes.
[40 CFR 60.8, Rule 62-204.800, FAC, Rule 62-297.310(4), FAC, Rule 2.201, JEPB and Rule 2.1201, JEPB]

10. Testing for demonstration of compliance shall be performed in accordance with EPA Reference Method 5 (as described in 40 CFR 60, Appendix A), for the determination of the PM concentration. The minimum sample volume shall be 30 dscf.
[Rule 62-296.711, FAC, and Rule 2.1101, JEPB]

11. PM testing shall be conducted upon request of the Permitting Authority.
[Rule 62-297.310(7)(b), FAC, and Rule 2.1201, JEPB]

Record-keeping and Reporting

12. The permittee shall submit an Operation and Maintenance Plan with the Title V Revision Application.
[Rule 62-296.700(6), FAC and Rule 2.1101, JEPB]

Emission Unit No. 111-No. 3 Board Plant Starch Receiver/Refill Bin

Emission Unit Description: Starch receiving and storage

Particulate Matter (PM) control device: SENECA Baghouse Model 2-CARTHZ-245

Essential Potential to Emit (PTE) Parameters

1. The estimated maximum process rate is 3 TPH.
[Rule 62-296.700(4), FAC, and Rule 2.1101, JEPB]
2. The estimated maximum air flow rate is 500 dscfm.
[Rule 62-296.700(4), FAC, and Rule 2.1101, JEPB]

3. This EU shall be allowed to operate continuously ; i.e.: 8760 hours per year.
[Rule 62-210.200(PTE), FAC, and Rule 2.301, JEPB]

Emission Limitations and Standards

4. 40 CFR 60, Subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants and 40 CFR 60, Subpart A, General Provisions, shall apply to this emission unit.

5. Reasonably Available Control Technology (RACT) requirements including **Specific RACT Emission Limiting Standards for Stationary Emissions Units** [Rule 62-296.700(3), FAC, and Rule 2.1101, JEPB]**; Maximum Allowable Emission Rates** [Rule 62-296.700(4), FAC, and Rule 2.1101, JEPB]; **Circumvention** [Rule 62-296.700(5), FAC, and Rule 2.1101, JEPB], and **Operation and Maintenance Plan** [Rule 62-296.700(6), FAC, and Rule 2.1101, JEPB] shall apply to this emission unit.

6. PM emissions shall be limited to 0.015 gr/dscf [0.06 lbs/hr and 0.28 TPY].
[Applicant's Request, Rule 62-296.711, FAC, and Rule 2.1101, JEPB]

7. VE shall be limited to 5 % opacity.
[40 CFR 60.672, Rule 62-204.800(8), FAC, Rule 62-296.711, FAC, Rule 2.1101, JEPB, and Rule 2.201, JEPB]

Test Methods and Procedures

8. Testing for demonstration of compliance shall be performed in accordance with EPA Reference Method 9 (as described in 40 CFR 60, Appendix A), and the procedures in 40 CFR 60.11, for the visual determination of opacity.
[40 CFR 60.675, Rule 62-204.800(8), FAC, Rule 62-296.711, FAC, Rule 2.1101, JEPB, and Rule 2.201, JEPB]

9. Initial VE compliance testing on the new baghouse shall be conducted within 60 days after achieving the maximum production rate at which the emission unit will be operated, but no later than 120 days after initial start-up. VE testing shall be conducted for a minimum period of 30 minutes.
[40 CFR 60.8, Rule 62-204.800, FAC, Rule 62-297.310(4), FAC, Rule 2.201, JEPB and Rule 2.1201, JEPB]

10. Testing for demonstration of compliance shall be performed in accordance with EPA Reference Method 5 (as described in 40 CFR 60, Appendix A), for the determination of the PM concentration. The minimum sample volume shall be 30 dscf.
[Rule 62-296.711, FAC, and Rule 2.1101, JEPB]

11. PM testing shall be conducted upon request of the Permitting Authority.
[Rule 62-297.310(7)(b), FAC, and Rule 2.1201, JEPB]

Record-keeping and Reporting

12. The permittee shall submit an Operation and Maintenance Plan with the Title V Revision Application. [Rule 62-296.700(6), FAC and Rule 2.1101, JEPB]

S:\air quality\permitv\TVCP\draft\0310072-019acf-AC