BASF Corporation
Quincy Operations
Facility ID No.: 0390005
Gadsden County

Title V Air Operation Permit Revision
DRAFT Permit No.: 0390005-016-AV

Revision to Title V Air Operation Permit No.: 0390005-014-AV

Permitting and Compliance Authority
Department of Environmental Protection
Northwest District Office
160 W. Government Street, Suite 308
Pensacola, FL 32502-5740
Telephone: 850/595-8300
Fax: 850/595-8096

Title V Air Operation Permit Revision

DRAFT Permit No.: 0390005-016-AV
Revision to Title V Air Operation Permit No.: 0390005-014-AV

Table of Contents

Section **Page Number**

Placard Page 1

I. Facility Information 2
- A. Facility Description.
- B. Summary of Emissions Unit ID No(s). and Brief Description(s).
- C. Relevant Documents.

II. Facility-wide Conditions 6

III. Emissions Unit(s) and Conditions
- A. Gel Clay Production Equipment not subject to NSPS (Baghouses) 9
- B. Gel Clay Production Equipment subject to NSPS (Baghouses) 12
- C. Granular Clay Production Equipment subject to NSPS (Baghouses) 16
- D. Granular Clay Fired Equipment not subject to NSPS (Baghouses) 20
- E. Granular Clay Fired Equipment not subject to NSPS (Scrubbers) 23
- F. Gel Clay Fired Equipment not subject to NSPS (Scrubbers) 26
- G. ACM Milling/Ultra Fine Grind subject to NSPS (Baghouses) 29
- H. Common Conditions 34
- I. NSPS Common Conditions 36

Appendices
- Statement of Basis
- Appendix A-1, Abbreviations, Acronyms, Citations, and Identification Numbers
- Appendix I-1, List of Insignificant Emissions Units and/or Activities
- Appendix SS-1, STACK SAMPLING FACILITIES version dated 10/07/96
- Appendix TV-6, TITLE V CONDITIONS version dated 6/23/06
- Appendix CAM
- Startup and Shutdown Plan
- Appendix Equipment Requirements (available upon request)
- Table 1, Applicability of Subpart A to Subpart OOO

Permittee:
BASF Corporation
1101 North Madison Street
Quincy, Florida 32352

DRAFT Permit No.: 0390005-016-AV
Facility ID No.: 0390005
SIC No(s).: 32, 3295
Project: Title V Air Operation Permit Revision

This permit revision is being issued to incorporate the terms and conditions of air construction permit No. 0390005-015-AC, for the modification of two existing pneumatic transporters and the installation of one pneumatic transporter to replace an existing Horizon pneumatic transporter system at the existing Quincy Operations. This facility is located at 1101 North Madison Street in Quincy, Gadsden County; UTM Coordinates: Zone 16, 732.6 km East and 3387.5 km North.

This Title V Air Operation Permit Revision is issued under the provisions of Chapter 403, Florida Statutes (F.S.), and Florida Administrative Code (F.A.C.) Chapters 62-4, 62-210 and 62-213. The above named permittee is hereby authorized to operate the facility shown on the application and approved drawing(s), plans, and other documents, attached hereto or on file with the permitting authority, in accordance with the terms and conditions of this permit.

Referenced attachments made a part of this permit:
Appendix I-1, List of Insignificant Emissions Units and/or Activities
Appendix TV-6, TITLE V CONDITIONS version dated 06/23/06
Appendix SS-1, STACK SAMPLING FACILITIES version dated 10/07/96
Appendix CAM
Appendix A-1, Abbreviations, Acronyms, Citations, and Identification Numbers
Startup and Shutdown Plan
Appendix Equipment Requirements (available upon request)
Table 1, Applicability of Subpart A to Subpart OOO

Initial Effective Date: January 26, 2010
Revision Effective Date: [ARMS Day 55+1]
Renewal Application Due Date: June 15, 2014
Expiration Date: January 26, 2015

Rick Bradburn
Air Program Administrator

RB/aj/c

Section I. Facility Information.

This permit revision is being issued for the purpose of incorporating the terms and conditions of air construction permit, No. 0390005-015-AC, being concurrently processed, into 0390005-014-AV, effective January 26, 2010.

The permittee requested that the Visible Emissions (VE) testing frequency be reduced from annually to prior to permit renewal. Emissions Units that are not subject to 40 CFR 60 subpart OOO and have consistently demonstrated low opacity readings will be modified to a VE test frequency from annually to prior to permit renewal.

Subsection A. Facility Description.

The BASF Corporation Quincy Operation processes Attapulgite Clay and Fullers Earth in two major product lines: Granular Processing and Gel Processing. Granular processing essentially consists of crushing drying, sizing and packing. Gel processing essentially consists of crushing, extruding with additives (magnesium oxide), drying/milling, classifying and packing. The crude clay from the mines is trucked to the facility either stockpiled by quality or fed directly to a primary crusher. Based on production needs and clay quality, it may be blended by mixing various grades using a front end loader. The clay is then stored under the Granular Storage Shed or the Gel Storage Shed, dependent on the clay quality.

In general, emissions consisting of particulate matter (PM) resulting from clay handling and processing are controlled by baghouses. Some of the natural gas or propane-fired equipment (Granular Clay and Gel Clay fired equipment) emissions are controlled by scrubbers.

Granular Processing

A front-end loader feeds clay from the granular Crude Shed to a crusher and screen systems to reduce the size to one-half inch. The crude feed may be blended with extradite material and fed to one of two Fluid Bed Dryers. The clay is fed directly from the dryers to the 1A Mill or stored in a stock bin. A reconstitution system consisting of three extruders is used to handle fines. Water is added to the fines from the Granular Processing Systems and passed through the extruders. The extrudite is added to the crude clay and sent to the Fluid Bed Dryers.

In the 1A Mill the clay is passed through primary screens to make a 6/60 mesh cut. The oversized material (overs) is passed through roller mills and sent to secondary screens. The overs from the secondary screens are sent to roller mills. The overs from these mills are sent to screening and the roller mill recirculation circuit. The product from this operation is stored in a bin. The fines are pumped back to Fluid Bed reconstitution.

Clay from the product bin is sent to three mesh screens. The product is sent to the #2 Kiln and calcined. The #2 Kiln product is sent to a rotary cooler and, from the cooler, the product is put into a storage bin for bagging or bulk shipment.

Clay from the 6/60 bin can also be sent to the screen tower. The screen tower consists of 18 sifters and storage bins. The sifters are set up to make various size products. Screen tower products can be shipped as product or calcined. The output of the #1 Kiln goes to a rotary cooler. From the #1 Cooler the product goes to bins for bagging or bulk shipment.

The Granular Shipping area has a packer, pelletizer and stretch wrap machine associated with its operation. This allows granular product to be shipped in bags, bulk trucks and bulk railcars.

Gel Processing

A front end loader feeds clay to a feed system for four extruders. A screw feeder may be used to add magnesium oxide to the extruder feed. The clay then goes to one of three dryer mills to be dried and sized. The clay is recovered from the air stream by a cyclone collector. From the Mills, the clay is pumped pneumatically to the Gel Shipping Areas or bulk loaded for shipment. The shipping area includes a pelletizer, packers and stretch wrap machines.

Fine Grind

Some of the clay from the Gel Mills is sent to either Fine Grind for ACM Milling or Ultra Fine Grind for additional processing. In Fine Grind the clay is sent to a pulverizer mill where the clay is ground. The clay form the mill is sent to a classifier to make the final products. The products can then be loaded bulk or bagged on one of the packers.

In ACM Milling, the clay is sent to a pulverizer mill where the clay is ground. The clay from the mill is sent to classifier to make the final product cuts. The products can then be loaded in bulk or bagged for shipment.

In Ultra Fine Grind, clay is fed to two jet mills where the clay is ground. The clay from the mill is sent to a classifier to make the final product cuts. The products can then be loaded in bulk or bagged for shipment.

The facility includes emissions units subject to NSPS (40 CFR 60 subpart OOO) as a result of the date of construction of the affected equipment. These emissions units have particulate emissions controlled by baghouses and include the Gel Clay Production Equipment, Granular Clay Production Equipment, and the ACM Milling/Ultra Fine Grind Equipment. The permit limits are comparable or more stringent then those required by NSPS and include 5% opacity limits.

The clay mining areas are not contiguous with the process plant areas, and are not included in this Title V Facility permit.

The facility is subject to a facility-wide limit of 124 tons per year of NOx associated with a BACT determination for the construction of the north and south fluid bed dryers (Construction Permits AC20-41424 and AC20-41425 issued August 4, 1981).

Since this BASF facility has a potential-to-emit of greater than 250 tons per year of PM (297 tons/yr), the facility is a major source under Prevention of Significant Deterioration (PSD) and any future modifications and/or construction must be evaluated with respect to the preconstruction review requirements of Chapter 62-212, F.A.C.

Also included in this permit are miscellaneous unregulated/insignificant emissions units and/or activities.

Based on the Title V Air Operation Permit Revision application received March 18, 2011, this facility is not a major source of hazardous air pollutants (HAP).

Subsection B. Summary of Emissions Unit ID No(s). and Brief Description(s).

E.U. ID No.	Brief Description
	Gel Clay Production Equipment not subject to NSPS (Baghouses)
017	Mini-U-Gel Truck Loading and Bagging
021	Coarse Gel West Bagging
022	East Product Storage Bin
023	West Product Storage Bin
024	Miscellaneous Product Storage Bin
025	Fine Gel Mill Product Collector
026	Fine Gel Classifier System
	Gel Clay Production Equipment subject to NSPS (Baghouses)
013	Fine Grinding
016	Extrusion Reagent Process
018	#4 Mill Material Handling
020	East Bagging and Fugitive Dust
027	Loadout East Bagging
028	Classifier Product Bagging
	Granular Clay Production Equipment subject to NSPS (Baghouses)
011	#1 Milling Area
031	Fluid Bed Dryer Material Handling
032	Reconstitution Area
033	#1A Mill System
035	Finishing Area
036	Granular Packaging Area
	Granular Clay Production Equipment not subject to NSPS (Baghouses)
029	North Fluid Bed Dryer
030	South Fluid Bed Dryer
	Granular Clay Production Equipment not subject to NSPS (Scrubbers)
014	High Temperature Drying Kiln No. 1
015	High Temperature Drying Kiln No. 2
	Gel Clay Fired Equipment not subject to NSPS (Scrubbers)
002	Mill #4A Scrubber
008	Mill #4 Scrubber
019	Mill #4B Scrubber
	ACM Milling Equipment subject to NSPS (Baghouses)
038	ACM Feed Bin
038	Return Conveyer Exhaust
038	ACM Mill Receiver Collector
038	#1 Classifier Feed Bin
038	Product Bin 400
038	Product Bin 405
038	Product Bin 410
038	Product Bin 600
038	Product Bin 700
038	Bulk Loadout Exhaust-Truck
038	Bulk Loadout Exhaust-Rail
038	Bagger Exhaust
038	Product Storage Bin and Loading Spout
038	Receiver Bin Vent
	Ultra Fine Grind Equipment subject to NSPS (Baghouses)
039	Receiver Bin Vent
039	ACM Mill #1 Receiver Collector
039	ACM Mill #2 Receiver Collector
039	#2 Classifier Feed Vent

Unregulated Emissions Units and/or Activities

E.U. ID No.	Brief Description
041	Fugitive Emissions

Please reference the Permit No., Facility ID No., and appropriate Emissions Unit(s) ID No(s). on all correspondence, test report submittals, applications, etc.

Subsection C. Relevant Documents.

The documents listed below are not a part of this permit; however, they are specifically related to this permitting action.

These documents are provided to the permittee for information purposes only:
Appendix A-1: Abbreviations, Acronyms, Citations, and Identification Numbers
Statement of Basis

These documents are on file with the permitting authority:
Initial Title V Air Operation Permit issued March 16, 1999
Appendix H-1: Permit History
Application for a Title V Air Operation Permit Revision received March 18, 2011

Section II. Facility-wide Conditions.

The following conditions apply facility-wide:

1. APPENDIX TV-6, TITLE V CONDITIONS, is a part of this permit.

2. General Pollutant Emission Limiting Standards. Objectionable Odor Prohibited. No person shall cause, suffer, allow, or permit the discharge of air pollutants which cause or contribute to an objectionable odor. [Rule 62-296.320(2), F.A.C.; permit 0390005- 015-AC]

3. General Particulate Emission Limiting Standards. General Visible Emissions Standard. Except for emissions units that are subject to a particulate matter or opacity limit set forth or established by rule and reflected by conditions in this permit, no person shall cause, let, permit, suffer or allow to be discharged into the atmosphere the emissions of air pollutants from any activity, the density of which is equal to or greater than that designated as Number 1 on the Ringelmann Chart (20 percent opacity). EPA Method 9 is the method of compliance pursuant to Chapter 62-297, F.A.C. [Rules 62-296.320(4)(b)1. & 4., F.A.C.]

4. Prevention of Accidental Releases (Section 112(r) of CAA).
a. The permittee shall submit its Risk Management Plan (RMP) to the Chemical Emergency Preparedness and Prevention Office (CEPPO) RMP Reporting Center when, and if, such requirement becomes applicable. Any Risk Management Plans, original submittals, revisions or updates to submittals, should be sent to:

RMP Reporting Center
Post Office Box 10162
Fairfax, VA 22038
Telephone: 703/227-7650

and,
b. The permittee shall submit to the permitting authority Title V certification forms or a compliance schedule in accordance with Rule 62-213.440(2), F.A.C.
[40 CFR 68]

5. Unregulated Emissions Units and/or Activities. Appendix U-1, List of Unregulated Emissions Units and/or Activities, is a part of this permit. [Rule 62-213.440(1), F.A.C.]

6. Insignificant Emissions Units and/or Activities. Appendix I-1, List of Insignificant Emissions Units and/or Activities, is a part of this permit. [Rules 62-213.440(1), 62-213.430(6) and 62-4.040(1)(b), F.A.C.]

7. General Pollutant Emission Limiting Standards. Volatile Organic Compounds (VOC) Emissions or Organic Solvents (OS) Emissions. The permittee shall allow no person to store, pump, handle, process, load, unload or use in any process or installation, volatile organic compounds (VOC) or organic solvents (OS) without applying known and existing vapor emission control devices or systems deemed necessary and ordered by the Department.

"Nothing was deemed necessary and ordered at this time."

[Rule 62-296.320(1), F.A.C.; permit 0390005- 015-AC]

8. Emissions of Unconfined Particulate Matter. No person shall cause, let, permit, suffer or allow the emissions of unconfined particulate matter from any activity, including vehicular movement; transportation of materials; construction, alteration, demolition or wrecking; or industrially related activities such as loading, unloading, storing or handling; without taking

reasonable precautions to prevent such emissions. Reasonable precautions to prevent emissions of unconfined (fugitive) particulate matter at this facility include (see Condition 57 of APPENDIX TV-6, TITLE V CONDITIONS):

a. Paving and maintenance of roads, parking areas, and yards.
b. Application of water or other dust suppressants to unpaved roads, yards, open stock piles and similar activities.
c. Removal of particulate matter from roads and other paved areas under the control of the owner or operator of the facility to prevent reentrainment, and from buildings or work areas to prevent particulate from becoming airborne.
d. Landscaping or planting of vegetation.
e. Repair rotary feeder leaks, dust piping holes, general equipment leaks immediately upon detection.
f. Vacuum sweep regularly.
g. Minimize dust generation during bag stacking by using improved work procedures.
h. Use extreme caution and carefulness while changing out dust collector bags.
i. Utilize control equipment as necessary during loadout of open trucks.
j. Control belt speeds to minimize transfer points emissions, use regular maintenance of dust pick up points.
k. Confining abrasive blasting wherever possible.

[Rule 62-296.320(4)(c)., F.A.C.; permit 0390005- 015-AC]

9. When appropriate, any recording, monitoring, or reporting requirements that are time-specific shall be in accordance with the effective date of the permit, which defines day one. [Rule 62-213.440, F.A.C.]

10. Emissions of Nitrogen Dioxide. Facility-wide nitrogen dioxide emissions are limited to 124 tons per year.
[Title V Operation Permit 0390005-014-AV; construction permits AC20-41424 and 41425]

11. Statement of Compliance. The annual statement of compliance pursuant to Rule 62-213.440(3)(a)2., F.A.C., shall be submitted to the Department and EPA within 60 days after the end of the calendar year using DEP Form No. 62-213.900(7), F.A.C. [Rules 62-213.440(3) and 62-213.900, F.A.C.]

{Permitting Note: This condition implements the requirements of Rules 62-213.440(3)(a)2. & 3., F.A.C. (see Condition 51 of APPENDIX TV-6, TITLE V CONDITIONS)}

12. The permittee shall submit all compliance related notifications and reports required of this permit to the Department's Northwest District office.

Department of Environmental Protection
Northwest District Office
160 W. Government Street, Suite 308
Pensacola, FL 32502-5740
Telephone: 850/595-8300; Fax: 850/595-8096

13. Any reports, data, notifications, certifications, and requests required to be sent to the United States Environmental Protection Agency, Region 4, should be sent to:

United States Environmental Protection Agency
Region 4
Air, Pesticides & Toxics Management Division
Air and EPCRA Enforcement Branch

Air Enforcement Section
61 Forsyth Street
Atlanta, Georgia 30303-8960
Telephone: 404/562-9155; Fax: 404/562-9163

14. Certification by Responsible Official (RO). In addition to the professional engineering certification required for applications by Rule 62-4.050(3), F.A.C., any application form, report, compliance statement, compliance plan and compliance schedule submitted pursuant to Chapter 62-213, F.A.C., shall contain a certification signed by a responsible official that, based on information and belief formed after reasonable inquiry, the statements and information in the document are true, accurate, and complete. Any responsible official who fails to submit any required information or who has submitted incorrect information shall, upon becoming aware of such failure or incorrect submittal, promptly submit such supplementary information or correct information. [Rule 62-213.420(4), F.A.C.]

Section III. Emissions Unit(s) and Conditions.

Subsection A. This section addresses the following emissions units.

E.U. ID No.	Brief Description
	Gel Clay Production Equipment not subject to NSPS (Baghouses)
017	Mini-U-Gel Truck Loading and Bagging
021	Coarse Gel West Bagging
022	East Product Storage Bin
023	West Product Storage Bin
024	Miscellaneous Product Storage Bin
025	Fine Gel Mill Product Collector
026	Fine Gel Classifier System

This revision incorporates permit 0390005-015-AC that allowed modifications to Emissions Units 022, 023 and 024 that included the installation of a new Cyclonaire Pneumatic Transporter, modifying the existing pneumatic transporters, Con 100 and Con 500 plus additional modifications. These pneumatic transporters and the rotary valve have no specific requirements under 40 CFR 60 subpart OOO and their installation will not result in an overall emissions increase. The plant also proposed to recycle waste tailings back to the final product through EU 024 and will install a larger rotary valve at the bin discharge.

Emission limits include 5% opacity (original BACT) and 0.017 gpdscf (applicant's request, used as supporting information in original construction permit applications).

All other regulated emissions units include gel attapulgite clay production equipment constructed prior to August 31, 1983 and are not subject to NSPS (Subpart OOO, 40 CFR 60). These emissions units are subject to BACT.

The equipment includes conveyors, classifiers, storage bins, bag packers and emissions from miscellaneous fugitive sources. This equipment is identified in Appendix Equipment Requirements, Identification of Applicable Requirements by Equipment.

Emissions are controlled by dust collectors, identified as follows:

E.U. ID No.	Description	Baghouse
017	Min-U-Gel Truck Loading/Bagging	Seneca 100-IM-8 with 100 polyethylene bags
021	Coarse Gel West Bagging	Flex-Kleen 84-CTBS-74-III with 74 polyethylene bags
022	East Product Storage Bin	Flex-Kleen 84-BVBS-36 with 36 polyethylene bags
023	West Product Storage Bin	Flex-Kleen 84-BVBS-36 with 36 polyethylene bags
024	Miscellaneous Product Storage Bin	Flex-Kleen 84-BVBS-36 with 36 polyethylene bags
025	Fine Gel Mill Product Collector	Mikro-Pulsaire 289S-8-40 with 289 polyethylene bags
026	Fine Gel Classifier System	Mikro-Pulsaire 81S-20 with 81 polyethylene bags

Emission limits include 5% opacity (original BACT) and 0.017 gdscf (applicant's request, used as supporting information in original construction permit.

The following specific conditions apply to the emissions units listed above:

Essential Potential to Emit (PTE) Parameters

A.1. Capacity. The maximum process throughput rate shall not exceed the following:

E.U. ID No.	Description	Operation rate TPH	TPY
017	Min-U-Gel Truck Loading and Bagging	35	306,600
021	Coarse Gel West Bagging	18	157,680
022	East Product Storage Bin	25	219,000
023	West Product Storage Bin	25	219,000
024	Miscellaneous Product Storage Bin	10	87,600
025	Fine Gel Mill Product Collector	8	70,080
026	Fine Gel Classifier System	3	26,280

[Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.; Title V Operation Permit 0390005-002-AV and permit 0390005-015-AC]

A.2. Hours of Operation. These emissions units are allowed to operate continuously, i.e., 8760 hours/year. [Rule 62-213.410, F.A.C.; Title V Operation Permit 0390005-002-AV]

Emission Limitations and Standards

A.3. Visible Emissions: Visible emissions (VE) shall not exceed 5% opacity. [Rule 62-297.620(4), F.A.C., Title V Operation Permit 0390005-002-AV]

A.4. Particulate Matter**:** Particulate matter (PM) shall not exceed the following:

E.U. ID No.	Description	Particulate Matter Limits gpdscf	lbs/hr	TPY
017	Min-U-Gel Truck Loading and Bagging	0.017	0.5	2.2
021	Coarse Gel West Bagging	0.017	0.5	1.9
022	East Product Storage Bin	0.017	0.2	0.9
023	West Product Storage Bin	0.017	0.2	0.9
024	Miscellaneous Product Storage Bin	0.017	0.2	0.9
025	Fine Gel Mill Product Collector	0.017	1.7	7.3
026	Fine Gel Classifier System	0.017	0.5	2.2
	TOTAL:		3.8	16.3

[Title V Operation Permit 0390005-002-AV]

Test Methods and Procedures

A.5. Initial Compliance Tests: Emissions Units 022, 023 and 024 shall be tested to demonstrate initial compliance with the emissions standards for PM and VE. The initial tests shall be conducted within 60 days after achieving permitted capacity, but not later than 180 days after initial operation of the unit. [Rules 62-4.070(3), 62-297.401(c) and 62-297.310(7)(a)1, F.A.C., permit 0390005-015-AC]

A.5. PM, VE: The permittee shall conduct visible emissions tests on each emissions unit. The test method shall be EPA Method 9, incorporated and adopted by reference in Rule 62-297, F.A.C., and the test duration is 30 minutes. Such tests shall be scheduled and performed within the last 12 months prior to the renewal application due date. [Rules 62-297.401(c), and 62-297.310, F.A.C.; Title V Operation Permit 0390005-002-AV; permit 0390005-015-AC]

A.6. PM: Rule 62-297.620(4), F.A.C., allows the waiver of particulate matter compliance test requirements for an emissions unit which has the potential to emit less than 100 tons per year of particulate matter and is equipped with a baghouse. If the Department has reason to believe that the particulate weight emission standard applicable to such emissions unit is not being met, it shall require that compliance be demonstrated by the applicable test method. Compliance with the particulate matter emission limit may be demonstrated by compliance with the alternative opacity standard of 5%. In the event any emissions unit does not satisfactorily demonstrate compliance with the alternative VE opacity standard, each such emissions unit shall demonstrate compliance with the PM standard by EPA Method 5 within 90 days of the visible emissions test date. [Rules 62-4.070(3) and 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-002-AV]

Monitoring of Operations and Recordkeeping

A.7. The permittee shall maintain a record of baghouse pressure differentials, recording the pressure drops at least at each shift change or every eight hours, whichever is more frequent. [Rule 62-4.070(3), F.A.C.; Title V Operation Permit 0390005-002-AV]

{Permit Note: The baghouse pressure differential should be within the normal operational range of 0.5" to 5" WG. If the pressure differential is observed outside of the normal operation parameters, appropriate corrective action should be taken immediately.}

A.8. These emissions units are also subject to Common Conditions **H.1** (Test Methods and Procedures), **H.2** (Monitoring of Operations), and **H.3** (Excess Emissions).
[Title V Operation Permit 0390005-002-AV]

Section III. Emissions Unit(s) and Conditions.

Subsection B. This section addresses the following emissions units.

E.U. ID No.	Brief Description
	Gel Clay Production Equipment subject to NSPS (Baghouses)
013	Fine Grinding
016	Extrusion Reagent Process
018	#4 Mill Material Handling
020	East Bagging and Fugitive Dust
027	Loadout East Bagging (Inactive)
028	Classifier Product Bagging System

These are regulated emissions units that include gel attapulgite clay production equipment modified after August 31, 1983 and subject to NSPS (Subpart OOO, 40 CFR 60). These emissions units are subject to BACT. The equipment includes conveyors, classifiers, storage bins, bag packers, and emissions from miscellaneous fugitive sources. This equipment is identified in Appendix Equipment Requirements, Identification of Applicable Requirements by Equipment.

Emissions are controlled by dust collectors, identified as follows:

E.U. ID No.	Description	Baghouse
013	Fine Grinding	Flex-Kleen 100-WMWC-525-III with 525 polyethylene bags
016	Extrusion Reagent Process	Flex-Kleen 100-WRW-80-III with 80 polyethylene bags
018	#4 Mill Material Handling	Flex-Kleen 100-WMWC-600-III with 600 polyethylene bags
020	East Bagging and Fugitive Dust	Flex-Kleen 84-CTB-74-III with 74 polyethylene bags
027	Loadout East Bagging	Two Flex-Kleen 84-WRS-48 with 48 polyethylene bags (common stack)
028	Classifier Product Bagging	Flex-Kleen 100-WMW-360 with 360 polyethylene bags

Emission limits include 5% opacity (original BACT, more stringent than NSPS standard of 7% opacity) and 0.05 grams per dry standard cubic meter. Emissions unit 013 includes a PM limit of 1.1 lbs/hr PM and 4.4 TPY PM based on limits included in permit AC20-31307 dated November 17, 1980, which is more stringent than the NSPS standard of 0.05 grams/dscm (0.022gr/dscf).

These emissions units are subject to the requirements of 40CFR60 subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants applicable to each crusher, screening operation, bucket elevator, belt conveyor, bagging operation, storage bin, enclosed truck or railcar loading station. In general, the applicable standards for particulate matter are 0.022 gr/dscf and 7% opacity for affected facilities [40 CFR 60.672(a)]. Operations enclosed in a building are subject to the requirements in 40 CFR 60.672(e) of no visible fugitive emissions from the building and 0.022 gr/dscf and 7% opacity for any building vents. The facility has requested the alternate VE standard of 5% opacity in accordance with Rule 62-297.620(4), F.A.C., to demonstrate compliance with the PM limit, more stringent than the limits in 40 CFR 60.672.

The following specific conditions apply to the emissions units listed above:

Essential Potential to Emit (PTE) Parameters

B.1. Capacity. The maximum process throughput rate shall not exceed the following:

EU ID No.	Description	Operation rate TPH	TPY
013	Fine Grinding	12	105,120
016	Extrusion Reagent Process	33	289,080
018	#4 Mill Material Handling	33	289,080
020	East Bagging and Fugitive Dust	25	219,000
027	Loadout East Bagging	5	43,800
028	Classifier Product Bagging System	12	105,120

[Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.; Title V Operation Permit 0390005-002-AV]

B.2. Hours of Operation. These emissions units are allowed to operate continuously, i.e., 8,760 hours/year. [Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.]

Emission Limitations and Standards

B.3. Visible Emissions: Visible emissions shall not exceed 5% opacity. [Rule 62-297.620(4), F.A.C.]

B.4. Particulate Matter: Particulate matter shall not exceed the following:
(1) The permittee shall not cause to be discharged into the atmosphere from any transfer point on belt conveyors or from any other affected facility any stack emissions which:
(a) Contain particulate matter in excess of 0.05 g/dscm (0.022 gr/dscf); and
(b) Exhibit greater than 5 percent opacity.
{Permit Note: The 7% opacity limitation contained in 40 CFR 60.672 is replaced with a 5% opacity limitation at the permittee's request in accordance with Rule 62-297.620(4) as an alternate PM compliance standard.}

(2) Each emission point enclosed in a building shall comply with the emission limits in paragraph (1) above, or the building shall comply with the following emission limits:

No owner or operator shall cause to be discharged into the atmosphere from any building enclosing any transfer point on a conveyor belt or any other affected facility any visible fugitive emissions except emissions from a vent as defined in 40 CFR 60.671. No owner or operator shall cause to be discharged into the atmosphere from any vent of any building enclosing any transfer point on a conveyor belt or any other affected facility emissions that exceed the stack emissions limits in paragraph (1) of this condition.

The following emission points are subject to the particulate matter standards identified below:

EU ID No.	Description		Particulate Matter Limits gpdscf	lbs/hr	TPY
013	Fine Grinding		0.022	1.1	4.4
016	Extrusion Reagent Process		0.022	0.7	3.1
018	#4 Mill Material Handling		0.022	3.9	17.1
020	East Bagging and Fugitive Dust		0.022	0.7	2.8
027	Loadout East Bagging		0.022	0.4	1.4
028	Classifier Product Bagging System		0.022	2.4	9.9
		TOTAL:		9.2	38.7

[BACT, 40CFR60.672; Rule 62-204.800(8)(b)66. F.A.C.; Title V Operation Permit 0390005-002-AV]

Test Methods and Procedures

B.5. PM, VE: The permittee shall conduct annual visible emissions tests on each emission point once during each federal fiscal year (October 1 through September 30) and generally at 12-month intervals. The test method shall be EPA Method 9, incorporated and adopted by reference in Rule 62-297, F.A.C. and the test duration is 30 minutes.

In addition, to demonstrate compliance with specific condition **B.4(1)(b)**, the owner or operator shall conduct EPA Method 22 performance tests for fugitive emissions on each building enclosing the referenced emission points twice during the lifetime of this permit and generally at 24-month intervals. The performance test shall be conducted while all affected emission points inside the building are operating. The performance test for each building shall be at least 75 minutes in duration, with each side of the building and the roof being observed for at least 15 minutes.
[Rules 62-297.401(9) and (22), 62-297.310, and 62-204.800(8)(b)66, F.A.C.; Title V Operation Permit 0390005-002-AV; 40 CFR 60.675(d)]

B.6. PM: Rule 62-297.620(4), F.A.C., allows the waiver of particulate matter compliance test requirements for an emissions unit which has the potential to emit less than 100 tons per year of particulate matter and is equipped with a baghouse. If the Department has reason to believe that the particulate weight emission standard applicable to such emissions unit is not being met, it shall require that compliance be demonstrated by the applicable test method. Compliance with the particulate matter emission limit may be demonstrated by compliance with the alternative opacity standard of 5%. In the event any emissions unit does not satisfactorily demonstrate compliance, with the alternative VE opacity standard, each such emissions unit shall demonstrate compliance with the PM standard by EPA Method 5 within 90 days of the visible emissions test date. [Rules 62-4.070(3) and 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-002-AV]

Monitoring of Operations and Recordkeeping

B.7. The permittee shall maintain a record of baghouse pressure differentials, recording the pressure drops at least at each shift change or every eight hours, whichever is more frequent. [Rule 62-4.070(3), F.A.C.; Title V Operation Permit 0390005-002-AV]

{Permit Note: The baghouse pressure differential should be within the normal operational range of 0.5" to 5" WG. If the pressure differential is observed outside of the normal operation parameters, appropriate corrective action should be taken immediately.}

B.8. These emissions units are also subject to Common Conditions **H.1** (Test Methods and Procedures), **H.2** (Monitoring of Operations), **I.1** (40 CFR 60, Subpart A - General Provisions Requirements) and **I.2** (40 CFR 60 Subpart OOO Standards of Performance for Nonmetallic Mineral Processing Plants). [Title V Operation Permit 0390005-002-AV]

Section III. Emissions Units and Conditions.

Subsection C. This section addresses the following emissions units.

E.U. ID No.	Brief Description
	Granular Clay Production Equipment subject to NSPS (Baghouses)
011	#1 Milling Area
031	Fluid Bed Dryer Material Handling
032	Reconstitution Area
033	#1A Mill System
035	Finishing Area
036	Granular Packaging Area

These are regulated emissions units that include granular clay production equipment modified after August 31, 1983, and subject to NSPS (Subpart OOO, 40 CFR 60). These emissions units are subject to BACT.

The equipment includes conveyors, classifiers, storage bins, bag packers, and emissions from miscellaneous fugitive sources. This equipment is identified in Appendix Equipment Requirements, Identification of Applicable Requirements by Equipment.

Emissions are controlled by dust collectors, identified as follows:

EU	Description	Baghouse
011	#1 Milling Area	Micro Pulsaire 1-FS-24 with 240 polyethylene bags
031	Fluid Bed Dryer Material Handling	Flex-Kleen 100-WMW-180 with 180 polyethylene bags
032	Reconstitution Area	Flex-Kleen 100-WMWC-120 with 120 polyethylene bags
033	#1A Mill System	Flex-Kleen 84-CTB-74-III with 74 polyethylene bags
035	Finishing Area	Flex-Kleen 100-WMW-540 with 540 polyethylene bags
036	Granular Packaging Area	Flex-Kleen 100-WMW-300 with 300 polyethylene bags

Emission limits include 5% opacity (original BACT, more stringent than NSPS standard of 7% opacity) and 0.05 grams per dry standard cubic meter. Emissions unit 032 includes a PM limit of 1.0 lbs/hr PM and 4.4 TPY PM based on limits included in permit AC20-41427 dated August 4, 1981; 033, 4.0 lbs/hr PM and 17.6 TPY PM based on AC20-41428 dated August 4, 1981; 035, 2.4 lbs/hr and 10.6 TPY based on AC20-41430 dated August 4, 1981; and 036, 1.0 lbs/hr PM and 4.4 TPY PM based on AC20-41431 dated August 4, 1981. The construction permit limits are all more stringent than 0.05 grams/dscm (0.022 gr/dscf).

These emissions units are subject to the requirements of 40 CFR 60 subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants applicable to each crusher, screening operation, bucket elevator, belt conveyor, bagging operation, storage bin, enclosed truck or railcar loading station. In general, the applicable standards for particulate matter are 0.022 gr/dscf and 7% opacity for affected facilities [40 CFR 60.672(a)]. Operations enclosed in a building are subject to the requirements in 40 CFR 60.672(e) of no visible fugitive emissions from the building and 0.022 gr/dscf and 7% opacity for any building vents. The facility has requested the alternate VE standard of 5% opacity in accordance with Rule 62-297.620(4),

F.A.C., to demonstrate compliance with the PM limit, more stringent than the limits in 40 CFR 60.672.

The following specific conditions apply to the emissions units listed above:

Essential Potential to Emit (PTE) Parameters

C.1. Capacity. The maximum process throughput rate shall not exceed the following:

EU ID No.	Description	Operation rate TPH	TPY
011	#1 Milling Area	14	80,360
031	Fluid Bed Dryer Material Handling	68	595,680
032	Reconstitution Area	52	455,520
033	#1A Mill System	66	378,840
035	Finishing Area	65	569,400
036	Granular Packaging Area	45	394,200

[Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.; Title V Operation Permit 0390005-002-AV]

C.2. Hours of Operation. These emissions units are allowed to operate continuously, i.e., 8,760 hours/year. However, emissions unit ID No. 011, the #1 Milling Area, is limited to 5,740 hours of operation. The permittee shall maintain records of operation of the #1 Milling Area.
[Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.; Title V Operation Permit 0390005-002-AV]

Emission Limitations and Standards

C.3. Visible Emissions: Visible emissions shall not exceed 5% opacity. [Rule 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-002-AV]

C.4. Particulate Matter: Particulate matter shall not exceed the following:
(1) The permittee shall not cause to be discharged into the atmosphere from any transfer point on belt conveyors or from any other affected facility any stack emissions which:
(a) Contain particulate matter in excess of 0.05 g/dscm (0.022 gr/dscf); and,
(b) Exhibit greater than 5% opacity.

{Permit Note: The 7% opacity limitation contained in 40 CFR 60.672 is replaced with a 5% opacity limitation at the permittee's request in accordance with Rule 62-297.620(4) as an alternate PM compliance standard.}

(2) Each emission point enclosed in a building shall comply with the emission limits in paragraphs (1) above, or the building shall comply with the following emission limits:

No owner or operator shall cause to be discharged into the atmosphere from any building enclosing any transfer point on a conveyor belt or any other affected facility any visible fugitive emissions except emissions from a vent as defined in 40 CFR 60.671. No owner or operator shall cause to be discharged into the atmosphere from any vent of any building enclosing any transfer point on a conveyor belt or any other affected facility emissions that exceed the stack emissions limits in paragraph (1) of this condition.

The following emission points are subject to the particulate matter standards identified below:

EU ID No.	Description	Particulate Matter Limits gpdscf	lbs/hr	TPY
011	#1 Milling Area	0.022	2.6	7.5
031	Fluid Bed Dryer Material Handling	0.022	0.7	2.8
032	Reconstitution Area	0.022	1.0	4.4
033	#1 A Mill System	0.022	4.0	17.6
035	Finishing Area	0.022	2.4	10.6
036	Granular Packaging Area	0.022	1.0	4.4
	TOTAL:		11.7	47.3

[BACT, 40CFR60.672; Rule 62-204.800(8)(b)66, F.A.C.; Title V Operation Permit 0390005-002-AV]

Test Methods and Procedures

C.5. PM, VE: The permittee shall conduct annual visible emissions tests on each emission point once during each federal fiscal year (October 1 through September 30) and generally at 12-month intervals. The test method shall be EPA Method 9, incorporated and adopted by reference in Rule 62-297, F.A.C. and the test duration is 30 minutes.

In addition, to demonstrate compliance with specific condition **C.4(1)(b)**, the owner or operator shall conduct EPA Method 22 performance tests for fugitive emissions on each building enclosing the referenced emission points twice during the lifetime of this permit and generally at 24-month intervals. The performance test shall be conducted while all affected emission points inside the building are operating. The performance test for each building shall be at least 75 minutes in duration, with each side of the building and the roof being observed for at least 15 minutes.
[Rules 62-4.070(3), 62-297.401 and 62-204.800(8)(b)66, F.A.C.; Title V Operation Permit 0390005-002-AV; 40 CFR 60.675(d)]

C.6. PM: Rule 62-297.620(4), F.A.C., allows the waiver of particulate matter compliance test requirements for an emissions unit which has the potential to emit less than 100 tons per year of particulate matter and is equipped with a baghouse. If the Department has reason to believe that the particulate weight emission standard applicable to such emissions unit is not being met, it shall require that compliance be demonstrated by the applicable test method. Compliance with the particulate matter emission limit may be demonstrated by compliance with the alternative opacity standard of 5%. In the event any emissions unit does not satisfactorily demonstrate compliance, with the alternative VE opacity standard, each such emissions unit shall demonstrate compliance with the PM standard by EPA Method 5 within 90 days of the visible emissions test date. [Rule 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-002-AV]

C.7. The permittee shall maintain a record of baghouse pressure differentials, recording the pressure drops at least at each shift change or every eight hours, whichever is more frequent. [Rule 62-4.070(3), F.A.C.; Title V Operation Permit 0390005-002-AV]

{Permit Note: The baghouse pressure differential should be within the normal operational range of 0.5" to 5" WG. If the pressure differential is observed outside of the normal operation parameters, appropriate corrective action should be taken immediately.}

C.8. These emissions units are also subject to Common Conditions **H.1** (Test Methods and Procedures), **H.2** (Monitoring of Operations), **I.1** (40 CFR 60, Subpart A - General Provisions Requirements) and **I.2** (40 CFR 60. Subpart OOO Standards of Performance for Nonmetallic Mineral Processing Plants). [Title V Operation Permit 0390005-002-AV]

Section III. Emissions Units and Conditions.

Subsection D. This section addresses the following emissions units.

E.U. ID No.	Brief Description
	Granular Clay Fired Equipment not subject to NSPS (Baghouses)
029	Fluid Bed Dryer – North (Inactive)
030	Fluid Bed Dryer – South

These are regulated emissions units consisting of natural gas or propane-fired equipment utilized for the production of granular attapulgite clay products constructed prior to August 31, 1983, and not subject to NSPS (40 CFR 60 Subpart OOO). These emissions units are subject to BACT, and to Compliance Assurance Monitoring (CAM) requirements. Additionally, these emissions units have accepted a NOx emissions limit to avoid PSD review.

The equipment includes collector screws, dryers, burners, and product coolers with emissions controlled by a product dust collector and dual cyclones, followed by twin baghouses. The equipment is identified in Appendix Equipment Requirements, Identification of Applicable Requirements by Equipment.

The emission control equipment is identified as follows:

EU ID No.	Description	Baghouse
029	Fluid Bed Dryer - North	Dust collector and product cyclone followed by dual baghouses consisting of Flex-Kleen 120 WMW 960 with Nomex bags.
030	Fluid Bed Dryer -South	Dust collector and product cyclone followed by dual baghouses consisting of Flex-Kleen 120 WMW 960 with Nomex bags

Emission limits include 5% opacity (original BACT) and limits included in original construction permits. Construction permit AC20-41424, issued August 4, 1981, for the North Fluid Bed Dryer included limits of 4.7 lbs/hr PM, and construction permit AC20-41425, issued August 4, 1981, for the South Fluid Bed Dryer included limits of 4.7 lbs/hr PM. Combustion by-products are subject to a facility-wide BACT limiting NOx emissions to 124 TPY.

The following specific conditions apply to the emissions units listed above:

Essential Potential to Emit (PTE) Parameters

D.1. Capacity. The maximum process throughput rate and heat input (for each dryer) shall not exceed the following:

EU ID No.	Description	Operation rate/tons processed TPH	TPY	Heat Input MMBtu/hr
029	Fluid Bed Dryer - North	68	595,680	100
030	Fluid Bed Dryer - South	68	595,680	100
	TOTAL:	136	1,191,360	

[Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.; Title V Operation Permit 0390005-002-AV]

D.2. Hours of Operation. These emissions unit are allowed to operate continuously, i.e., 8,760 hours/year. [Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.]

D.3. Methods of Operation (i.e. Fuels). These emissions units may operate using pipeline quality natural gas or liquid propane. The permittee shall track fuel usage by emissions unit and facility overall. The permittee shall maintain a log available for Department inspection of the fuel usage, and shall maintain vendor certificates documenting the fuel sulfur content. [Rules 62-4.070 and 62-213.440(1), F.A.C., construction permit 0390005-008-AC]

Emission Limitations and Standards

D.4. Visible Emissions: Visible emissions shall not exceed 5% opacity. [Rule 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-012-AV]

D.5. Particulate Matter: Particulate matter shall not exceed the following:

EU ID No.	Description	Particulate Matter Limits lbs/hr	TPY
029	Fluid Bed Dryer - North	4.7	20.6
030	Fluid Bed Dryer - South	4.7	20.6
	TOTAL:	9.4	41.2

[BACT; Permits AC20-41424 and AC20-41425; Title V Operation Permit 0390005-002-AV]

D.6. Nitrogen Dioxide: Nitrogen dioxide emissions are limited by **Facility-Wide Condition No. 9 (Section II)**. [BACT; Permits AC20-41424 and AC20-41425, Title V Operation Permit 0390005-002-AV]

Test Methods and Procedures

D.7. PM, VE: The permittee shall conduct visible emissions tests on each emissions unit. The test method shall be EPA Method 9, incorporated and adopted by reference in Rule 62-297, F.A.C., and the test duration is 30 minutes. Such tests shall be scheduled and performed within the last 12 months prior to the renewal application due date [Rule 62-297.401, F.A.C.; Title V Operation Permit 0390005-002-AV; and permit 0390005-015-AC]

D.8. PM: Rule 62-297.620(4), F.A.C., allows the waiver of particulate matter compliance test requirements for an emissions unit which has the potential to emit less than 100 tons per year of particulate matter and is equipped with a baghouse. If the Department has reason to believe that the particulate weight emission standard applicable to such emissions unit is not being met, it shall require that compliance be demonstrated by the applicable test method. Compliance with the particulate matter emission limit may be demonstrated by compliance with the alternative opacity standard of 5%. In the event any emissions unit does not satisfactorily demonstrate compliance, with the alternative VE opacity standard, each such emissions unit shall demonstrate compliance with the PM standard by EPA Method 5 within 90 days of the visible emissions test date. [Rule 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-002-AV]

D.9. NOx. Compliance with the nitrogen dioxide limit shall be demonstrated by tracking fuel usage by emissions unit and facility overall. Nitrogen dioxide emissions shall be calculated on a quarterly basis using applicable emission factors. However, in the event nitrogen dioxide

emissions exceed 62 tons (50% of annual emission limit) at any time during any calendar year, the permittee shall calculate nitrogen emissions on a monthly basis. In the event nitrogen dioxide emissions exceed 93 tons (75% of annual emission limit) at any time during any calendar year, the permittee shall calculate nitrogen emissions on a weekly basis unless the maximum potential emissions remaining in the calendar year is less than 124 tons. In the event nitrogen dioxide emissions exceed 112 tons (90% of annual emission limit) and the maximum potential emissions remaining in the calendar year exceeds 124 tons, the permittee shall immediately advise the department of those emergency measures to be taken to ensure compliance with the nitrogen dioxide emissions limit. [Title V Operation Permit 0390005-002-AV]

D.10. Emission Unit 029 is in long-term reserve shutdown as of the effective date of this permit. Prior to placing the emission unit back in operation, the permittee shall:

a. Advise the Department within seven days of startup.
b. Conduct tests for visible emissions and particulate matter within 30 days after achieving permitted capacity.

[Rules 62-4.070, F.A.C.]

Compliance Assurance Monitoring (CAM) Requirements

D.11. These emissions units are subject to the CAM requirements contained in the attached Appendix CAM. Failure to adhere to the monitoring requirements specified does not necessarily indicate an exceedance of a specific emissions limitation; however, it may constitute good reason to require compliance testing pursuant to Rule 62-297.310(7)(b), F.A.C. [40 CFR 64; Rules 62-204.800(12) and 62-213.440(1)(b)1.a., F.A.C.]

D.12. These emissions units are also subject to Common Conditions **H.1** (Test Methods and Procedures), **H.2** (Monitoring of Operations), and **H.3** (Excess Emissions). [Title V Operation Permit 0390005-002-AV]

Section III. Emissions Units and Conditions.

Subsection E. This section addresses the following emissions units.

E.U. ID No.	Brief Description
	Granular Clay Fired Equipment not subject to NSPS (Scrubbers)
014	High Temperature Drying Kiln No. 1
015	High Temperature Drying Kiln No. 2

These are regulated emissions units consisting of natural gas or propane-fired kilns utilized for the production of granular attapulgite clay products constructed prior to August 31, 1983, and not subject to NSPS (Subpart OOO, 40 CFR 60). These emissions units are subject to BACT, and to Compliance Assurance Monitoring (CAM) requirements. Additionally, these emissions units have accepted a NOx emissions limit to avoid PSD review.

Emissions are controlled by wet scrubbers. Associated equipment is identified in Appendix Equipment Requirements, Identification of Applicable Requirements by Equipment.

The emission control equipment is identified as follows:

EU ID No.	Description	Controls
014	High Temperature Drying Kiln No. 1	Venturi scrubber
015	High Temperature Drying Kiln No. 2	Venturi scrubber

Emission limits include 5% opacity (original BACT), and PM limits included in supporting information associated with original construction permit applications (0.017 gpdscf). Combustion by-products are subject to a facility-wide BACT limiting NOx emissions to 124 TPY.

The following specific conditions apply to the emissions units listed above:

Essential Potential to Emit (PTE) Parameters

E.1. Capacity. The maximum process throughput rate and heat input shall not exceed the following:

EU ID No.	Description	Operation rate/tons processed TPH	TPY	Heat Input MMBtu/hr
014	High Temperature Drying Kiln No. 1	16 (wet)	140,160	35
015	High Temperature Drying Kiln No. 2	28 (wet)	245,280	50
	TOTAL:	44	385,440	85

[Rules 62-4.160(2) and 62-210.200(PTE), F.A.C., Title V Operation Permit 0390005-002-AV]

E.2. Hours of Operation. These emissions units are allowed to operate continuously, i.e., 8,760 hours/year. [Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.]

E.3. Methods of Operation (i.e. Fuels). These emissions units may operate using pipeline quality natural gas or liquid propane. The permittee shall track fuel usage by emissions unit and facility overall. The permittee shall maintain a log available for Department inspection of the fuel usage, and shall maintain vendor certificates documenting the fuel sulfur content. [Rules 62-4.070 and 62-213.440(1), F.A.C., construction permit 0390005-008-AC]

Emission Limitations and Standards

E.4. Visible Emissions: Visible emissions shall not exceed 5% opacity. [Rule 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-002-AV]

E.5. Particulate Matter: Particulate matter shall not exceed the following:

EU ID No.	Description		Particulate Matter Limits lbs/hr	TPY
014	High Temperature Drying Kiln No. 1		4.2	18.4
015	High Temperature Drying Kiln No. 2		4.4	19.3
		TOTAL:	8.6	37.7

[BACT, Permit AO20-181697; Title V Operation Permit 0390005-002-AV]

E.6. Nitrogen Dioxide: Nitrogen dioxide emissions are limited by Facility-Wide Condition No. 9 (Section II). [BACT; Title V Operation Permit 0390005-002-AV]

Test Methods and Procedures

E.7. PM, VE: The permittee shall conduct visible emissions tests on each emissions unit. The test method shall be EPA Method 9, incorporated and adopted by reference in Rule 62-297, F.A.C., and the test duration is 30 minutes. Such tests shall be scheduled and performed within the last 12 months prior to the renewal application due date. [Rule 62-297.401, F.A.C.; Title V Operation Permit 0390005-002-AV and permit 0390005-015-AC]

E.8. PM: Except as noted below, compliance with the particulate matter emission limit may be demonstrated by compliance with the alternative opacity standard of 5%. In the event any emissions unit does not satisfactorily demonstrate compliance, with the alternative VE opacity standard, each such emissions unit shall demonstrate compliance with the PM standard by EPA Method 5 within 90 days of the visible emissions test date. [Rule 62-297.620(4), F.A.C.]

Each unit shall demonstrate compliance with the particulate matter limits contained in condition **E.5**, in accordance with EPA Method 5 between October 1, 2013, and September 30, 2014. The visible emissions tests required by condition **E.7** shall be conducted during one of the Method 5 test runs. [Rule 62-297.310, F.A.C.; Title V Operation Permit 0390005-002-AV]

E.9. NOx: Compliance with the nitrogen dioxide limit shall be demonstrated by tracking fuel usage by emissions unit and facility overall. Nitrogen dioxide emissions shall be calculated on a quarterly basis using applicable emission factors. However, in the event nitrogen dioxide emissions exceed 62 tons (50% of annual emission limit) at any time during any calendar year, the permittee shall calculate nitrogen emissions on a monthly basis. In the event nitrogen dioxide emissions exceed 93 tons (75% of annual emission limit) at any time during any calendar year, the permittee shall calculate nitrogen emissions on a weekly basis unless the maximum potential

emissions remaining in the calendar year is less than 124 tons. In the event nitrogen dioxide emissions exceed 112 tons (90% of annual emission limit) and the maximum potential emissions remaining in the calendar year exceeds 124 tons, the permittee shall immediately advise the department of those emergency measures to be taken to ensure compliance with the nitrogen dioxide emissions limit. [Title V Operation Permit 0390005-002-AV]

Compliance Assurance Monitoring (CAM) Requirements

E.10. These emissions units are subject to the CAM requirements contained in the attached Appendix CAM. Failure to adhere to the monitoring requirements specified does not necessarily indicate an exceedance of a specific emissions limitation; however, it may constitute good reason to require compliance testing pursuant to Rule 62-297.310(7)(b), F.A.C. [40 CFR 64; Rules 62-204.800(12) and 62-213.440(1)(b)1.a., F.A.C.]

E.11. These emissions units are also subject to Common Conditions **H.1** (Test Methods and Procedures), **H.2** (Monitoring of Operations), and **H.3** (Excess Emissions). [Title V Operation Permit 0390005-002-AV]

Section III. Emissions Units and Conditions.

Subsection F. This section addresses the following emissions units.

E.U. ID No.	Brief Description
	Gelling Clay Fired Equipment not subject to NSPS (Scrubbers)
002	Mill #4A
008	Mill #4
019	Mill #4B

These are regulated emissions units consisting of natural gas or propane-fired hammermills utilized for the production of gel attapulgite clay products constructed prior to August 31, 1983 and not subject to NSPS (Subpart OOO, 40 CFR 60). These emissions units are subject to BACT, and to Compliance Assurance Monitoring (CAM) requirements. Additionally, these emissions units have accepted a NOx emissions limit to avoid PSD review.

Emissions are controlled by wet scrubbers. Associated equipment is identified in Appendix Equipment Requirements, Identification of Applicable Requirements by Equipment.

The emission control equipment is identified as follows:

EU ID No.	Description	Controls
002	Mill #4A	Stansteel venturi-impactor type, high efficiency scrubber model D
008	Mill #4	Stansteel venturi-impactor type, high efficiency scrubber model D
019	Mill #4B	Stansteel venturi-impactor type, high efficiency scrubber model D

Emission limits include 5% opacity (original BACT), and PM limits included in supporting information associated with original construction permit applications. Combustion by-products are subject to a facility-wide BACT limiting NOx emissions to 124 TPY.

The following specific conditions apply to the emissions units listed above:

Essential Potential to Emit (PTE) Parameters

F.1. Capacity. The maximum process throughput rate and heat input shall not exceed the following:

EU ID No.	Description		Operation rate/tons processed TPH	TPY	Heat Input MMBtu/hr
002	Mill #4A		13	113,880	30
008	Mill #4		13	113,880	30
019	Mill #4B		13	113,880	30
		TOTAL:	39	341,640	90

[Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.; Title V Operation Permit 0390005-002-AV]

F.2. Hours of Operation. These emissions unit are allowed to operate continuously, i.e., 8,760 hours/year. [Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.]

F.3. Methods of Operation (i.e. Fuels). These emissions units may operate using pipeline quality natural gas or liquid propane. The permittee shall track fuel usage by emissions unit and facility overall. The permittee shall maintain a log available for Department inspection of the fuel usage, and shall maintain vendor certificates documenting the fuel sulfur content. [Rules 62-4.070 and 62-213.440(1), F.A.C.; construction permit 0390005-008-AC]

Emission Limitations and Standards

F.4. Visible Emissions: Visible emissions shall not exceed 5% opacity. [Rule 62-297.620, F.A.C.]

F.5. Particulate Matter: Particulate matter shall not exceed the following:

EU ID No.	Description	Particulate Matter Limits lbs/hr	TPY
002	Mill #4A	7.0	30.7
008	Mill #4	7.0	30.7
019	Mill #4B	7.0	30.7
	TOTAL:	21.0	92.1

[BACT, Permit AO20-181688; Title V Operation Permit 0390005-002-AV]

F.6. Nitrogen Dioxide: Nitrogen dioxide emissions are limited by Facility-Wide Condition No. 9 (Section II). [BACT; Title V Operation Permit 0390005-002-AV]

Test Methods and Procedures

F.7. PM, VE: To demonstrate compliance with conditions **F.4** and **F.5**, the permittee shall conduct visible emissions tests on each emissions unit. The test method shall be EPA Method 9, incorporated and adopted by reference in Rule 62-297, F.A.C., and the test duration is 30 minutes. Such tests shall be scheduled and performed within the last 12 months prior to the renewal application due date. [Rule 62-297.401, F.A.C.; Title V Operation Permit 0390005-007-AV and permit 0390005-015-AC]

F.8. PM: Except as noted below, compliance with the particulate matter emission limit may be demonstrated by compliance with the alternative opacity standard of 5%. In the event any emissions unit does not satisfactorily demonstrate compliance, with the alternative VE opacity standard, each such emissions unit shall demonstrate compliance with the PM standard by EPA Method 5 within 90 days of the visible emissions test date. [Rule 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-002-AV]

Each unit shall demonstrate compliance with the particulate matter limits contained in condition **F.5**, in accordance with EPA Method 5 between October 1, 2013 and September 30, 2014. The visible emissions tests required by condition **F.7** shall be conducted during one of the Method 5 test runs. [Rule 62-297.310, F.A.C.]

F.9. NOx: Compliance with the nitrogen dioxide limit shall be demonstrated by tracking fuel usage by emissions unit and facility overall. Nitrogen dioxide emissions shall be calculated on a quarterly basis using applicable emission factors. However, in the event nitrogen dioxide

emissions exceed 62 tons (50% of annual emission limit) at any time during any calendar year, the permittee shall calculate nitrogen emissions on a monthly basis. In the event nitrogen dioxide emissions exceed 93 tons (75% of annual emission limit) at any time during any calendar year, the permittee shall calculate nitrogen emissions on a weekly basis unless the maximum potential emissions remaining in the calendar year is less than 124 tons. In the event nitrogen dioxide emissions exceed 112 tons (90% of annual emission limit) and the maximum potential emissions remaining in the calendar year exceeds 124 tons, the permittee shall immediately advise the department of those emergency measures to be taken to ensure compliance with the nitrogen dioxide emissions limit. [Title V Operation Permit 0390005-002-AV]

Compliance Assurance Monitoring (CAM) Requirements

F.10. These emissions units are subject to the CAM requirements contained in the attached Appendix CAM. Failure to adhere to the monitoring requirements specified does not necessarily indicate an exceedance of a specific emissions limitation; however, it may constitute good reason to require compliance testing pursuant to Rule 62-297.310(7)(b), F.A.C. [40 CFR 64; Rules 62-204.800(12) and 62-213.440(1)(b)1.a., F.A.C.]

F.11. These emissions units are also subject to Common Conditions **H.1** (Test Methods and Procedures), **H.2** (Monitoring of Operations) and **H.3** (Excess Emissions).

Section III. Emissions Unit(s) and Conditions.

Subsection G. This section addresses the following emissions units.

E.U. ID No.	Brief Description
	ACM Milling/Ultra Fine Grind with Baghouses – Subject to NSPS
038	ACM Milling
039	Ultra Fine Grind

These are regulated emissions units that include gel attapulgite clay production equipment consisting of conveyors, classifiers, storage bins, bag packers, and emission from miscellaneous fugitive sources constructed after August 31, 1983, and subject to NSPS (Subpart OOO, 40 CFR 60). The equipment includes conveyors, classifiers, storage bins, bag packers and emissions from miscellaneous fugitive sources. Construction permit 0390005-009-AC allowed for an additional gel load spout to facilitate flexibility of loading products produced at the plant into railcars. Construction permit 0390005-011-AC allowed for debottlenecking construction activities in emissions unit 038 and 039 (ACM Milling and Ultra Fine Grind), to allow simultaneous production of different products.

This equipment is identified in Appendix Equipment Requirements, Identification of Applicable Requirements by Equipment (available from the Department upon request).

Emissions are controlled by dust collectors, identified as follows:

EU	Stack	Description	Baghouse
038	37	ACM Feed Bin	Flex-Kleen 100-WSW-81-IIIG with 81 polyethylene bags
038	38	Return Conveyor Exhaust	Flex-Kleen 100-WSW-49-IIIG with 49 polyethylene bags
038	39	ACM Mill Receiver Collector	Flex-Kleen 100-WSW-361-IIIG with 361 polyethylene bags
038	40	#1 Mill Classifier Feed Bin	Flex-Kleen 84-BVBS-36IIG with 36 polyethylene bags
038	41a	Product Bin 400	Flex-Kleen 100-WSW-49-IIG with 49 polyethylene bags
038	41b	Product Bin 405	Flex-Kleen 84-BVBS-9-IIG with 9 polyethylene bags
038	41c	Product Bin 410	Flex-Kleen 84-BVBS-25-IIG with 25 polyethylene bags
038	41d	Product Bin 600	Flex-Kleen 84-BVBS-49-IIG with 49 polyethylene bags
038	41e	Product Bin 700	Flex-Kleen 84-BVBS-25-IIG with 25 polyethylene bags
038	42	Bulk Loadout Exhaust - Truck	Flex-Kleen 84-BVBS-25-IIG with 25 polyethylene bags
038	43	Bulk Loadout Exhaust - Rail	Flex-Kleen 84-BVBS-25-IIG with 25 polyethylene bags
038	44	Receiver Bin Vent	Ultra BW-25-84 with 25 polyethylene bags
038	46	Bagger Exhaust	Ultra RW-192-100 with 192 polyethylene bags
038	54	Product storage bin and loading spout	Flex-Kleen 84-BVBS-25-IIG with 25 polyethylene bags
039	48	Receiver Bin 200 Vent	Flex-Kleen 100-WSWS-64-II with 64 polyethylene bags
039	49	FEM Mill 1 Receiver Collector	Flex-Kleen 84-WSWS-49-III with 49 polyethylene bags
039	50	FEM Mill 2 Receiver Collector	Flex-Kleen 84-WSWS-49-III with 49 polyethylene bags

EU	Stack	Description	Baghouse
039	53	#2 Classifier Feed Vent	Flex-Kleen 84-CTBS-25-IIG with 25 polyethylene bags
039	55	Gel Rail Loadout	Torit 36-PJD-6-reverse jet with 36 polypropylene bags
039	56	Bin 151	Flex-Kleen 84-BVBS-25-IIG with 25 polyethylene bags

Emission limits include 5% opacity from the construction permits (0390005-009 AC issued November 9, 2004, and 0390005-011-AC issued April 19, 2005, both more stringent than NSPS standard of 7% opacity) and 0.05 grams per dry standard cubic meter.

This emissions unit is subject to the requirements of 40 CFR 60 subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants applicable to each crusher, screening operation, bucket elevator, belt conveyor, bagging operation, storage bin, enclosed truck or railcar loading station. In general, the applicable standards for particulate matter are 0.022 gr/dscf and 7% opacity for affected facilities [40 CFR 60.672(a)]. Operations enclosed in a building are subject to the requirements in 40 CFR 60.672(e) of no visible fugitive emissions from the building and 0.022 gr/dscf and 7% opacity for any building vents. The facility has requested the alternate VE standard of 5% opacity in accordance with Rule 62-297.620, F.A.C., to demonstrate compliance with the PM limit.

The following specific conditions apply to the emissions units listed above:

Essential Potential to Emit (PTE) Parameters

G.1. Capacity. The maximum process throughput rate shall not exceed the following:

EU	Point	Description	Operation rate	
			TPH	TPY
038	37	ACM Feed Bin	20	146,000
	38	Return Conveyor Exhaust	20	146,000
	39	ACM Mill Receiver Collector	20	146,000
	40	#1 Mill Classifier Feed Bin	20	160,000
	41a	Product Bin 400	20	80,000
	41b	Product Bin 405	20	120,000
	41c	Product Bin 410	20	120,000
	41d	Product Bin 600	20	80,000
	41e	Product Bin 700	20	80,000
	42	Bulk Loadout Exhaust - Truck	20	20,000
	43	Bulk Loadout Exhaust - Rail	20	20,000
	44	Receiver Bin Vent	20	160,000
	46	Bagger Exhaust	20	80,000
	54	Product Storage Bin & Loading Spout	20	80,000
039	48	Receiver Bin 200 Vent	4.2	33,600
	49	FEM Mill #1 Receiver Collector	4.2	16,800
	50	FEM Mill #2 Receiver Collector	4.2	16,800
	53	#2 Classifier Feed Vent	4.2	16,800
	55	Gel Rail Loadout	20	80,000
	56	Product Bin 151	20	80,000
		TOTAL:	336.8	1,682,000

[Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.; Title V Operation Permit 0390005-002-AV; construction permits 0390005-009-AC and 0390005-011-AC]

G.2. Hours of Operation. These emissions units and points are limited to the following hours of operation:

EU	Point	Description	Allowable hours of operation per year
038	37	ACM Feed Bin	7300
	38	Return Conveyor Exhaust	7300
	39	ACM Mill Receiver Collector	7300
	40	#1 Mill Classifier Feed Bin	8000
	41a	Product Bin 400	4000
	41b	Product Bin 405	6000
	41c	Product Bin 410	6000
	41d	Product Bin 600	3500
	41e	Product Bin 700	4000
	42	Bulk Loadout Exhaust - Truck	1000
	43	Bulk Loadout Exhaust - Rail	1000
	44	Receiver Bin Vent	8000
	46	Bagger Exhaust	4000
	54	Product Storage Bin and Loading Spout	4000
039	48	Receiver Bin 200 Vent	8000
	49	FEM Mill #1 Receiver Collector	4000
	50	FEM Mill #2 Receiver Collector	4000
	53	#2 Classifier Feed Vent	4000
	55	Gel Rail Loadout	4000
	56	Product Bin 151	4000

The permittee shall maintain a log documenting the hours of operation of each emission point. [Rules 62-4.160(2) and 62-210.200(PTE), F.A.C.; Title V Operation Permit 0390005-002-AV; construction permits 0390005-008-AC, 0390005-009-AC and 0390005-011-AC]

Emission Limitations and Standards

G.3. Visible Emissions: Visible emissions shall not exceed 5% opacity. [Rule 62-297.620(4), F.A.C.; Permits 0390005-009-AC and 0390005-011-AC; Title V Operation Permit 0390005-002-AV]

G.4. Particulate Matter: Particulate matter shall not exceed the following:
(1) The permittee shall not cause to be discharged into the atmosphere from any transfer point on belt conveyors or from any other affected facility any stack emissions which:

(a) Contain particulate matter in excess of 0.05 g/dscm (0.022 gr/dscf); and,
(b) Exhibit greater than 5%opacity.

{Permitting Note: The 7% opacity limitation contained in 40 CFR 60.672 is replaced with a 5% opacity limitation at the permittee's request in accordance with Rule 62-297.620(4), F.A.C., as an alternate PM compliance standard.}

(2) Each emission point enclosed in a building shall comply with the emission limits in paragraphs (1) above, or the building shall comply with the following emission limits:
No owner or operator shall cause to be discharged into the atmosphere from any building enclosing any transfer point on a conveyor belt or any other affected facility any visible fugitive

emissions except emissions from a vent as defined in 40 CFR 60.671. No owner or operator shall cause to be discharged into the atmosphere from any vent of any building enclosing any transfer point on a conveyor belt or any other affected facility emissions that exceed the stack emissions limits in paragraph (1) of this condition.

The following emission points are subject to the particulate matter standards identified below:

EU	Point	Description	Particulate Matter Limits	
			lbs/hr	tons/year
038	37	ACM Feed Bin	0.7	2.4
	38	Return Conveyor Exhaust	0.4	1.5
	39	ACM Mill Receiver Collector	2.2	7.9
	40	#1 Mill Classifier Feed Bin	0.3	0.9
	41a	Product Bin 400	0.2	0.4
	41b	Product Bin 405	0.05	0.2
	41c	Product Bin 410	0.2	0.4
	41d	Product Bin 600	0.5	0.9
	41e	Product Bin 700	0.2	0.3
	42	Bulk Loadout Exhaust - Truck	0.2	0.1
	43	Bulk Loadout Exhaust - Rail	0.2	0.1
	44	Receiver Bin Vent	0.3	0.9
	46	Bagger Exhaust	1.3	2.6
	54	Product Storage bin and loading spout	0.2	0.4
039	48	Receiver Bin 200 Vent	0.6	2.2
	49	FEM Mill #1 Receiver Collector	0.4	0.8
	50	FEM Mill #2 Receiver Collector	0.4	0.8
	53	#2 Classifier Feed Vent	0.2	0.3
	55	Gel Rail Loadout	0.2	0.4
	56	Product Bin 151	0.1	0.2
		TOTAL:	8.85	23.7

[40CFR60.672, Rule 62-204.800(8)(b)66, F.A.C.; construction permits 0390005-009-AC and 0390005-011-AC; Title V Operation Permit 0390005-002-AV]

Test Methods and Procedures

G.5. PM, VE: To demonstrate compliance with conditions **G.3** and **G.4**, the permittee shall conduct annual visible emissions tests on each emission point once during each federal fiscal year (October 1 through September 30) and generally at 12-month intervals. The test method shall be EPA Method 9, incorporated and adopted by reference in Rule 62-297, F.A.C. and the test duration is 30 minutes.

In addition, to demonstrate compliance with condition **G.4.1(b)**, the owner or operator shall conduct EPA Method 22 performance tests for fugitive emissions on each building enclosing the referenced emission points twice during the lifetime of this permit and generally at 24-month intervals. The performance test shall be conducted while all affected emission points inside the building are operating. The performance test for each building shall be at least 75 minutes in duration, with each side of the building and the roof being observed for at least 15 minutes. [Rules 62-297.401 and 62-204.800(8)(b)66, F.A.C.; Title V Operation Permit 0390005-002-AV; 40 CFR 60.675(d)]

G.6. PM: Rule 62-297.620(4), F.A.C., allows the waiver of particulate matter compliance test requirements for an emissions unit which has the potential to emit less than 100 tons per year of particulate matter and is equipped with a baghouse. If the Department has reason to believe that the particulate weight emission standard applicable to such emissions unit is not being met, it shall require that compliance be demonstrated by the applicable test method. Compliance with the particulate matter emission limit may be demonstrated by compliance with the alternative opacity standard of 5% as required by condition **G.5**. In the event any emissions unit does not satisfactorily demonstrate compliance as required by condition **G.5** above, each such emissions unit shall demonstrate compliance with the PM limit by EPA Method 5 within 90 days of the visible emissions test date. [Rule 62-297.620(4), F.A.C.; Title V Operation Permit 0390005-002-AV]

Recordkeeping and Reporting Requirements

G.7: The permittee shall maintain a record of baghouse pressure differentials, recording the pressure drops at least at each shift change or every eight hours, whichever is more frequent. [Rule 62-4.070(3), F.A.C.; Title V Operation Permit 0390005-002-AV]
{Permitting Note: The baghouse pressure differential should be within the normal operational range of 0.5" to 5" WG. If the pressure differential is observed outside of the normal operation parameters, appropriate corrective action should be taken immediately.}

G.8. These emissions units are also subject to Common Conditions **H.1** (Test Methods and Procedures), **H.2** (Monitoring of Operations) **I.1** (40 CFR 60, Subpart A - General Provisions Requirements) and **I.2** (40 CFR 60. Subpart OOO Standards of Performance for Nonmetallic Mineral Processing Plants). [Title V Operation Permit 0390005-002-AV]

Section III. Emissions Unit(s) and Conditions.

Subsection H. Common Conditions.

The following conditions apply to the emissions units as noted in the applicable specific conditions.

{Permitting Note: The following conditions are placed here as a convenience and to avoid duplication. See specific conditions in Subsections A through G for applicability.}

H.1. Test Methods and Procedures

Emissions tests are required to show continuing compliance with the standards of the Department. The test results must provide reasonable assurance that the source is capable of compliance at the permitted maximum operating rate. Tests shall be conducted as required by the applicable specific condition(s) of Subsections A through G. Results shall be submitted to the Department within 45 days after testing. The Department shall be notified at least 15 days prior to testing to allow witnessing. [Rule 62-297.310, F.A.C.]

Testing of emissions shall be conducted with the emissions unit operating at permitted capacity, which is defined as 90 to 100 percent of the maximum operation rate allowed by the permit. If it is impracticable to test at permitted capacity, an emissions unit may be tested at less than the minimum permitted capacity (i.e., at less than 90 percent of the maximum operation rate allowed by the permit); in this case, subsequent emissions unit operation is limited to 110 percent of the test load until a new test is conducted, provided however, operations do not exceed 100 percent of the maximum operation rate allowed by the permit. Once the emissions unit is so limited, operation at higher capacities is allowed for no more than 15 consecutive days for the purpose of additional compliance testing to regain the authority to operate at the permitted capacity. [Rules 62-297.310(2) & (2)(b), F.A.C.]

H.2. Determination of Process Variables/Monitoring of Operations

The owner or operator of an emissions unit for which compliance tests are required shall install, operate and maintain equipment or instruments necessary to determine process variables, such as process weight input or heat input, or baghouse or scrubber pressure drop, when such data re needed in conjunction with emissions data to determine the compliance of the emissions unit with applicable emission limiting standards.

Equipment or instruments used to directly or indirectly determine process variables, including devices such as belt scales, weight hoppers, flow meters, and tank scales, shall be calibrated and adjusted to indicate the true value of the parameter being measured with sufficient accuracy to allow the applicable process variable to be determined within 10% of its true value.
[Rule 62-297.310(5), F.A.C.]

H.3. Excess Emissions

Excess emissions resulting from startup, shutdown or malfunction of any emissions unit shall be permitted providing (1) best operational practices to minimize emissions are adhered to and (2) the duration of excess emissions shall be minimized but in no case exceed two hours in any 24-hour period unless specifically authorized by the Department for longer durations.

Excess emissions which are caused entirely or in part by poor maintenance, poor operation, or any other equipment or process failure which may reasonably be prevented during startup, shutdown, or malfunction shall be prohibited.

In case of excess emissions resulting from malfunctions, each owner or operator shall notify the Department in accordance with Rule 62-4.130, F.A.C. A full written report on the malfunctions shall be submitted in a quarterly report, if requested by the Department.
[Rule 62-210.700, F.A.C.]

Section III. Emissions Unit(s) and Conditions.

Subsection I. NSPS Common Conditions

E.U. ID No.	Brief Description
013	Fine Grinding
016	Extrusion Reagent Process
018	#4 Mill Material Handling
020	East Bagging and Fugitive Dust
027	Loadout East Bagging
028	Classifier Product Bagging System
011	#1 Milling Area
031	Fluid Bed Dryer Material Handling
032	Reconstitution Area
033	#1A Mill System
035	Finishing Area
036	Granular Packaging Area
038	ACM Milling
039	Ultra Fine Grind

The following conditions apply to the emissions units as noted in the applicable specific conditions.

{Permitting Note: The following conditions are placed here as a convenience and to avoid duplication. See specific conditions in Subsections A through H for applicability.}

The following conditions apply to the NSPS emissions units listed above:

40 CFR 60, Subpart A – General Provisions Requirements

I.1. These emissions units are subject to applicable requirements from Part 60 – Standards of Performance for New Stationary Sources, including Subpart A as identified in attached Table 1: Applicability of Subpart A to Subpart OOO. [40 CFR 60 Subpart OOO, Rule 62-204.8008(b)66., F.A.C.]

I.2. Subpart OOO-Standards of Performance for Nonmetallic Mineral Processing Plants
These emissions units are subject to applicable requirements form Part 60 – Standards of Performance for New Stationary Sources, including Subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants, including:

§60.670 Applicability and designation of affected facility
(a) The provisions of this subpart are applicable to the following affected facilities in fixed or portable nonmetallic mineral processing plants: each crusher, grinding mill, screening operation, bucket elevator, belt conveyor, bagging operation, storage bin, enclosed truck or railcar loading station.
(d) (1) When an existing facility is replaced by a piece of equipment of equal or smaller size, as defined in §40 CFR 60.671, having the same function as the existing facility, and there is no

increase in the amount of emissions, the new facility is exempt from the provisions of §§60.672, 60.674, and 60.675 except as provided for in paragraph (d)(3) of this section.
(2) An owner or operator complying with paragraph (d)(1) of this section shall submit the information required in §60.676(a).
(3) An owner or operator replacing all existing facilities in a production line with new facilities does not qualify for the exemption described in paragraph (d)(1) of this section and must comply with the provisions of §§60.672, 60.674 and 60.675.

60.676 Reporting and recordkeeping

Each owner or operator seeking to comply with §60.670(d) shall submit to the Administrator the following information about the existing facility being replaced and the replacement piece of equipment.
(1) For a crusher, grinding mill, bucket elevator, bagging operation, or enclosed truck or railcar loading station:
(i) The rated capacity in megagrams or tons per hour of the existing facility being replaced and
(ii) The rated capacity in tons per hour of the replacement equipment.
(2) For a screening operation:
(i) The total surface area of the top screen of the existing screening operation being replaced and
(ii) The total surface area of the top screen of the replacement screening operation.
(3) For a conveyor belt:
(i) The width of the existing belt being replaced and
(ii) The width of the replacement conveyor belt.
(4) For a storage bin:
(i) The rated capacity in megagrams or tons of the existing storage bin being replaced and
(ii) The rated capacity in megagrams or tons of replacement storage bins.