Federal Regulations Adopted by Reference

In accordance with Rule 62-204.800, F.A.C., the following federal regulation in Title 40 of the Code of Federal Regulations (CFR) was adopted by reference. The original federal rule numbering has been retained.

Federal Revision Date: December 20, 2006

State Rule Effective Date: April 2, 2007

Standardized Conditions Revision Date: December 9, 2008

40 CFR Part 63, Subpart LLL—National Emission Standards for Hazardous Air Pollutants From the Portland Cement Manufacturing Industry

Source: 64 FR 31925, June 14, 1999, unless otherwise noted.

General

§ 63.1340 Applicability and designation of affected sources.

(a) Except as specified in paragraphs (b) and (c) of this section, the provisions of this subpart apply to each new and existing portland cement plant which is a major source or an area source as defined in §63.2.

(b) The affected sources subject to this subpart are:

(1) Each kiln and each in-line kiln/raw mill at any major or area source, including alkali bypasses, except for kilns and in-line kiln/raw mills that burn hazardous waste and are subject to and regulated under subpart EEE of this part;

(2) Each clinker cooler at any portland cement plant which is a major source;

(3) Each raw mill at any portland cement plant which is a major source;

(4) Each finish mill at any portland cement plant which is a major source;

(5) Each raw material dryer at any portland cement plant which is a major source and each greenfield raw material dryer at any portland cement plant which is a major or area source;

(6) Each raw material, clinker, or finished product storage bin at any portland cement plant which is a major source;

(7) Each conveying system transfer point including those associated with coal preparation used to convey coal from the mill to the kiln at any portland cement plant which is a major source; and

(8) Each bagging and bulk loading and unloading system at any portland cement plant which is a major source.

(c) For portland cement plants with on-site nonmetallic mineral processing facilities, the first affected source in the sequence of materials handling operations subject to this subpart is the raw material storage, which is just prior to the raw mill. Any equipment of the on-site nonmetallic mineral processing plant which precedes the raw material storage is not subject to this subpart. In addition, the primary and secondary crushers of the on-site nonmetallic mineral processing plant, regardless of whether they precede the raw material storage, are not subject to this subpart. Furthermore, the first conveyor transfer point subject to this subpart is the transfer point associated with the conveyor transferring material from the raw material storage to the raw mill.

(d) The owner or operator of any affected source subject to the provisions of this subpart is subject to title V permitting requirements.

[64 FR 31925, June 14, 1999, as amended at 67 FR 16619, Apr. 5, 2002; 67 FR 72584, Dec. 6, 2002]

§ 63.1341 Definitions.

All terms used in this subpart that are not defined in this section have the meaning given to them in the CAA and in subpart A of this part.

Alkali bypass means a duct between the feed end of the kiln and the preheater tower through which a portion of the kiln exit gas stream is withdrawn and quickly cooled by air or water to avoid excessive buildup of alkali, chloride and/or sulfur on the raw feed. This may also be referred to as the “kiln exhaust gas bypass”.

Bagging system means the equipment which fills bags with portland cement.

Bin means a manmade enclosure for storage of raw materials, clinker, or finished product prior to further processing at a portland cement plant.

Clinker cooler means equipment into which clinker product leaving the kiln is placed to be cooled by air supplied by a forced draft or natural draft supply system.

Continuous monitor means a device which continuously samples the regulated parameter specified in §63.1350 of this subpart without interruption, evaluates the detector response at least once every 15 seconds, and computes and records the average value at least every 60 seconds, except during allowable periods of calibration and except as defined otherwise by the continuous emission monitoring system performance specifications in appendix B to part 60 of this chapter.

Conveying system means a device for transporting materials from one piece of equipment or location to another location within a facility. Conveying systems include but are not limited to the following: feeders, belt conveyors, bucket elevators and pneumatic systems.

Conveying system transfer point means a point where any material including but not limited to feed material, fuel, clinker or product, is transferred to or from a conveying system, or between separate parts of a conveying system.

Dioxins and furans (D/F) means tetra-, penta-, hexa-, hepta-, and octa-chlorinated dibenzo dioxins and furans.

Facility means all contiguous or adjoining property that is under common ownership or control, including properties that are separated only by a road or other public right-of-way.

Feed means the prepared and mixed materials, which include but are not limited to materials such as limestone, clay, shale, sand, iron ore, mill scale, cement kiln dust and fly ash, that are fed to the kiln. Feed does not include the fuels used in the kiln to produce heat to form the clinker product.

Finish mill means a roll crusher, ball and tube mill or other size reduction equipment used to grind clinker to a fine powder. Gypsum and other materials may be added to and blended with clinker in a finish mill. The finish mill also includes the air separator associated with the finish mill.

Greenfield kiln, in-line kiln/raw mill, or raw material dryer means a kiln, in-line kiln/raw mill, or raw material dryer for which construction is commenced at a plant site (where no kilns and no in-line kiln/raw mills were in operation at any time prior to March 24, 1998) after March 24, 1998.

Hazardous waste is defined in §261.3 of this chapter.

In-line kiln/raw mill means a system in a portland cement production process where a dry kiln system is integrated with the raw mill so that all or a portion of the kiln exhaust gases are used to perform the drying operation of the raw mill, with no auxiliary heat source used. In this system the kiln is capable of operating without the raw mill operating, but the raw mill cannot operate without the kiln gases, and consequently, the raw mill does not generate a separate exhaust gas stream.

Kiln means a device, including any associated preheater or precalciner devices, that produces clinker by heating limestone and other materials for subsequent production of portland cement.

Kiln exhaust gas bypass means alkali bypass.

Monovent means an exhaust configuration of a building or emission control device (e. g. positive pressure fabric filter) that extends the length of the structure and has a width very small in relation to its length (i. e., length to width ratio is typically greater than 5:1). The exhaust may be an open vent with or without a roof, louvered vents, or a combination of such features.

New brownfield kiln, in-line kiln raw mill, or raw material dryer means a kiln, in-line kiln/raw mill or raw material dryer for which construction is commenced at a plant site (where kilns and/or in-line kiln/raw mills were in operation prior to March 24, 1998) after March 24, 1998.

One-minute average means the average of thermocouple or other sensor responses calculated at least every 60 seconds from responses obtained at least once during each consecutive 15 second period.

Portland cement plant means any facility manufacturing portland cement.

Raw material dryer means an impact dryer, drum dryer, paddle-equipped rapid dryer, air separator, or other equipment used to reduce the moisture content of feed materials.

Raw mill means a ball and tube mill, vertical roller mill or other size reduction equipment, that is not part of an in-line kiln/raw mill, used to grind feed to the appropriate size. Moisture may be added or removed from the feed during the grinding operation. If the raw mill is used to remove moisture from feed materials, it is also, by definition, a raw material dryer. The raw mill also includes the air separator associated with the raw mill.

Rolling average means the average of all one-minute averages over the averaging period.

Run average means the average of the one-minute parameter values for a run.

TEQ means the international method of expressing toxicity equivalents for dioxins and furans as defined in U.S. EPA, Interim Procedures for Estimating Risks Associated with Exposures to Mixtures of Chlorinated Dibenzo-p-dioxins and -dibenzofurans (CDDs and CDFs) and 1989 Update, March 1989.

[64 FR 31925, June 14, 1999, as amended at 67 FR 16619, Apr. 5, 2002]

Emission Standards and Operating Limits

§ 63.1342 Standards: General.

Table 1 to this subpart provides cross references to the 40 CFR part 63, subpart A, general provisions, indicating the applicability of the general provisions requirements to subpart LLL.

[71 FR 76549, Dec. 20, 2006]

§ 63.1343 Standards for kilns and in-line kiln/raw mills.

(a) *General.* The provisions in this section apply to each kiln, each in-line kiln/raw mill, and any alkali bypass associated with that kiln or in-line kiln/raw mill. All gaseous, mercury and D/F emission limits are on a dry basis, corrected to 7 percent oxygen. All total hydrocarbon (THC) emission limits are measured as propane. The block averaging periods to demonstrate compliance are hourly for 20 ppmv total hydrocarbon (THC) limits and monthly for the 50 ppmv THC limit.

(b) *Existing kilns located at major sources.* No owner or operator of an existing kiln or an existing kiln/raw mill located at a facility that is a major source subject to the provisions of this subpart shall cause to be discharged into the atmosphere from these affected sources, any gases which:

(1) Contain particulate matter (PM) in excess of 0.15 kg per Mg (0.30 lb per ton) of feed (dry basis) to the kiln. When there is an alkali bypass associated with a kiln or in-line kiln/raw mill, the combined particulate matter emissions from the kiln or in-line kiln/raw mill and the alkali bypass are subject to this emission limit.

(2) Exhibit opacity greater than 20 percent.

(3) Contain D/F in excess of:

(i) 0.20 ng per dscm (8.7×10^{-11}gr per dscf) (TEQ); or

(ii) 0.40 ng per dscm (1.7×10^{-10}gr per dscf) (TEQ) when the average of the performance test run average temperatures at the inlet to the particulate matter control device is 204 °C (400 °F) or less.

(c) *Reconstructed or new kilns located at major sources.* No owner or operator of a reconstructed or new kiln or reconstructed or new inline kiln/raw mill located at a facility which is a major source subject to the provisions of this subpart shall cause to be discharged into the atmosphere from these affected sources any gases which:

(1) Contain particulate matter in excess of 0.15 kg per Mg (0.30 lb per ton) of feed (dry basis) to the kiln. When there is an alkali bypass associated with a kiln or in-line kiln/raw mill, the combined particulate matter emissions from the kiln or in-line kiln/raw mill and the bypass stack are subject to this emission limit.

(2) Exhibit opacity greater than 20 percent.

(3) Contain D/F in excess of:

(i) 0.20 ng per dscm (8.7×10^{-11}gr per dscf) (TEQ); or

(ii) 0.40 ng per dscm (1.7×10^{-10}gr per dscf) (TEQ) when the average of the performance test run average temperatures at the inlet to the particulate matter control device is 204 °C (400 °F) or less.

(4) Contain total hydrocarbons (THC), from the main exhaust of the kiln, or main exhaust of the in-line kiln/raw mill, in excess of 20 ppmv if the source is a new or reconstructed source that commenced construction after December 2, 2005. As an alternative to meeting the 20 ppmv standard you may demonstrate a 98 percent reduction of THC emissions from the exit of the kiln to discharge to the atmosphere. If the source is a greenfield kiln that commenced construction on or prior to December 2, 2005, then the THC limit is 50 ppmv.

(5) Contain mercury from the main exhaust of the kiln, or main exhaust of the in-line kiln/raw mill, or the alkali bypass in excess of 41μg/dscm if the source is a new or reconstructed source that commenced construction after December 2, 2005. As an alternative to meeting the 41 μg/dscm standard you may route the emissions through a packed bed or

spray tower wet scrubber with a liquid-to-gas (l/g) ratio of 30 gallons per 1000 actual cubic feet per minute (acfm) or more and meet a site-specific emissions limit based on the measured performance of the wet scrubber.

(d) *Existing kilns located at area sources.* No owner or operator of an existing kiln or an existing in-line kiln/raw mill located at a facility that is an area source subject to the provisions of this subpart shall cause to be discharged into the atmosphere from these affected sources any gases which:

(1) Contain D/F in excess of 0.20 ng per dscm (8.7×10^{-11}gr per dscf) (TEQ); or

(2) Contain D/F in excess of 0.40 ng per dscm (1.7×10^{-10}gr per dscf) (TEQ) when the average of the performance test run average temperatures at the inlet to the particulate matter control device is 204 °C (400 °F) or less.

(e) *New or reconstructed kilns located at area sources.* No owner or operator of a new or reconstructed kiln or new or reconstructed in-line kiln/raw mill located at a facility that is an area source subject to the provisions of this subpart shall cause to be discharged into the atmosphere from these affected sources any gases which:

(1) Contain D/F in excess of:

(i) 0.20 ng per dscm (8.7×10^{-11}gr per dscf) (TEQ; or

(ii) 0.40 ng per dscm (1.7×10^{-10}gr per dscf) (TEQ) when the average of the performance test run average temperatures at the inlet to the particulate matter control device is 204 °C (400 °F) or less.

(2) Contain total hydrocarbons (THC), from the main exhaust of the kiln, or main exhaust of the in-line kiln/raw mill, in excess of 20 ppmv if the source is a new or reconstructed source that commenced construction after December 2, 2005. As an alternative to meeting the 20 ppmv standard you may demonstrate a 98 percent reduction of THC emissions from the exit of the kiln to discharge to the atmosphere. If the source is a greenfield kiln that commenced construction on or prior to December 2, 2005, then the THC limit is 50 ppmv.

(3) Contain mercury from the main exhaust of the kiln, or main exhaust of the in-line kiln/raw mill, or the alkali bypass in excess of 41 μg/dscm if the source is a new or reconstructed source that commenced construction after December 2, 2005. As an alternative to meeting the 41 μg/dscm standard you may route the emissions through a packed bed or spray tower wet scrubber with a liquid-to-gas (l/g) ratio of 30 gallons per 1000 actual cubic feet per minute (acfm) or more and meet a site-specific emissions limit based on the measured performance of the wet scrubber.

[71 FR 76549, Dec. 20, 2006]

§ 63.1344 Operating limits for kilns and in-line kiln/raw mills.

(a) The owner or operator of a kiln subject to a D/F emission limitation under §63.1343 must operate the kiln such that the temperature of the gas at the inlet to the kiln particulate matter control device (PMCD) and alkali bypass PMCD, if applicable, does not exceed the applicable temperature limit specified in paragraph (b) of this section. The owner or operator of an in-line kiln/raw mill subject to a D/F emission limitation under §63.1343 must operate the in-line kiln/raw mill, such that:

(1) When the raw mill of the in-line kiln/raw mill is operating, the applicable temperature limit for the main in-line kiln/raw mill exhaust, specified in paragraph (b) of this section and established during the performance test when the raw mill was operating is not exceeded.

(2) When the raw mill of the in-line kiln/raw mill is not operating, the applicable temperature limit for the main in-line kiln/raw mill exhaust, specified in paragraph (b) of this section and established during the performance test when the raw mill was not operating, is not exceeded.

(3) If the in-line kiln/raw mill is equipped with an alkali bypass, the applicable temperature limit for the alkali bypass specified in paragraph (b) of this section and established during the performance test, with or without the raw mill operating, is not exceeded.

(b) The temperature limit for affected sources meeting the limits of paragraph (a) of this section or paragraphs (a)(1) through (a)(3) of this section is determined in accordance with §63.1349(b)(3)(iv).

(c) The owner or operator of an affected source subject to a mercury, THC or D/F emission limitation under §63.1343 that employs carbon injection as an emission control technique must operate the carbon injection system in accordance with paragraphs (c)(1) and (c)(2) of this section.

(1) The three-hour rolling average activated carbon injection rate shall be equal to or greater than the activated carbon injection rate determined in accordance with §63.1349(b)(3)(vi).

(2) The owner or operator shall either:

(i) Maintain the minimum activated carbon injection carrier gas flow rate, as a three-hour rolling average, based on the manufacturer's specifications. These specifications must be documented in the test plan developed in accordance with §63.7(c), or

(ii) Maintain the minimum activated carbon injection carrier gas pressure drop, as a three-hour rolling average, based on the manufacturer's specifications. These specifications must be documented in the test plan developed in accordance with §63.7(c).

(d) Except as provided in paragraph (e) of this section, the owner or operator of an affected source subject to a mercury, THC or D/F emission limitation under §63.1343 that employs carbon injection as an emission control technique must specify and use the brand and type of activated carbon used during the performance test until a subsequent performance test is conducted, unless the site-specific performance test plan contains documentation of key parameters that affect adsorption and the owner or operator establishes limits based on those parameters, and the limits on these parameters are maintained.

(e) The owner or operator of an affected source subject to a D/F, THC, or mercury emission limitation under §63.1343 that employs carbon injection as an emission control technique may substitute, at any time, a different brand or type of activated carbon provided that the replacement has equivalent or improved properties compared to the activated carbon specified in the site-specific performance test plan and used in the performance test. The owner or operator must maintain documentation that the substitute activated carbon will provide the same or better level of control as the original activated carbon.

(f) Existing kilns and in-line kilns/raw mills must implement good combustion practices (GCP) designed to minimize THC from fuel combustion. GCP include training all operators and supervisors to operate and maintain the kiln and calciner, and the pollution control systems in accordance with good engineering practices. The training shall include methods for minimizing excess emissions.

(g) No kiln and in-line kiln/raw mill may use as a raw material or fuel any fly ash where the mercury content of the fly ash has been increased through the use of activated carbon, or any other sorbent unless the facility can demonstrate that the use of that fly ash will not result in an increase in mercury emissions over baseline emissions (i.e. emissions not using the fly ash). The facility has the burden of proving there has been no emissions increase over baseline.

(h) All kilns and in-line kilns/raw mills must remove (i.e. not recycle to the kiln) from the kiln system sufficient cement kiln dust to maintain the desired product quality.

(i) New and reconstructed kilns and in-line kilns/raw mills must not exceed the average hourly CKD recycle rate measured during mercury performance testing. Any exceedance of this average hourly rate is considered a violation of the standard.

[64 FR 31925, June 14, 1999, as amended at 67 FR 72585, Dec. 6, 2002; 71 FR 76550, Dec. 20, 2006]

§ 63.1345 Standards for clinker coolers.

(a) No owner or operator of a new or existing clinker cooler at a facility which is a major source subject to the provisions of this subpart shall cause to be discharged into the atmosphere from the clinker cooler any gases which:

(1) Contain particulate matter in excess of 0.050 kg per Mg (0.10 lb per ton) of feed (dry basis) to the kiln.

(2) Exhibit opacity greater than ten percent.

(b) [Reserved]

§ 63.1346 Standards for new or reconstructed raw material dryers.

(a) New or reconstructed raw material dryers located at facilities that are major sources can not discharge to the atmosphere any gases which:

(1) Exhibit opacity greater than ten percent, or

(2) Contain THC in excess of 20 ppmv, on a dry basis as propane corrected to 7 percent oxygen if the source commenced construction after December 2, 2005. As an alternative to the 20 ppmv standard, you may demonstrate a 98 percent reduction in THC emissions from the exit of the raw materials dryer to discharge to the atmosphere. If the source is a greenfield dryer constructed on or prior to December 2, 2005, then the THC limit is 50 ppmv, on a dry basis corrected to 7 percent oxygen.

(b) New or reconstructed raw materials dryers located at a facility that is an area source cannot discharge to the atmosphere any gases which contain THC in excess of 20 ppmv, on a dry basis as propane corrected to 7 percent oxygen if the source commenced construction after December 2, 2005. As an alternative to the 20 ppmv standard, you may demonstrate a 98 percent reduction in THC emissions from the exit of the raw materials dryer to discharge to the atmosphere. If the source is a greenfield dryer constructed on or prior to December 2, 2005, then the THC limit is 50 ppmv, on a dry basis corrected to 7 percent oxygen.

[71 FR 76551, Dec. 20, 2006]

§ 63.1347 Standards for raw and finish mills.

The owner or operator of each new or existing raw mill or finish mill at a facility which is a major source subject to the provisions of this subpart shall not cause to be discharged from the mill sweep or air separator air pollution control devices of these affected sources any gases which exhibit opacity in excess of ten percent.

§ 63.1348 Standards for affected sources other than kilns; in-line kiln/raw mills; clinker coolers; new and reconstructed raw material dryers; and raw and finish mills.

The owner or operator of each new or existing raw material, clinker, or finished product storage bin; conveying system transfer point; bagging system; and bulk loading or unloading system; and each existing raw material dryer, at a facility which is a major source subject to the provisions of this subpart shall not cause to be discharged any gases from these affected sources which exhibit opacity in excess of ten percent.

Monitoring and Compliance Provisions

§ 63.1349 Performance testing requirements.

(a) The owner or operator of an affected source subject to this subpart shall demonstrate initial compliance with the emission limits of §63.1343 and §§63.1345 through 63.1348 using the test methods and procedures in paragraph (b) of this section and §63.7. Performance test results shall be documented in complete test reports that contain the information required by paragraphs (a)(1) through (a)(10) of this section, as well as all other relevant information. The plan to be followed during testing shall be made available to the Administrator prior to testing, if requested.

(1) A brief description of the process and the air pollution control system;

(2) Sampling location description(s);

(3) A description of sampling and analytical procedures and any modifications to standard procedures;

(4) Test results;

(5) Quality assurance procedures and results;

(6) Records of operating conditions during the test, preparation of standards, and calibration procedures;

(7) Raw data sheets for field sampling and field and laboratory analyses;

(8) Documentation of calculations;

(9) All data recorded and used to establish parameters for compliance monitoring; and

(10) Any other information required by the test method.

(b) Performance tests to demonstrate initial compliance with this subpart shall be conducted as specified in paragraphs (b)(1) through (b)(4) of this section.

(1) The owner or operator of a kiln subject to limitations on particulate matter emissions shall demonstrate initial compliance by conducting a performance test as specified in paragraphs (b)(1)(i) through (b)(1)(iv) of this section. The owner or operator of an in-line kiln/raw mill subject to limitations on particulate matter emissions shall demonstrate initial compliance by conducting separate performance tests as specified in paragraphs (b)(1)(i) through (b)(1)(iv) of this section while the raw mill of the in-line kiln/raw mill is under normal operating conditions and while the raw mill of the in-line kiln/raw mill is not operating. The owner or operator of a clinker cooler subject to limitations on particulate matter emissions shall demonstrate initial compliance by conducting a performance test as specified in paragraphs (b)(1)(i) through (b)(1)(iii) of this section. The opacity exhibited during the period of the Method 5 of Appendix A to part 60 of this chapter performance tests required by paragraph (b)(1)(i) of this section shall be determined as required in paragraphs (b)(1)(v) through (vi) of this section.

(i) Method 5 of appendix A to part 60 of this chapter shall be used to determine PM emissions. Each performance test shall consist of three separate runs under the conditions that exist when the affected source is operating at the representative performance conditions in accordance with §63.7(e). Each run shall be conducted for at least 1 hour, and the minimum sample volume shall be 0.85 dscm (30 dscf). The average of the three runs shall be used to determine compliance. A determination of the PM collected in the impingers ("back half") of the Method 5 particulate sampling train is not required to demonstrate initial compliance with the PM standards of this subpart. However, this shall not preclude the permitting authority from requiring a determination of the "back half" for other purposes.

(ii) Suitable methods shall be used to determine the kiln or inline kiln/raw mill feed rate, except for fuels, for each run.

(iii) The emission rate, E, of PM shall be computed for each run using equation 1:

$$E = (C_s Q_{sd})/P \qquad (Eq.\ 1)$$

View or download PDF

Where:

E = emission rate of particulate matter, kg/Mg of kiln feed.

c_s = concentration of PM, kg/dscm.

Q_{sd} = volumetric flow rate of effluent gas, dscm/hr.

P = total kiln feed (dry basis), Mg/hr.

(iv) When there is an alkali bypass associated with a kiln or in-line kiln/raw mill, the main exhaust and alkali bypass of the kiln or in-line kiln/raw mill shall be tested simultaneously and the combined emission rate of particulate matter from the kiln or in-line kiln/raw mill and alkali bypass shall be computed for each run using equation 2,

$$E_c = (C_{sk} Q_{sdk} + C_{sb} Q_{sdb})/P \qquad (Eq.\ 2)$$

View or download PDF

Where:

E_c = the combined emission rate of particulate matter from the kiln or in-line kiln/raw mill and bypass stack, kg/Mg of kiln feed.

c_{sk} = concentration of particulate matter in the kiln or in-line kiln/raw mill effluent, kg/dscm.

Q_{sdk} = volumetric flow rate of kiln or in-line kiln/raw mill effluent, dscm/hr.

c_{sb} = concentration of particulate matter in the alkali bypass gas, kg/dscm.

Q_{sdb} = volumetric flow rate of alkali bypass gas, dscm/hr.

P = total kiln feed (dry basis), Mg/hr.

(v) Except as provided in paragraph (b)(1)(vi) of this section the opacity exhibited during the period of the Method 5 performance tests required by paragraph (b)(1)(i) of this section shall be determined through the use of a continuous opacity monitor (COM). The maximum six-minute average opacity during the three Method 5 test runs shall be determined during each Method 5 test run, and used to demonstrate initial compliance with the applicable opacity limits of §63.1343(b)(2), §63.1343(c)(2), or §63.1345(a)(2).

(vi) Each owner or operator of a kiln, in-line kiln/raw mill, or clinker cooler subject to the provisions of this subpart using a fabric filter with multiple stacks or an electrostatic precipitator with multiple stacks may, in lieu of installing the continuous opacity monitoring system required by paragraph (b)(1)(v) of this section, conduct an opacity test in accordance with Method 9 of appendix A to part 60 of this chapter during each Method 5 performance test required by paragraph (b)(1)(i) of this section. If the control device exhausts through a monovent, or if the use of a COM in accordance with the installation specifications of Performance Specification 1 (PS–1) of appendix B to part 60 of this chapter is not feasible, a test shall be conducted in accordance with Method 9 of appendix A to part 60 of this chapter during each Method 5 performance test required by paragraph (b)(1)(i) of this section. The maximum six-minute average opacity shall be determined

during the three Method 5 test runs, and used to demonstrate initial compliance with the applicable opacity limits of §63.1343(b)(2), §63.1343(c)(2), or §63.1345(a)(2).

(2) The owner or operator of any affected source subject to limitations on opacity under this subpart that is not subject to paragraph (b)(1) of this section shall demonstrate initial compliance with the affected source opacity limit by conducting a test in accordance with Method 9 of appendix A to part 60 of this chapter. The performance test shall be conducted under the conditions that exist when the affected source is operating at the representative performance conditions in accordance with §63.7(e). The maximum 6-minute average opacity exhibited during the test period shall be used to determine whether the affected source is in initial compliance with the standard. The duration of the Method 9 performance test shall be 3 hours (30 6-minute averages), except that the duration of the Method 9 performance test may be reduced to 1 hour if the conditions of paragraphs (b)(2)(i) through (ii) of this section apply:

(i) There are no individual readings greater than 10 percent opacity;

(ii) There are no more than three readings of 10 percent for the first 1-hour period.

(3) The owner or operator of an affected source subject to limitations on D/F emissions under this subpart shall demonstrate initial compliance with the D/F emission limit by conducting a performance test using Method 23 of appendix A to part 60 of this chapter. The owner or operator of an in-line kiln/raw mill shall demonstrate initial compliance by conducting separate performance tests while the raw mill of the in-line kiln/raw mill is under normal operating conditions and while the raw mill of the in-line kiln/raw mill is not operating. The owner or operator of a kiln or in-line kiln/raw mill equipped with an alkali bypass shall conduct simultaneous performance tests of the kiln or in-line kiln/raw mill exhaust and the alkali bypass. However, the owner or operator of an in-line kiln/raw mill may conduct a performance test of the alkali bypass exhaust when the raw mill of the in-line kiln/raw mill is operating or not operating.

(i) Each performance test shall consist of three separate runs; each run shall be conducted under the conditions that exist when the affected source is operating at the representative performance conditions in accordance with §63.7(e). The duration of each run shall be at least 3 hours, and the sample volume for each run shall be at least 2.5 dscm (90 dscf). The concentration shall be determined for each run, and the arithmetic average of the concentrations measured for the three runs shall be calculated and used to determine compliance.

(ii) The temperature at the inlet to the kiln or in-line kiln/raw mill PMCD, and where applicable, the temperature at the inlet to the alkali bypass PMCD, must be continuously recorded during the period of the Method 23 test, and the continuous temperature record(s) must be included in the performance test report.

(iii) One-minute average temperatures must be calculated for each minute of each run of the test.

(iv) The run average temperature must be calculated for each run, and the average of the run average temperatures must be determined and included in the performance test report and will determine the applicable temperature limit in accordance with §63.1344(b).

(v) If activated carbon injection is used for D/F control, the rate of activated carbon injection to the kiln or in-line kiln/raw mill exhaust, and where applicable, the rate of activated carbon injection to the alkali bypass exhaust, must be continuously recorded during the period of the Method 23 test, and the continuous injection rate record(s) must be included in the performance test report. In addition, the performance test report must include the brand and type of activated carbon used during the performance test and a continuous record of either the carrier gas flow rate or the carrier gas pressure drop for the duration of the test. Activated carbon injection rate parameters must be determined in accordance with paragraphs (b)(3)(vi) of this section.

(vi) The run average injection rate must be calculated for each run, and the average of the run average injection rates must be determined and included in the performance test report and will determine the applicable injection rate limit in accordance with §63.1344(c)(1).

(4)

(i) The owner or operator of an affected source subject to limitations on emissions of THC shall demonstrate initial compliance with the THC limit by operating a continuous emission monitor in accordance with Performance Specification 8A of appendix B to part 60 of this chapter. The duration of the performance test shall be three hours, and the average THC concentration (as calculated from the one-minute averages) during the three-hour performance test shall be calculated. The owner or operator of an in-line kiln/raw mill shall demonstrate initial compliance by conducting separate performance tests while the raw mill of the in-line kiln/raw mill is under normal operating conditions and while the raw mill of the in-line kiln/raw mill is not operating.

(ii) The owner or operator of an affected source subject to limitations on emissions of THC who elects to demonstrate compliance with the alternative THC emission limit of 98 percent weight reduction must demonstrate compliance by also operating a continuous emission monitor in accordance with Performance Specification 8A of appendix B to part 60 at the inlet to the THC control device of the kiln, inline kiln raw mill, or raw materials dryer in the same manner as prescribed in paragraph (i) above. Alternately, you may elect to demonstrate a 98 weight percent reduction in THC across the control device using the performance test requirements in 40 CFR part 63, subpart SS.

(5) The owner or operator of a kiln or in-line kiln/raw mill subject to the 41 μg/dscm mercury standard shall demonstrate compliance using EPA Method 29 of 40 CFR part 60. ASTM D6784–02, Standard Test Method for Elemental, Oxidized, Particle-Bound and Total Mercury Gas Generated from Coal-Fired Stationary Sources (Ontario Hydro Method), is an acceptable alternative to EPA Method 29 (portion for mercury only). If the kiln has an in-line raw mill, you must demonstrate compliance with both raw mill off and raw mill on. You must record the hourly recycle rate of CKD during both test conditions and calculate an average hourly rate for the three test runs for each test condition.

(c) Except as provided in paragraph (e) of this section, performance tests required under paragraphs (b)(1) and (b)(2) of this section shall be repeated every five years, except that the owner or operator of a kiln, in-line kiln/raw mill or clinker cooler is not required to repeat the initial performance test of opacity for the kiln, in-line kiln/raw mill or clinker cooler.

(d) Performance tests required under paragraph (b)(3) of this section shall be repeated every 30 months.

(e)

(1) If a source plans to undertake a change in operations that may adversely affect compliance with an applicable D/F standard under this subpart, the source must conduct a performance test and establish new temperature limit(s) as specified in paragraph (b)(3) of this section.

(2) If a source plans to undertake a change in operations that may adversely affect compliance with an applicable PM standard under §63.1343, the source must conduct a performance test as specified in paragraph (b)(1) of this section.

(3) In preparation for and while conducting a performance test required in paragraph (e)(1) of this section, a source may operate under the planned operational change conditions for a period not to exceed 360 hours, provided that the conditions in paragraphs (e)(3)(i) through (iv) of this section are met. The source shall submit temperature and other monitoring data that are recorded during the pretest operations.

(i) The source must provide the Administrator written notice at least 60 days prior to undertaking an operational change that may adversely affect compliance with an applicable standard under this subpart, or as soon as practicable where 60 days advance notice is not feasible. Notice provided under this paragraph shall include a description of the planned change, the emissions standards that may be affected by the change, and a schedule for completion of the performance test required under paragraph (e)(1) of this section, including when the planned operational change period would begin.

(ii) The performance test results must be documented in a test report according to paragraph (a) of this section.

(iii) A test plan must be made available to the Administrator prior to testing, if requested.

(iv) The performance test must be conducted, and it must be completed within 360 hours after the planned operational change period begins.

[64 FR 31925, June 14, 1999, as amended at 67 FR 16619, Apr. 5, 2002; 67 FR 72585, Dec. 6, 2002; 71 FR 76551, Dec. 20, 2006]

§ 63.1350 Monitoring requirements.

(a) The owner or operator of each portland cement plant shall prepare for each affected source subject to the provisions of this subpart, a written operations and maintenance plan. The plan shall be submitted to the Administrator for review and approval as part of the application for a part 70 permit and shall include the following information:

(1) Procedures for proper operation and maintenance of the affected source and air pollution control devices in order to meet the emission limits and operating limits of §§63.1343 through 63.1348;

(2) Corrective actions to be taken when required by paragraph (e) of this section;

(3) Procedures to be used during an inspection of the components of the combustion system of each kiln and each in-line kiln raw mill located at the facility at least once per year; and

(4) Procedures to be used to periodically monitor affected sources subject to opacity standards under §§63.1346 and 63.1348. Such procedures must include the provisions of paragraphs (a)(4)(i) through (a)(4)(iv) of this section.

(i) The owner or operator must conduct a monthly 1-minute visible emissions test of each affected source in accordance with Method 22 of Appendix A to part 60 of this chapter. The test must be conducted while the affected source is in operation.

(ii) If no visible emissions are observed in six consecutive monthly tests for any affected source, the owner or operator may decrease the frequency of testing from monthly to semi-annually for that affected source. If visible emissions are observed during any semi-annual test, the owner or operator must resume testing of that affected source on a monthly basis and maintain that schedule until no visible emissions are observed in six consecutive monthly tests.

(iii) If no visible emissions are observed during the semi-annual test for any affected source, the owner or operator may decrease the frequency of testing from semi-annually to annually for that affected source. If visible emissions are observed during any annual test, the owner or operator must resume testing of that affected source on a monthly basis and maintain that schedule until no visible emissions are observed in six consecutive monthly tests.

(iv) If visible emissions are observed during any Method 22 test, the owner or operator must conduct a 6-minute test of opacity in accordance with Method 9 of appendix A to part 60 of this chapter. The Method 9 test must begin within one hour of any observation of visible emissions.

(v) The requirement to conduct Method 22 visible emissions monitoring under this paragraph shall not apply to any totally enclosed conveying system transfer point, regardless of the location of the transfer point. “Totally enclosed conveying system transfer point” shall mean a conveying system transfer point that is enclosed on all sides, top, and bottom. The enclosures for these transfer points shall be operated and maintained as total enclosures on a continuing basis in accordance with the facility operations and maintenance plan.

(vi) If any partially enclosed or unenclosed conveying system transfer point is located in a building, the owner or operator of the portland cement plant shall have the option to conduct a Method 22 visible emissions monitoring test according to the requirements of paragraphs (a)(4)(i) through (iv) of this section for each such conveying system transfer point located within the building, or for the building itself, according to paragraph (a)(4)(vii) of this section.

(vii) If visible emissions from a building are monitored, the requirements of paragraphs (a)(4)(i) through (iv) of this section apply to the monitoring of the building, and you must also test visible emissions from each side, roof and vent of the building for at least 1 minute. The test must be conducted under normal operating conditions.

(b) Failure to comply with any provision of the operations and maintenance plan developed in accordance with paragraph (a) of this section shall be a violation of the standard.

(c) The owner or operator of a kiln or in-line kiln/raw mill shall monitor opacity at each point where emissions are vented from these affected sources including alkali bypasses in accordance with paragraphs (c)(1) through (c)(3) of this section.

(1) Except as provided in paragraph (c)(2) of this section, the owner or operator shall install, calibrate, maintain, and continuously operate a continuous opacity monitor (COM) located at the outlet of the PM control device to continuously monitor the opacity. The COM shall be installed, maintained, calibrated, and operated as required by subpart A, general provisions of this part, and according to PS–1 of appendix B to part 60 of this chapter.

(2) The owner or operator of a kiln or in-line kiln/raw mill subject to the provisions of this subpart using a fabric filter with multiple stacks or an electrostatic precipitator with multiple stacks may, in lieu of installing the continuous opacity monitoring system required by paragraph (c)(1) of this section, monitor opacity in accordance with paragraphs (c)(2)(i) through (ii) of this section. If the control device exhausts through a monovent, or if the use of a COM in accordance with the installation specifications of PS–1 of appendix B to part 60 of this chapter is not feasible, the owner or operator must monitor opacity in accordance with paragraphs (c)(2)(i) through (ii) of this section.

(i) Perform daily visual opacity observations of each stack in accordance with the procedures of Method 9 of appendix A to part 60 of this chapter. The Method 9 test shall be conducted while the affected source is operating at the representative performance conditions. The duration of the Method 9 test shall be at least 30 minutes each day.

(ii) Use the Method 9 procedures to monitor and record the average opacity for each six-minute period during the test.

(3) To remain in compliance, the opacity must be maintained such that the 6-minute average opacity for any 6-minute block period does not exceed 20 percent. If the average opacity for any 6-minute block period exceeds 20 percent, this shall constitute a violation of the standard.

(d) The owner or operator of a clinker cooler shall monitor opacity at each point where emissions are vented from the clinker cooler in accordance with paragraphs (d)(1) through (d)(3) of this section.

(1) Except as provided in paragraph (d)(2) of this section, the owner or operator shall install, calibrate, maintain, and continuously operate a COM located at the outlet of the clinker cooler PM control device to continuously monitor the opacity. The COM shall be installed, maintained, calibrated, and operated as required by subpart A, general provisions of this part, and according to PS–1 of appendix B to part 60 of this chapter.

(2) The owner or operator of a clinker cooler subject to the provisions of this subpart using a fabric filter with multiple stacks or an electrostatic precipitator with multiple stacks may, in lieu of installing the continuous opacity monitoring system required by paragraph (d)(1) of this section, monitor opacity in accordance with paragraphs (d)(2)(i) through (ii) of this section. If the control device exhausts through a monovent, or if the use of a COM in accordance with the installation specifications of PS–1 of appendix B to part 60 of this chapter is not feasible, the owner or operator must monitor opacity in accordance with paragraphs (d)(2)(i) through (ii) of this section.

(i) Perform daily visual opacity observations of each stack in accordance with the procedures of Method 9 of appendix A to part 60 of this chapter. The Method 9 test shall be conducted while the affected source is operating at the representative performance conditions. The duration of the Method 9 test shall be at least 30 minutes each day.

(ii) Use the Method 9 procedures to monitor and record the average opacity for each six-minute period during the test.

(3) To remain in compliance, the opacity must be maintained such that the 6-minute average opacity for any 6-minute block period does not exceed 10 percent. If the average opacity for any 6-minute block period exceeds 10 percent, this shall constitute a violation of the standard.

(e) The owner or operator of a raw mill or finish mill shall monitor opacity by conducting daily visual emissions observations of the mill sweep and air separator PMCD of these affected sources in accordance with the procedures of Method 22 of appendix A to part 60 of this chapter. The Method 22 test shall be conducted while the affected source is operating at the representative performance conditions. The duration of the Method 22 test shall be 6 minutes. If visible emissions are observed during any Method 22 visible emissions test, the owner or operator must:

(1) Initiate, within one-hour, the corrective actions specified in the site specific operating and maintenance plan developed in accordance with paragraphs (a)(1) and (a)(2) of this section; and

(2) Within 24 hours of the end of the Method 22 test in which visible emissions were observed, conduct a follow-up Method 22 test of each stack from which visible emissions were observed during the previous Method 22 test. If visible emissions are observed during the follow-up Method 22 test from any stack from which visible emissions were observed during the previous Method 22 test, conduct a visual opacity test of each stack from which emissions were observed during the follow up Method 22 test in accordance with Method 9 of appendix A to part 60 of this chapter. The duration of the Method 9 test shall be 30 minutes.

(f) The owner or operator of an affected source subject to a limitation on D/F emissions shall monitor D/F emissions in accordance with paragraphs (f)(1) through (f)(6) of this section.

(1) The owner or operator shall install, calibrate, maintain, and continuously operate a continuous monitor to record the temperature of the exhaust gases from the kiln, in-line kiln/raw mill and alkali bypass, if applicable, at the inlet to, or upstream of, the kiln, in-line kiln/raw mill and/or alkali bypass PM control devices.

(i) The recorder response range must include zero and 1.5 times either of the average temperatures established according to the requirements in §63.1349(b)(3)(iv).

(ii) The reference method must be a National Institute of Standards and Technology calibrated reference thermocouple-potentiometer system or alternate reference, subject to approval by the Administrator.

(2) The owner or operator shall monitor and continuously record the temperature of the exhaust gases from the kiln, in-line kiln/raw mill and alkali bypass, if applicable, at the inlet to the kiln, in-line kiln/raw mill and/or alkali bypass PMCD.

(3) The three-hour rolling average temperature shall be calculated as the average of 180 successive one-minute average temperatures.

(4) Periods of time when one-minute averages are not available shall be ignored when calculating three-hour rolling averages. When one-minute averages become available, the first one-minute average is added to the previous 179 values to calculate the three-hour rolling average.

(5) When the operating status of the raw mill of the in-line kiln/raw mill is changed from off to on, or from on to off the calculation of the three-hour rolling average temperature must begin anew, without considering previous recordings.

(6) The calibration of all thermocouples and other temperature sensors shall be verified at least once every three months.

(g) The owner or operator of an affected source subject to an emissions limitation on D/F, THC or mercury emissions that employs carbon injection as an emission control technique shall comply with the monitoring requirements of paragraphs (f)(1) through (f)(6) and (g)(1) through (g)(6) of this section to demonstrate continuous compliance with the D/F, THC or mercury emissions standard.

(1) Install, operate, calibrate and maintain a continuous monitor to record the rate of activated carbon injection. The accuracy of the rate measurement device must be ±1 percent of the rate being measured.

(2) Verify the calibration of the device at least once every three months.

(3) The three-hour rolling average activated carbon injection rate shall be calculated as the average of 180 successive one-minute average activated carbon injection rates.

(4) Periods of time when one-minute averages are not available shall be ignored when calculating three-hour rolling averages. When one-minute averages become available, the first one-minute average is added to the previous 179 values to calculate the three-hour rolling average.

(5) When the operating status of the raw mill of the in-line kiln/raw mill is changed from off to on, or from on to off, the calculation of the three-hour rolling average activated carbon injection rate must begin anew, without considering previous recordings.

(6) The owner or operator must install, operate, calibrate and maintain a continuous monitor to record the activated carbon injection system carrier gas parameter (either the carrier gas flow rate or the carrier gas pressure drop) established during the mercury, THC or D/F performance test in accordance with paragraphs (g)(6)(i) through (g)(6)(iii) of this section.

(i) The owner or operator shall install, calibrate, operate and maintain a device to continuously monitor and record the parameter value.

(ii) The owner or operator must calculate and record three-hour rolling averages of the parameter value.

(iii) Periods of time when one-minute averages are not available shall be ignored when calculating three-hour rolling averages. When one-minute averages become available, the first one-minute average shall be added to the previous 179 values to calculate the three-hour rolling average.

(h) The owner or operator of an affected source subject to a limitation on THC emissions under this subpart shall comply with the monitoring requirements of paragraphs (h)(1) through (h)(3) of this section to demonstrate continuous compliance with the THC emission standard:

(1) The owner or operator shall install, operate and maintain a THC continuous emission monitoring system in accordance with Performance Specification 8A, of appendix B to part 60 of this chapter and comply with all of the requirements for continuous monitoring systems found in the general provisions, subpart A of this part.

(2) The owner or operator is not required to calculate hourly rolling averages in accordance with section 4.9 of Performance Specification 8A if they are only complying with the 50 ppmv THC emissions limit.

(3) For facilities complying with the 50 ppmv THC emissions limit, any thirty-day block average THC concentration in any gas discharged from a greenfield raw material dryer, the main exhaust of a greenfield kiln, or the main exhaust

of a greenfield in-line kiln/raw mill, exceeding 50 ppmvd, reported as propane, corrected to seven percent oxygen, is a violation of the standard.

(4) For new facilities complying with the 20 ppmv THC emissions limit, any hourly average THC concentration in any gas discharged from a raw material dryer, the main exhaust of a greenfield kiln, or the main exhaust of a kiln or in-line kiln/raw mill, exceeding 20 ppmvd, reported as propane, corrected to seven percent oxygen, is a violation of the standard.

(i) The owner or operator of any kiln or in-line kiln/raw mill subject to a D/F emission limit under this subpart shall conduct an inspection of the components of the combustion system of each kiln or in-line kiln raw mill at least once per year.

(j) The owner or operator of an affected source subject to a limitation on opacity under §63.1346 or §63.1348 shall monitor opacity in accordance with the operation and maintenance plan developed in accordance with paragraph (a) of this section.

(k) The owner or operator of an affected source subject to a particulate matter standard under §63.1343 shall install, calibrate, maintain, and operate a particulate matter continuous emission monitoring system (PM CEMS) to measure the particulate matter discharged to the atmosphere. All requirements relating to installation, calibration, maintenance, operation or performance of the PM CEMS and implementation of the PM CEMS requirement are deferred pending further rulemaking.

(l) An owner or operator may submit an application to the Administrator for approval of alternate monitoring requirements to demonstrate compliance with the emission standards of this subpart, except for emission standards for THC, subject to the provisions of paragraphs (l)(1) through (l)(6) of this section.

(1) The Administrator will not approve averaging periods other than those specified in this section, unless the owner or operator documents, using data or information, that the longer averaging period will ensure that emissions do not exceed levels achieved during the performance test over any increment of time equivalent to the time required to conduct three runs of the performance test.

(2) If the application to use an alternate monitoring requirement is approved, the owner or operator must continue to use the original monitoring requirement until approval is received to use another monitoring requirement.

(3) The owner or operator shall submit the application for approval of alternate monitoring requirements no later than the notification of performance test. The application must contain the information specified in paragraphs (l)(3)(i) through (l)(3)(iii) of this section:

(i) Data or information justifying the request, such as the technical or economic infeasibility, or the impracticality of using the required approach;

(ii) A description of the proposed alternative monitoring requirement, including the operating parameter to be monitored, the monitoring approach and technique, the averaging period for the limit, and how the limit is to be calculated; and

(iii) Data or information documenting that the alternative monitoring requirement would provide equivalent or better assurance of compliance with the relevant emission standard.

(4) The Administrator will notify the owner or operator of the approval or denial of the application within 90 calendar days after receipt of the original request, or within 60 calendar days of the receipt of any supplementary information, whichever is later. The Administrator will not approve an alternate monitoring application unless it would provide equivalent or better assurance of compliance with the relevant emission standard. Before disapproving any alternate monitoring application, the Administrator will provide:

(i) Notice of the information and findings upon which the intended disapproval is based; and

(ii) Notice of opportunity for the owner or operator to present additional supporting information before final action is taken on the application. This notice will specify how much additional time is allowed for the owner or operator to provide additional supporting information.

(5) The owner or operator is responsible for submitting any supporting information in a timely manner to enable the Administrator to consider the application prior to the performance test. Neither submittal of an application, nor the Administrator's failure to approve or disapprove the application relieves the owner or operator of the responsibility to comply with any provision of this subpart.

(6) The Administrator may decide at any time, on a case-by-case basis that additional or alternative operating limits, or alternative approaches to establishing operating limits, are necessary to demonstrate compliance with the emission standards of this subpart.

(m) The requirements under paragraph (e) of this section to conduct daily Method 22 testing shall not apply to any specific raw mill or finish mill equipped with a continuous opacity monitor COM or bag leak detection system (BLDS). If the owner or operator chooses to install a COM in lieu of conducting the daily visual emissions testing required under paragraph (e) of this section, then the COM must be installed at the outlet of the PM control device of the raw mill or finish mill, and the COM must be installed, maintained, calibrated, and operated as required by the general provisions in subpart A of this part and according to PS–1 of appendix B to part 60 of this chapter. To remain in compliance, the opacity must be maintained such that the 6-minute average opacity for any 6-minute block period does not exceed 10 percent. If the average opacity for any 6-minute block period exceeds 10 percent, this shall constitute a violation of the standard. If the owner or operator chooses to install a BLDS in lieu of conducting the daily visual emissions testing required under paragraph (e) of this section, the requirements in paragraphs (m)(1) through (9) of this section apply to each BLDS:

(1) The BLDS must be certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less. “Certify” shall mean that the instrument manufacturer has tested the instrument on gas streams having a range of particle size distributions and confirmed by means of valid filterable PM tests that the minimum detectable concentration limit is at or below 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(2) The sensor on the BLDS must provide output of relative PM emissions.

(3) The BLDS must have an alarm that will activate automatically when it detects a significant increase in relative PM emissions greater than a preset level.

(4) The presence of an alarm condition should be clearly apparent to facility operating personnel.

(5) For a positive-pressure fabric filter, each compartment or cell must have a bag leak detector. For a negative-pressure or induced-air fabric filter, the bag leak detector must be installed downstream of the fabric filter. If multiple bag leak detectors are required (for either type of fabric filter), detectors may share the system instrumentation and alarm.

(6) All BLDS must be installed, operated, adjusted, and maintained so that they are based on the manufacturer's written specifications and recommendations. The EPA recommends that where appropriate, the standard operating procedures manual for each bag leak detection system include concepts from EPA's “Fabric Filter Bag Leak Detection Guidance” (EPA–454/R–98–015, September 1997).

(7) The baseline output of the system must be established as follows:

(i) Adjust the range and the averaging period of the device; and

(ii) Establish the alarm set points and the alarm delay time.

(8) After initial adjustment, the range, averaging period, alarm set points, or alarm delay time may not be adjusted except as specified in the operations and maintenance plan required by paragraph (a) of this section. In no event may the range be increased by more than 100 percent or decreased by more than 50 percent over a 1 calendar year period unless a responsible official as defined in §63.2 certifies in writing to the Administrator that the fabric filter has been inspected and found to be in good operating condition.

(9) The owner or operator must maintain and operate the fabric filter such that the bag leak detector alarm is not activated and alarm condition does not exist for more than 5 percent of the total operating time in a 6-month block period. Each time the alarm activates, alarm time will be counted as the actual amount of time taken by the owner or operator to initiate corrective actions. If inspection of the fabric filter demonstrates that no corrective actions are necessary, no alarm time will be counted. The owner or operator must continuously record the output from the BLDS during periods of normal operation. Normal operation does not include periods when the BLDS is being maintained or during startup, shutdown or malfunction.

(n) Any kiln or kiln/in-line raw mill using a control device (other then ACI) to comply with a mercury emissions limit or equipment standard will monitor the control device parameters as specified in 40 CFR part 63 subpart SS.

(o) For kilns and in-line kilns/raw mills complying with the requirements in Section 63.1344(g), each owner or operator must obtain a certification from the supplier for each shipment of fly ash received to demonstrate that the fly ash was not

derived from a source in which the use of activated carbon, or any other sorbent, is used as a method of mercury emissions control. The certification shall include the name of the supplier and a signed statement from the supplier confirming that the fly ash was not derived from a source in which the use of activated carbon, or any other sorbent, is used as a method of emission control.

(p) If the facility opts to use a fly ash derived from a source in which the use of activated carbon, or any other sorbent, is used as a method of mercury emissions control and demonstrate that the use of this fly ash does not increase mercury emissions, they must obtain daily fly ash samples, composites monthly, and analyze the samples for mercury.

[64 FR 31925, June 14, 1999, as amended at 64 FR 53070, Sept. 30, 1999; 67 FR 16620, Apr. 5, 2002; 67 FR 44769, July 5, 2002; 67 FR 72585, Dec. 6, 2002; 71 FR 76551, Dec. 20, 2006]

§ 63.1351 Compliance dates.

(a) Except as noted in paragraph (c) below, the compliance date for an owner or operator of an existing affected source subject to the provisions of this subpart is June 14, 2002.

(b) Except as noted in paragraph (d) below, the compliance date for an owner or operator of an affected source subject to the provisions of this subpart that commences new construction or reconstruction after March 24, 1998, is June 14, 1999, or upon startup of operations, whichever is later.

(c) The compliance date for an existing source to meet the requirements of GCP for THC is December 20, 2007.

(d) The compliance date for a new source which commenced construction after December 2, 2005, and before December 20, 2006 to meet the THC emission limit of 20 ppmv/98 percent reduction or the mercury standard of 41 μg/dscm or a site-specific standard based on application of a wet scrubber will be December 21, 2009.

[71 FR 76552, Dec. 20, 2006]

§ 63.1352 Additional test methods.

(a) Owners or operators conducting tests to determine the rates of emission of hydrogen chloride (HCl) from kilns, in-line kiln/raw mills and associated bypass stacks at portland cement manufacturing facilities, for use in applicability determinations under §63.1340 are permitted to use Method 320 or Method 321 of appendix A of this part.

(b) Owners or operators conducting tests to determine the rates of emission of hydrogen chloride (HCl) from kilns, in-line kiln/raw mills and associated bypass stacks at portland cement manufacturing facilities, for use in applicability determinations under §63.1340 are permitted to use Methods 26 or 26A of appendix A to part 60 of this chapter, except that the results of these tests shall not be used to establish status as an area source.

(c) Owners or operators conducting tests to determine the rates of emission of specific organic HAP from raw material dryers, kilns and in-line kiln/raw mills at portland cement manufacturing facilities, for use in applicability determinations under §63.1340 of this subpart are permitted to use Method 320 of appendix A to this part, or Method 18 of appendix A to part 60 of this chapter.

Notification, Reporting and Recordkeeping

§ 63.1353 Notification requirements.

(a) The notification provisions of 40 CFR part 63, subpart A that apply and those that do not apply to owners and operators of affected sources subject to this subpart are listed in Table 1 of this subpart. If any State requires a notice that contains all of the information required in a notification listed in this section, the owner or operator may send the Administrator a copy of the notice sent to the State to satisfy the requirements of this section for that notification.

(b) Each owner or operator subject to the requirements of this subpart shall comply with the notification requirements in §63.9 as follows:

(1) Initial notifications as required by §63.9(b) through (d). For the purposes of this subpart, a Title V or 40 CFR part 70 permit application may be used in lieu of the initial notification required under §63.9(b), provided the same information is contained in the permit application as required by §63.9(b), and the State to which the permit application has been submitted has an approved operating permit program under part 70 of this chapter and has received delegation of authority from the EPA. Permit applications shall be submitted by the same due dates as those specified for the initial notification.

(2) Notification of performance tests, as required by §§63.7 and 63.9(e).

(3) Notification of opacity and visible emission observations required by §63.1349 in accordance with §§63.6(h)(5) and 63.9(f).

(4) Notification, as required by §63.9(g), of the date that the continuous emission monitor performance evaluation required by §63.8(e) is scheduled to begin.

(5) Notification of compliance status, as required by §63.9(h).

§ 63.1354 Reporting requirements.

(a) The reporting provisions of subpart A of this part that apply and those that do not apply to owners or operators of affected sources subject to this subpart are listed in Table 1 of this subpart. If any State requires a report that contains all of the information required in a report listed in this section, the owner or operator may send the Administrator a copy of the report sent to the State to satisfy the requirements of this section for that report.

(b) The owner or operator of an affected source shall comply with the reporting requirements specified in §63.10 of the general provisions of this part 63, subpart A as follows:

(1) As required by §63.10(d)(2), the owner or operator shall report the results of performance tests as part of the notification of compliance status.

(2) As required by §63.10(d)(3), the owner or operator of an affected source shall report the opacity results from tests required by §63.1349.

(3) As required by §63.10(d)(4), the owner or operator of an affected source who is required to submit progress reports as a condition of receiving an extension of compliance under §63.6(i) shall submit such reports by the dates specified in the written extension of compliance.

(4) As required by §63.10(d)(5), if actions taken by an owner or operator during a startup, shutdown, or malfunction of an affected source (including actions taken to correct a malfunction) are consistent with the procedures specified in the source's startup, shutdown, and malfunction plan specified in §63.6(e)(3), the owner or operator shall state such information in a semiannual report. Reports shall only be required if a startup, shutdown, or malfunction occurred during the reporting period. The startup, shutdown, and malfunction report may be submitted simultaneously with the excess emissions and continuous monitoring system performance reports; and

(5) Any time an action taken by an owner or operator during a startup, shutdown, or malfunction (including actions taken to correct a malfunction) is not consistent with the procedures in the startup, shutdown, and malfunction plan, the owner or operator shall make an immediate report of the actions taken for that event within 2 working days, by telephone call or facsimile (FAX) transmission. The immediate report shall be followed by a letter, certified by the owner or operator or other responsible official, explaining the circumstances of the event, the reasons for not following the startup, shutdown, and malfunction plan, and whether any excess emissions and/or parameter monitoring exceedances are believed to have occurred.

(6) As required by §63.10(e)(2), the owner or operator shall submit a written report of the results of the performance evaluation for the continuous monitoring system required by §63.8(e). The owner or operator shall submit the report simultaneously with the results of the performance test.

(7) As required by §63.10(e)(2), the owner or operator of an affected source using a continuous opacity monitoring system to determine opacity compliance during any performance test required under §63.7 and described in §63.6(d)(6) shall report the results of the continuous opacity monitoring system performance evaluation conducted under §63.8(e).

(8) As required by §63.10(e)(3), the owner or operator of an affected source equipped with a continuous emission monitor shall submit an excess emissions and continuous monitoring system performance report for any event when the continuous monitoring system data indicate the source is not in compliance with the applicable emission limitation or operating parameter limit.

(9) The owner or operator shall submit a summary report semiannually which contains the information specified in §63.10(e)(3)(vi). In addition, the summary report shall include:

(i) All exceedences of maximum control device inlet gas temperature limits specified in §63.1344(a) and (b);

(ii) All failures to calibrate thermocouples and other temperature sensors as required under §63.1350(f)(7) of this subpart; and

(iii) All failures to maintain the activated carbon injection rate, and the activated carbon injection carrier gas flow rate or pressure drop, as applicable, as required under §63.1344(c).

(iv) The results of any combustion system component inspections conducted within the reporting period as required under §63.1350(i).

(v) All failures to comply with any provision of the operation and maintenance plan developed in accordance with §63.1350(a).

(10) If the total continuous monitoring system downtime for any CEM or any continuous monitoring system (CMS) for the reporting period is ten percent or greater of the total operating time for the reporting period, the owner or operator shall submit an excess emissions and continuous monitoring system performance report along with the summary report.

§ 63.1355 Recordkeeping requirements.

(a) The owner or operator shall maintain files of all information (including all reports and notifications) required by this section recorded in a form suitable and readily available for inspection and review as required by §63.10(b)(1). The files shall be retained for at least five years following the date of each occurrence, measurement, maintenance, corrective action, report, or record. At a minimum, the most recent two years of data shall be retained on site. The remaining three years of data may be retained off site. The files may be maintained on microfilm, on a computer, on floppy disks, on magnetic tape, or on microfiche.

(b) The owner or operator shall maintain records for each affected source as required by §63.10(b)(2) and (b)(3) of this part; and

(1) All documentation supporting initial notifications and notifications of compliance status under §63.9;

(2) All records of applicability determination, including supporting analyses; and

(3) If the owner or operator has been granted a waiver under §63.8(f)(6), any information demonstrating whether a source is meeting the requirements for a waiver of recordkeeping or reporting requirements.

(c) In addition to the recordkeeping requirements in paragraph (b) of this section, the owner or operator of an affected source equipped with a continuous monitoring system shall maintain all records required by §63.10(c).

(d) You must keep annual records of the amount of CKD which is removed from the kiln system and either disposed of as solid waste or otherwise recycled for a beneficial use outside of the kiln system.

(e) You must keep records of the amount of CKD recycled on an hourly basis.

(f) You must keep records of all fly ash supplier certifications as required by §63.1350(o).

[64 FR 31925, June 14, 1999, as amended at 71 FR 76552, Dec. 20, 2006]

Other

§ 63.1356 Exemption from new source performance standards.

(a) Except as provided in paragraphs (a)(1) and (2) of this section, any affected source subject to the provisions of this subpart is exempt from any otherwise applicable new source performance standard contained in subpart F or subpart OOO of part 60 of this chapter.

(1) Kilns and in-line kiln/raw mills, as applicable, under 40 CFR 60.60(b), located at area sources are subject to PM and opacity limits and associated reporting and recordkeeping, under 40 CFR part 60, subpart F.

(2) Greenfield raw material dryers, as applicable under 40 CFR 60.60(b), located at area sources, are subject to opacity limits and associated reporting and recordkeeping under 40 CFR part 60, subpart F.

(b) The requirements of subpart Y of part 60 of this chapter, “Standards of Performance for Coal Preparation Plants,” do not apply to conveying system transfer points used to convey coal from the mill to the kiln that are associated with coal preparation at a portland cement plant that is a major source under this subpart.

[64 FR 31925, June 14, 1999, as amended at 67 FR 16622, Apr. 5, 2002; 71 FR 76552, Dec. 20, 2006]

§ 63.1357 Temporary, conditioned exemption from particulate matter and opacity standards.

(a) Subject to the limitations of paragraphs (b) through (f) of this section, an owner or operator conducting PM CEMS correlation tests (that is, correlation with manual stack methods) is exempt from:

(1) Any particulate matter and opacity standards of part 60 or part 63 of this chapter that are applicable to cement kilns and in-line kiln/raw mills.

(2) Any permit or other emissions or operating parameter or other limitation on workplace practices that are applicable to cement kilns and in-line kiln raw mills to ensure compliance with any particulate matter and opacity standards of this part or part 60 of this chapter.

(b) The owner or operator must develop a PM CEMS correlation test plan. The plan must be submitted to the Administrator for approval at least 90 days before the correlation test is scheduled to be conducted. The plan must include:

(1) The number of test conditions and the number of runs for each test condition;

(2) The target particulate matter emission level for each test condition;

(3) How the operation of the affected source will be modified to attain the desired particulate matter emission rate; and

(4) The anticipated normal particulate matter emission level.

(c) The Administrator will review and approve or disapprove the correlation test plan in accordance with §63.7(c)(3)(i) and (iii). If the Administrator fails to approve or disapprove the correlation test plan within the time period specified in §63.7(c)(3)(iii), the plan shall be considered approved, unless the Administrator has requested additional information.

(d) The stack sampling team must be on-site and prepared to perform correlation testing no later than 24 hours after operations are modified to attain the desired particulate matter emissions concentrations, unless the correlation test plan documents that a longer period is appropriate.

(e) The PM and opacity standards and associated operating limits and conditions will not be waived for more than 96 hours, in the aggregate, for the purposes of conducting tests to correlate PM CEMS with manual method test results, including all runs and conditions, except as described in this paragraph. Where additional time is required to correlate a PM CEMS device, a source may petition the Administrator for an extension of the 96-hour aggregate waiver of compliance with the PM and opacity standards. An extension of the 96-hour aggregate waiver is renewable at the discretion of the Administrator.

(f) The owner or operator must return the affected source to operating conditions indicative of compliance with the applicable particulate matter and opacity standards as soon as possible after correlation testing is completed.

[64 FR 31925, June 14, 1999, as amended at 67 FR 16622, Apr. 5, 2002]

§ 63.1358 Implementation and enforcement.

(a) This subpart can be implemented and enforced by the U.S. EPA, or a delegated authority such as the applicable State, local, or Tribal agency. If the U.S. EPA Administrator has delegated authority to a State, local, or Tribal agency, then that agency, in addition to the U.S. EPA, has the authority to implement and enforce this subpart. Contact the applicable U.S. EPA Regional Office to find out if this subpart is delegated to a State, local, or Tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or Tribal agency under subpart E of this part, the authorities contained in paragraph (c) of this section are retained by the Administrator of U.S. EPA and cannot be transferred to the State, local, or Tribal agency.

(c) The authorities that cannot be delegated to State, local, or Tribal agencies are as specified in paragraphs (c)(1) through (4) of this section.

(1) Approval of alternatives to the requirements in §§63.1340, 63.1342 through 63.1348, and 63.1351.

(2) Approval of major alternatives to test methods under §63.7(e)(2)(ii) and (f), as defined in §63.90, and as required in this subpart.

(3) Approval of major alternatives to monitoring under §63.8(f), as defined in §63.90, and as required in this subpart.

(4) Approval of major alternatives to recordkeeping and reporting under §63.10(f), as defined in §63.90, and as required in this subpart.

[68 FR 37359, June 23, 2003]

§ 63.1359 [Reserved]

Table 1 to Subpart LLL of Part 63—Applicability of General Provisions

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.6(b)(6)		No	[Reserved]
63.6(b)(7)	Compliance Dates	Yes	
63.6(c)(1)–(2)	Compliance Dates	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.6(c)(3)–(4)		No	[Reserved]
63.6(c)(5)	Compliance Dates	Yes	
63.6(d)		No	[Reserved]
63.6(e)(1)–(2)	Operation & Maintenance	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.6(e)(3)	Startup, Shutdown Malfunction Plan	Yes	
63.6(f)(1)–(3)	Compliance with Emission Standards	Yes	
63.6(g)(1)–(3)	Alternative Standard	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.6(h)(1)–(2)	Opacity/VE Standards	Yes	
63.6(h)(3)		No	[Reserved]
63.6(h)(4)–(h)(5)(i)	Opacity/VE Standards	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.6(h)(5)(ii)–(iv)	Opacity/VE Standards	No	Test duration specified in subpart LLL.
63.6(h)(6)	Opacity/VE Standards	Yes	
63.6(h)(7)	Opacity/VE Standards	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.6(i)(1)–(14)	Extension of Compliance	Yes	
63.6(i)(15)		No	[Reserved]
63.6(i)(16)	Extension of Compliance	Yes	
63.6(j)	Exemption from Compliance	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.7(a)(1)–(3)	Performance Testing Requirements	Yes	§63.1349 has specific requirements.
63.7(b)	Notification	Yes	
63.7(c)	Quality Assurance/Test Plan	Yes	
63.7(d)	Testing Facilities	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.7(e)(1)–(4)	Conduct of Tests	Yes	
63.7(f)	Alternative Test Method	Yes	
63.7(g)	Data Analysis	Yes	
63.7(h)	Waiver of Tests	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.8(a)(1)	Monitoring Requirements	Yes	
63.8(a)(2)	Monitoring	No	§63.1350 includes CEMS requirements.
63.8(a)(3)		No	[Reserved]
63.8(a)(4)	Monitoring	No	Flares not applicable.

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.8(b)(1)–(3)	Conduct of Monitoring	Yes	
63.8(c)(1)–(8)	CMS Operation/Maintenance	Yes	Performance specification supersedes requirements for THC CEMS Temperature and activated carbon injection monitoring data reduction requirements given in subpart LLL.

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.8(d)	Quality Control	Yes	
63.8(e)	Performance Evaluation for CMS	Yes	Performance specification supersedes requirements for THC CEMS.
63.8(f)(1)–(5)	Alternative Monitoring Method	Yes	Additional requirements in §63.1350(l).

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.8(f)(6)	Alternative to RATA Test	Yes	
63.8(g)	Data Reduction	Yes	
63.9(a)	Notification Requirements	Yes	
63.9(b)(1)–(5)	Initial Notifications	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.9(c)	Request for Compliance Extension	Yes	
63.9(d)	New Source Notification for Special Compliance Requirements	Yes	
63.9(e)	Notification of Performance Test	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.9(f)	Notification of VE/Opacity Test	Yes	Notification not required for VE/opacity test under §63.1350(e) and (j).
63.9(g)	Additional CMS Notifications	Yes	
63.9(h)(1)–(3)	Notification of Compliance Status	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.9(h)(4)		No	[Reserved]
63.9(h)(5)–(6)	Notification of Compliance Status	Yes	
63.9(i)	Adjustment of Deadlines	Yes	
63.9(j)	Change in Previous Information	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.10(a)	Recordkeeping/Reporting	Yes	
63.10(b)	General Requirements	Yes	
63.10(c)(1)	Additional CMS Recordkeeping	Yes	PS–8A supersedes requirements for THC CEMS.
63.10(c)(2)–(4)		No	[Reserved]

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.10(c)(5)–(8)	Additional CMS Recordkeeping	Yes	PS–8A supersedes requirements for THC CEMS.
63.10(c)(9)		No	[Reserved]
63.10(c)(10)–(15)	Additional CMS Recordkeeping	Yes	PS–8A supersedes requirements for THC CEMS.

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.10(d)(1)	General Reporting Requirements	Yes	
63.10(d)(2)	Performance Test Results	Yes	
63.10(d)(3)	Opacity or VE Observations	Yes	
63.10(d)(4)	Progress Reports	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.10(d)(5)	Startup, Shutdown, Malfunction Reports	Yes	
63.10(e)(1)–(2)	Additional CMS Reports	Yes	
63.10(e)(3)	Excess Emissions and CMS	Yes	Exceedances are defined in subpart LLL.

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
	Performance Reports		
63.10(f)	Waiver for Recordkeeping/Reporting	Yes	
63.11(a)–(b)	Control Device Requirements	No	Flares not applicable.
63.12(a)–(c)	State Authority and Delegations	Yes	

Citation	Requirement	Applies to Subpart LLL	Explanation
63.1(a)(1)–(4)	Applicability	Yes	
63.1(a)(5)		No	[Reserved]
63.1(a)(6)–(8)	Applicability	Yes	
63.1(a)(9)		No	[Reserved]
63.1(a)(10)–(14)	Applicability	Yes	
63.1(b)(1)	Initial Applicability Determination	No	§63.1340 specifies applicability.
63.1(b)(2)–(3)	Initial Applicability Determination	Yes	
63.1(c)(1)	Applicability After Standard Established	Yes	
63.1(c)(2)	Permit Requirements	Yes	Area sources must obtain Title V permits.
63.1(c)(3)		No	[Reserved]
63.1(c)(4)–(5)	Extensions, Notifications	Yes	
63.1(d)		No	[Reserved]
63.1(e)	Applicability of Permit Program	Yes	
63.2	Definitions	Yes	Additional definitions in §63.1341.
63.3(a)–(c)	Units and Abbreviations	Yes	
63.4(a)(1)–(3)	Prohibited Activities	Yes	
63.4(a)(4)		No	[Reserved]
63.4(a)(5)	Compliance date	Yes	
63.4(b)–(c)	Circumvention, Severability	Yes	
63.5(a)(1)–(2)	Construction/Reconstruction	Yes	
63.5(b)(1)	Compliance Dates	Yes	
63.5(b)(2)		No	[Reserved]
63.5(b)(3)–(6)	Construction Approval, Applicability	Yes	
63.5(c)		No	[Reserved]
63.5(d)(1)–(4)	Approval of Construction/Reconstruction	Yes	
63.5(e)	Approval of Construction/Reconstruction	Yes	
63.5(f)(1)–(2)	Approval of Construction/Reconstruction	Yes	
63.6(a)	Compliance for Standards and Maintenance	Yes	
63.6(b)(1)–(5)	Compliance Dates	Yes	
63.13(a)–(c)	State/Regional Addresses	Yes	
63.14(a)–(b)	Incorporation by Reference	Yes	
63.15(a)–(b)	Availability of Information	Yes	