COMMISSION

Kevin Beckner
Victor D. Crist
Ken Hagan
Al Higginbotham
Lesley "Les" Miller, Jr.
Sandra L. Murman
Stacy White

EXECUTIVE DIRECTOR
Richard D. Garrity, Ph.D.

DIVISION DIRECTORS

Legal & Admin. — Richard Tschantz, Esq.
Air Management — Jerry Campbell, P.E.
Waste Management — Hooshang Boostani, P.E.
Water Management — Sam Elrabi, P.E.
Wetlands Management — Scott Emery, Ph.D.

ENVIRONMENTAL PROTECTION COMMISSION OF
HILLSBOROUGH COUNTY, as Delegated by

STATE OF FLORIDA
DEPARTMENT OF ENVIRONMENTAL PROTECTION

NOTICE OF PERMIT

Mr. Harrinarine Mootoor
Argos Cement, LLC
2001 Maritime Blvd.
Tampa, FL 33605

Dear Mr. Mootoor:

Enclosed is Air Construction Permit Number No. 0570018-024-AC to construct the bulk fine and bulk coarse/granular railcar loading and unloading operation at your facility. Also included in this permit are multiple modifications to existing emissions units. This permit is being issued pursuant to Section 403.087, Florida Statutes.

Any party to this order (permit) has the right to seek judicial review of the permit pursuant to Section 120.68, Florida Statutes, by the filing of a Notice of Appeal pursuant to Rule 9.110, Florida Rules of Appellate Procedure, with the Clerk of the EPC in the Legal Department at 3629 Queen Palm Drive, Tampa, FL 33619; and by filing a copy of the Notice of Appeal accompanied by the applicable filing fees with the appropriate District Court of Appeal. The Notice of Appeal must be filed within 30 days from the date this Notice is filed with the clerk of the EPC.

Executed in Tampa, Florida.

Sincerely,

Richard D. Garrity, Ph.D.
Executive Director

cc: FDEP Southwest District (posting online)
John Koogler, Ph.D., P.E. - Koogler and Associates, Inc. (via e-mail)

CERTIFICATE OF SERVICE

This is to certify that this NOTICE OF PERMIT and all copies were mailed before the close of business on 9/16/14 to the listed persons.

Clerk Stamp
FILED, on this date, pursuant to Section 120.52(7), Florida Statutes, with the designated clerk, receipt of which is hereby acknowledged.

Patricia S. Fons 9/16/14
Clerk Date

COMMISSION

Kevin Beckner
Victor D. Crist
Ken Hagan
Al Higginbotham
Lesley "Les" Miller, Jr.
Sandra L. Murman
Stacy White

EXECUTIVE DIRECTOR
Richard D. Garrity, Ph.D.

DIVISION DIRECTORS

Legal & Admin. — Richard Tschantz, Esq.
Air Management — Jerry Campbell, P.E.
Waste Management — Hooshang Boostani, P.E.
Water Management — Sam Elrabi, P.E.
Wetlands Management — Scott Emery, Ph.D.

PERMITTEE:

Argos Cement, LLC
2001 Maritime Blvd.
Tampa, FL 33605

PERMIT/CERTIFICATION

Permit No.: 0570018-024-AC
County: Hillsborough
Expiration Date: January 6, 2016
Project: Railcar Loading and Unloading Operation and Miscellaneous Modifications

This permit is issued under the provisions of Chapter 403, Florida Statutes, and Florida Administrative Code Rules 62-204, 62-210, 62-212, 62-296, 62-297, and 62-4. The above named permittee is hereby authorized to perform the work or operate the facility shown on the application and approved drawing(s), plans, and other documents, attached hereto or on file with the EPC and made a part hereof and specifically described as follows:

The facility (formerly known as LaFarge) is a bulk cement and aggregate material handling and packaging facility currently comprised of 44 different emission units. The plant receives various cementitious and aggregate products from ships or trucks for processing and shipment off-site by truck or ship. The raw products are dried in a dryer, ground, and blended in finish mills, as needed. The materials are then further blended to the desired cementitious mixture in the blending plant, if needed. The final product can be bulk loaded into trucks or ships for shipment off-site, or packaged into various sized bags for shipment via truck or ship. This Permit authorizes construction of air slides from the Old Bulk Silo Nos. 21 – 24 which will transfer material from the silos to the Packhouse airslide to feed the rotary packer. In addition, this permit authorizes the construction of a railcar loading and unloading operation and multiple modifications to existing emissions units as follows:

1) **Rail Line Project:**

Railcar Unloading

a) Argos Cement, LLC is proposing for the railcars to hook into the existing 4 truck unloading lines into Silo 27 or Silo 28 to offload at a max throughput rate of 240 TPH (60 TPH per railcar). Emissions would be controlled by BH 42 (EU 042) and BH 43 (EU 043).

b) Argos Cement, LLC is proposing to add a "T" junction from the existing four (4) truck unloading lines to Silo 27 or Silo 28 that will feed directly to the transfer air slide to unload material into the finish mill feed silos. Emissions will be controlled by BH 12 (EU 012).

A) Daily (if operating)
   (1) Day, Month, Year
   (2) Pressure drop [inches H_2O] across each baghouse as required by the current Operation and Maintenance Plan
   (3) Result of each instantaneous visual emissions determination on each emissions unit with a baghouse as required by the current Operation and Maintenance Plan
B) Monthly
   (1) Month, Year
   (2) Amount of bulk fine and bulk coarse/granular materials received by railcar during the month [tons] and the most recent consecutive twelve month period [tons/12 months]
   (3) The amount of bulk fine and bulk coarse/granular materials loaded into railcars/trucks during the month [tons] and the most recent consecutive twelve month period [tons/12 months]
   (4) Hours of operation for each type of operation under this Subsection (railcar loading, truck loading, transfer, etc.) during each month [hours/month] and the most recent consecutive twelve month period [tons/12 months]
   (5) Total hours of operation for the portable 15,000 acfm baghouse during each month [hours/month] and the most recent consecutive twelve month period [tons/12 months]

[Rules 62-213.440(1)(b), 62-4.070(3) and 62-4.160(14), F.A.C.]

ENVIRONMENTAL PROTECTION COMMISSION
OF HILLSBOROUGH COUNTY

Richard D. Garrity, Ph.D.
Executive Director