



COMMISSION

Kevin Beckner Lesley "Les" Miller, Jr.
Victor D. Crist Sandra L. Murman
Ken Hagan Stacy White
Al Higginbotham

EXECUTIVE DIRECTOR
Janet Dougherty

DIVISION DIRECTORS

Legal & Admin.	Richard Tschantz, Esq.
Air Management	Jerry Campbell, P.E.
Waste Management	Hooshang Boostani, P.E.
Water Management	Sam Elrabi, P.E.
Wetlands Management	Scott Emery, Ph.D.

ENVIRONMENTAL PROTECTION COMMISSION OF
HILLSBOROUGH COUNTY, as Delegated by

STATE OF FLORIDA
DEPARTMENT OF ENVIRONMENTAL PROTECTION

NOTICE OF PERMIT

Mr. Terry Bennett
Argos Cement, LLC
2001 Maritime Blvd.
Tampa, FL 33605


Dear Mr. Bennett:

Enclosed is Air Construction Permit Number No. 0570018-025-AC for the addition of two supersax transloaders at your facility. This permit is being issued pursuant to Section 403.087, Florida Statutes.

Any party to this order (permit) has the right to seek judicial review of the permit pursuant to Section 120.68, Florida Statutes, by the filing of a Notice of Appeal pursuant to Rule 9.110, Florida Rules of Appellate Procedure, with the Clerk of the EPC in the Legal Department at 3629 Queen Palm Drive, Tampa, FL 33619; and by filing a copy of the Notice of Appeal accompanied by the applicable filing fees with the appropriate District Court of Appeal. The Notice of Appeal must be filed within 30 days from the date this Notice is filed with the clerk of the EPC.

Executed in Tampa, Florida.

Sincerely,


Janet L. Dougherty
Executive Director

JDL/SN/sn


cc: FDEP Southwest District (posting online)
Pradeep Raval - Koogler and Associates, Inc. (via e-mail)

CERTIFICATE OF SERVICE

This is to certify that this NOTICE OF PERMIT and all copies were mailed before the close of business on 9/16/2015 to the listed persons.

Clerk Stamp

FILED, on this date, pursuant to Section 120.52(7), Florida Statutes, with the designated clerk, receipt of which is hereby acknowledged.



Clerk

9/16/2015

Date



COMMISSION

Kevin Beckner Lesley "Les" Miller, Jr.
Victor D. Crist Sandra L. Murman
Ken Hagan Stacy White
Al Higginbotham

DIVISION DIRECTORS

Legal & Admin. Richard Tschantz, Esq.
Air Management Jerry Campbell, P.E.
Waste Management Hooshang Boostani, P.E.
Water Management Sam Elrabi, P.E.
Wetlands Management Scott Emery, Ph.D.

EXECUTIVE DIRECTOR
Janet Dougherty

PERMITTEE:

Argos Cement, LLC
2001 Maritime Blvd.
Tampa, FL 33605

PERMIT/CERTIFICATION

Permit No.: 0570018-025-AC
County: Hillsborough
Expiration Date: February 14, 2016
Project: Addition of Two Supersax Transloaders

This permit is issued under the provisions of Chapter 403, Florida Statutes, and Florida Administrative Code Rules 62-204, 62-210, 62-212, 62-296, 62-297, and 62-4. The above named permittee is hereby authorized to perform the work or operate the facility shown on the application and approved drawing(s), plans, and other documents, attached hereto or on file with the EPC and made a part hereof and specifically described as follows:

The facility is a bulk cement and aggregate material handling, processing, and packaging facility. The plant receives various cementitious and aggregate products from ships, trucks, or railcars for processing and shipment off-site by truck, ship, or railcar. The raw products are dried in a dryer, ground, and blended in finish mills, as needed. The materials are then further blended to the desired cementitious mixtures in the blending plant, if needed. The final product can be bulk loaded into trucks, ships, or railcars for shipment off-site, or packaged into various sized bags for shipment off-site.

Argos is authorized use two supersax transloaders at the facility. Each transloader will transfer approximately 100 tons per hour of fine material from supersax into railcars, trucks or silos. The Bazooka Tube Supersax 1200 transloader or equivalent loads super sack bulk products into truck or railcar and the SupersaxX Trans Pod System transloader or equivalent loads super sack products into silos. The units, which may be purchased or rented, will be 80 hp and can be either electric or diesel powered. Each unit will operate for no more than 3,000 hours per year.

The facility will be able to load supersacks into any existing silo, as needed. The availability of a silo for storage of a certain product is often determined by market conditions, material cross-contamination issues and maintenance schedules. The Particulate Matter (PM) emissions from the material transfer operation will be controlled by an integral dust collector on each transloader.

The facility is subject to PM RACT (Rule 62-296.700, F.A.C.) and Chapter 1-3.52, Rules of the EPC.

Location: 2001 Maritime Blvd., Tampa

UTM: 17-357.9E 3090.7N FACILITY ID NO: 0570018

An agency with values of environmental stewardship, fairness, and cooperation

Roger P. Stewart Center

3629 Queen Palm Drive, Tampa, FL 33619 - (813) 627-2600 - www.epchc.org

An Affirmative Action / Equal Opportunity Employer

PERMITTEE:
Argos Cement, LLC

PERMIT CERTIFICATION NO.: 0570018-025-AC
PROJECT: Addition of Two Supersax Transloaders

H.11. The required minimum period of observation for an EPA Method 9 compliance test shall be thirty (30) minutes. If the operation is completed within less than the minimum observation period, the period of observation shall include each occurrence of the operation during the minimum observation period. The opacity test observation period shall include the period during which the highest opacity emissions can reasonably be expected to occur. [Rule 62-297.310(5)(b), F.A.C.]


H.12. Testing of emissions shall be conducted with the sources operating at capacity. Capacity is defined as 90-100% of the material handling of 100 tons per hour. If it is impracticable to test at capacity, then the source may be tested at less than capacity; in this case subsequent source operation is limited to 110% of the test load until a new test is conducted. Once the unit is so limited, then operation at higher capacities is allowed for no more than fifteen days for purposes of additional compliance testing to regain the rated capacity in the permit, with prior notification to the Environmental Protection Commission of Hillsborough County. Failure to submit the input rates and actual operating conditions, including pressure differential across the baghouse, may invalidate the test. [Rule 62-297.310(3), F.A.C., Construction Permit Application Received on July 13, 2015]

H.13. The permittee shall maintain records to demonstrate compliance with the requirements of Specific Condition Nos. H.2 and H.4. The records shall include, as a minimum, the following information and shall be made available for inspection by the Environmental Protection Commission of Hillsborough County for at least five years:

- A) Month, Year
- B) Amount and type of material transloaded (tons)
- C) Hours of operation of each supersax transloader
- D) Hours of operation of each diesel engine
- E) Amount of fuel usage for each portable diesel engine
- F) Twelve month rolling total of C), D), E) and F) above

[Rules 62-213.440(1)(b), 62-4.070(3) and 62-4.160(14), F.A.C.; Permit No. 0570018-024-AC; and Construction Permit Application received July 13, 2015]

ENVIRONMENTAL PROTECTION COMMISSION
OF HILLSBOROUGH COUNTY


Janet L. Dougherty
Executive Director