BEST AVAILABLE COPY

LAW OFFICES

OERTEL, HOFFMAN, FERNANDEZ & COLE, P.A.

301 SOUTH BRONOUGH STREET

SUITE 500

TALLAHASSEE, FLORIDA 32301

MAILING ADDRESS:

POST OFFICE BOX 1110

TALLAHASSEE, FLORIDA 32302-1110

http://www.onfc.com

OCT 3 U 2000

October 27, 2000

CAN'T DE ELOCIDIVIA Hand Delivery

Mr. Howard C. Rhodes, Director Division of Air Resource Management Florida Department of Environmental Protection 111 S. Magnolia Drive - Suite 23 Tallahassee, FL 32301

Re:

TIMOTHY P. ATKINSON

M. CHRISTOPHER BRYANT

C. ANTHONY CLEVELAND

SEGUNDO J. FERNANDEZ

PATRICIA A. RENOVITCH

JEFFREY BROWN

SCOTT W. FOLTZ KENNETH F. HOFFMAN CHRISTOPHER D. JOHNSTON KENNETH G. OERTEL

TERRY COLE

Florida Rock Industries, Inc.

Thompson S. Baker Cement Plant, Newberry

SO2 Continuous Emission Monitoring

FDEP Permit No. AC01-267311; PSD-FL-228

Dear Mr. Rhodes:

The purpose of this letter is to update you on the status of the continuous emission monitoring for sulfur dioxide (SO2) at the Thompson S. Baker Cement Plant in Newberry, Florida.

A continuous emission monitor supplied by Air World is presently installed and working well to measure the SO2 emissions from the kiln/raw mill stack. This is a stand-alone unit with its own sampling system. It was installed and calibrated on August 9, 2000. It is on loan from the supplier, Air World, until a replacement arrives, to be manufactured by SICK USA.

The unit originally supplied to measure SO2 was also supplied by Air World, and was installed on or about the last half of June, 2000. It was in the form of a cell, as part of a multi gas component system. Certification of the SO2 CEM component was attempted in early July, 2000. The NOx CEM component was certified on July 14, 2000, and has been working as designed since then.

While NOx has been accurately measured on a continuous basis by the appropriate CEM component, the SO2 instrument exhibited excessive drift and was ultimately rejected as unacceptable and unreliable to be used as a scientific measuring device for the purpose it was installed. Essentially, the company was unable to certify the SO2 CEM because neither the stability nor the accuracy of the instrument could be established and maintained.

The loaner unit is being replaced by an instrument manufactured in Minnesota by SICK USA. The new instrument is scheduled to arrive in Newberry in the 2nd half of November 2000 and will be in service shortly thereafter.

Howard Rhodes, Director October 27, 2000 Page 2

The Jacksonville FDEP Office was notified by FRI's consultant of the plan and that office understood and did not raise any other questions. The kiln at the FRI facility was shut-down today for a 10-day maintenance period. It is scheduled to be restarted on or about Wednesday, November 8, 2000. The company will commence a 7-day drift test on the loaner instrument now in use, and we expect that it will be certified by November 15, 2000. FRI could keep this unit in service indefinitely, as it is certain that it is reliable. Nevertheless, the company prefers to upgrade to a SICK analyzer, which has now received EPA approval. That CEM will be certified upon installation.

SO2 emissions continue to be at extremely low levels. To demonstrate compliance with the SO2 limits in the permit, the company conducted an SO2 Compliance Stack Test on July 13, 2000, and the results were reported to FDEP on August 28, 2000. The SO2 compliance test reported on August 28, 2000, demonstrated an average emission rate of 1.4 lbs/hour compared to an allowable 28.8 lbs/hour.

I hope that this information will serve to keep you and your staff informed as to the status of the SO2 CEMs at the Newberry facility. Please let me know if you have any questions or comments.

Sincerely,

Segunda I Fernande

c: Kirby Green, Deputy Secretary, FDEP
Christopher L. Kirts, Air Program Administer
Al Linero, P.E., Administrator
Fred W. Cohrs, Vice President, FRI
John B. Koogler, Ph.D., P.E.
Timothy P. Atkinson

F:\Document\TPA\LTR\Rhodes.ltr10-26-00.wpd