Golder Associates Inc.

6241 NW 23rd Street, Suite 500 Gainesville, FL 32653-1500 Telephone (352) 336-5600 Fax (352) 336-6603



March 23, 2008

063-7643

, <u>;</u>

Florida Department of Environmental Protection 2600 Blair Stone Road Tallahassee, FL 32399-2400

RECEIVED

Attention: Scott M. Sheplak, P.E.

MAR 24 2009

BURGEAU OF AIR REGULATION

RE: DRAFT PERMIT NO. 0570008-061-AC

BART EXEMPTION PROJECT

MOSAIC FERTILIZER, LLC, RIVERVIEW FACILITY

Dear Mr. Sheplak:

Mosaic Fertilizer, LLC (Mosaic) has received Florida Department of Environmental Protection's (FDEP) draft permit for the best available retrofit technology (BART) exemption project. We have reviewed the draft permit in detail and have developed several comments. The comments are presented below.

Page 6, Condition 1: The current TV permit is permit No. 0570008-051-AV.

Page 8 of 13: Under descriptions for the EUs, the current catalyst loadings for No. 7 SAP do not correspond to the BART exemption application, which shows 102,000 liters in the 1st pass, 112,000 liters in the 2nd pass, 155,000 liters in the 3rd pass, and 209,000 liters in the 4th pass, for a total of 578,000 liters. Also, in the paragraph under Stack Parameters, the second sentence should read "SAP Nos. 7, 8, and 9" (SAP No. 7 is left out).

Page 9, Condition 5: Condition 5 references that future catalyst loadings should be stated as "approximately", per the BART exemption application. The permit should also allow higher catalyst loadings if these are necessary in order to meet the BART emission limits.

Page 10, Condition 6: The wording of this condition does not necessarily have to be changed, but Mosaic would like to clarify that this condition does not mean that a specific supplier (i.e., Haldor Topsoe) must be used unless written approval is obtained from FDEP. A specific catalyst supplier should not be specified in the permit. The condition should only refer to the specific catalyst loadings and type of catalyst (i.e., vanadium or cesium-enhanced catalyst).

Page 10, Conditions 9 and 10. It should be clarified that the 24-hour (daily) block average can start and end at a time selected by the permittee (i.e., the block does not have to be from midnight to midnight; another 24-hour block, i.e., 6 am to 6 am, may be selected).

Page 12, Condition 19: It should be clarified that the final compliance date for complying with the sulfur dixoide (SO₂), sulfuric acid mist (SAM), and visible emission limits is June 30, 2013, coinciding with the permit expiration date. Condition C.19 states that the new SAM limits must be met by April 1, 2012 (since initial compliance testing must be conducted); Condition C.21 states that all construction must be completed by December 31, 2012; and Condition C.9 states that the permittee must comply with the new SO₂ limit using continuous emission monitoring systems, but it

does not state when. The compliance deadline should be after all construction is complete. Therefore, it is suggested that the initial compliance testing, completion of construction, and compliance with the new limits all be specified as June 30, 2013, which is when the construction permit expires.

Page 13, Condition 21. There is no date specified for when the Construction Plan has to be submitted. Also, it is not specified when exactly the Progress Reports are due each year.

And as discussed previously, Condition 19 requires that SAM testing be performed prior to April 12, 2012, which would require construction to be completed in order to do the testing, but Condition 21.b requires completion of construction by December 31, 2012. These need to be reconciled. It is suggested all these dates be stated as June 30, 2013.

Thank you for consideration of these comments. If you have any questions, or would like to discuss this information further, please do not hesitate to call me at (352) 336-5600.

Sincerely,

GOLDER ASSOCIATES INC.

David a. Buff

David A. Buff, P.E., Q.E.P.

Principal Engineer

DB/tlc

cc:

Jeff Stewart David Turley Diana Jaigella Rama Iyer Robert Manning Sal Mohammad

L032309 643