

Air Emissions Compliance Test and RATA Report

Completed for:

***Orange Cogeneration L.P.
Orange Cogeneration Facility
Auxiliary Boiler (EU -003)***

Test Report Number: 20-7044-03-001

Test Completed: April 16, 2014



Air Emissions Compliance Test and RATA Report

**Orange Cogeneration L.P.
Orange Cogeneration Facility
Auxiliary Boiler (EU -003)
Bartow, Florida**

C.E.M. Solutions Project No. 7044


Testing Completed: April 16, 2014

C.E.M. Solutions, Inc Report Number: 20-7044-03-001

**C.E.M. Solutions, Inc.
1183 E. Overdrive Circle
Hernando, Florida 34442
Phone: 352-489-4337**

**Declaration of Conformance to ASTM D 7036-04:
Standard Practice for Competence of Air Emission
Testing Bodies**


C.E.M. Solutions operates in conformance with the requirements of ASTM D 7036-04: Standard Practice for Competence of Air Emission Testing Bodies through the use of a quality system which incorporates a quality manual, internal audit system, systematic training of personnel and rigorous review of test methods and operating procedures.



Joe Conti
Quality Assurance Manager,
C.E.M. Solutions, Inc.

Statement of Validity

I hereby certify the information and data provided in this emissions test report for tests performed on the auxiliary boiler at the Orange Cogeneration L.P., Orange Cogeneration Facility, conducted on April 16, 2014 are complete and accurate to the best of my knowledge.



Joe Conti
Quality Assurance Manager,
C.E.M. Solutions, Inc.

Project Background

Name of Source Owner: Orange Cogeneration L.P.

Address of Owner: 1901 Clear Springs Mine Rd.
Bartow FL 33830

Source Identification: Facility ID: 1050231
Emissions Unit: Aux Boiler (EU -003)

Location of Source: Polk County, Florida

Type of Operation: SIC Code: 4911

Tests Performed: Method 9 – Visual Determination of Visible emissions

Test Supervisor
(QSTI certified): Mr. Alex Houseal

Date(s) Tests Conducted: April 16, 2014: Compliance on Aux. Boiler

Site Test Coordinator: Mr. Kristen Albritton

State Regulatory Observers: No Observers Present

Table of Contents

1.0	Introduction	1
2.0	Facility Description	2
2.1	Process Equipment	2
2.2	Regulatory Requirements	2
3.0	Test Program/Operating Conditions	3
4.0	Test Methods	4
4.1	Determination of Visible Emissions	4
5.0	Test Results	5
5.1	Auxiliary Boiler (EU -003) Visible Emissions.....	5

List of Tables

Table 1:	Summary of Compliance Test.....	1
Table 2:	Summary of Emissions and CEMS Accuracy Limits	2
Table 3:	Heat Input During Test Program	3

Appendices

- Appendix A: Plant Operations Data
- Appendix B: Method 9 Support Data

1.0 Introduction

Orange Cogeneration L.P. retained C.E.M. Solutions, Inc. to perform visible emission monitoring on the auxiliary boiler (EU -003). Annual compliance testing was conducted on the auxiliary boiler for visible emissions. The test program and results are presented and discussed in this report.

Derek Kopera was the certified visible emissions evaluator for C.E.M. Solutions, Inc. Kristen Albritton of the Orange Cogeneration L.P. Orange Cogeneration Facility coordinated plant operations throughout the test program. All testing was conducted in accordance with test methods promulgated by the USEPA.

The auxiliary boiler of the Orange Cogeneration Facility was found to be in compliance with permit number 1050231-012-AV. Table 1 summarizes the results of the compliance tests conducted on the auxiliary boiler.

1.1 Errors and Omissions

At the time of testing, the Auxiliary Boiler data acquisition system is one hour behind Eastern Daylight Saving time. The VE observations were conducted from 09:20 to 10:20 Eastern Time, which translates to 08:20 to 09:20 on the plant's operations report located in Appendix A of this document.

**Table 1: Summary of Compliance Test
Orange Cogeneration L.P.
Orange Cogeneration Facility
Auxiliary Boiler**

Pollutant	Applicable CFR Part	Result	Performance Specification	Pass/ Fail
V.E.	permit	0.0	≤ 15%	Pass

2.0 Facility Description

The Orange Cogeneration Facility consists of two General Electric Model LM6000 Combustion Turbines (Units 1 and 2) each having a nominal generating capacity of 41.4 MW and are capable of firing natural gas. A Zurn Nepco two-drum, bent tube auxiliary boiler is also in operation at the facility.

2.1 Process Equipment

The auxiliary boiler has a maximum heat input of 100 mmBtu/hr firing natural gas. Heat input for the auxiliary boiler is based on the higher heating value (HHV).

The auxiliary boiler emissions are controlled with low NO_x burners. Emissions are exhausted through a 65 foot tall, 3.7 foot diameter stack.

2.2 Regulatory Requirements

The facility is required to conduct annual emissions tests for the following pollutants while operating at 90-100 percent of the heat input curve. Emission testing was conducted to determine the compliance status of the following pollutants:

- Visible emissions in percent

Table 2 summarizes the applicable emissions and CEMS accuracy limits for the auxiliary boiler.

**Table 2: Summary of Emissions and CEMS Accuracy Limits
Orange Cogeneration L.P.
Orange Cogeneration Facility
Auxiliary Boiler**

Pollutant	Unit	Control Technology	Emission Limit/Performance Specification	Permit Condition
Visual Emission	Aux Boiler	Good Combustion	≤15% for gas ¹	B.5

¹ Highest 6 minute block average

3.0 Test Program/Operating Conditions

Emissions tests were completed at the Orange Cogeneration Facility to determine the compliance status of the auxiliary boiler on April 16, 2014.

Unit operating data was collected and provided by facility personnel during the entire test program. Data provided include, but was not limited to:

- Unit Heat Input
- Combustor inlet air temperature
- Fuel flow rate

Table 3 presents the percentage of the maximum heat input, for each Unit, during the V.E. test.

**Table 3: Heat Input During Test Program
Orange Cogeneration L.P.
Orange Cogeneration Facility
Auxiliary Boiler**

Unit	Calculated Heat Input mmBtu/hr	Maximum Heat Input mmBtu/hr	Percent of Heat Input %
Aux Boiler	81.6	100	81.6%

Unit operating data can be viewed in Appendix A.

4.0 Test Methods

All testing was performed in accordance with methods approved by the USEPA and FDEP. The following discusses the methods, as well as quality assurance and sample handling procedures.

4.1 Determination of Visible Emissions

USEPA Method 9 was utilized to determine visible emissions.

Visible emissions observations were performed by a FDEP certified visible emissions reader. Readings were taken at 15 second intervals and reduced into six minute averages as required by the applicable EPA standard. One-sixty minute visible emission run was performed while each source was operating at maximum capacity.

5.0 Test Results

Summaries of the test results for the VE are discussed below. Supporting VE field data are presented in Appendix B.

5.1 Auxiliary Boiler (EU -003) Visible Emissions

The highest visible emissions observed in any six-minute average on the auxiliary boiler during the one hour test runs was 0.0%, passing the 15% emission limitation.

Appendix A: Plant Operations Data

ORANGE COGEN
 BARTOW, FL
Aux Boiler Hourly Operations Report
 April 16, 2014 - Hour 8

Minute	Gas Flow klb/hr	Heat Input mmBtu/hr	Ambient Temp °F
08:00	3.373	66.6	54.0
08:01	3.419	67.5	54.1
08:02	3.433	67.8	54.0
08:03	3.419	67.5	54.0
08:04	3.422	67.6	54.1
08:05	3.510	69.3	54.1
08:06	3.640	71.9	54.1
08:07	3.788	74.8	54.2
08:08	3.839	75.8	54.1
08:09	3.861	76.2	54.1
08:10	3.848	76.0	54.2
08:11	3.814	75.4	54.2
08:12	3.775	74.6	54.3
08:13	3.731	73.8	54.2
08:14	3.820	75.5	54.2
08:15	3.905	77.2	54.2
08:16	3.929	77.7	54.2
08:17	3.884	76.7	54.3
08:18	3.867	76.5	54.4
08:19	3.873	76.5	54.4
08:20	3.900	77.0	54.4
08:21	3.919	77.4	54.4
08:22	3.915	77.3	54.4
08:23	3.854	76.1	54.5
08:24	3.799	75.0	54.5
08:25	3.767	74.3	54.6
08:26	3.767	74.3	54.5
08:27	3.774	74.5	54.6
08:28	3.777	74.5	54.8
08:29	3.781	74.6	54.7
08:30	3.854	76.1	54.8
08:31	3.983	78.6	54.9
08:32	4.106	81.1	54.9
08:33	4.184	82.6	54.9
08:34	4.224	83.5	55.0
08:35	4.220	83.5	55.0
08:36	4.194	83.0	55.1
08:37	4.174	82.6	55.1
08:38	4.163	82.4	55.2
08:39	4.161	82.4	55.2
08:40	4.178	82.5	55.1
08:41	4.190	82.8	55.3
08:42	4.197	82.9	55.3
08:43	4.191	82.8	55.3
08:44	4.177	82.5	55.3
08:45	4.189	82.3	55.3
08:46	4.188	82.3	55.3
08:47	4.166	82.3	55.4
08:48	4.173	82.4	55.4
08:49	4.170	82.4	55.4
08:50	4.167	82.3	55.4
08:51	4.185	82.7	55.5
08:52	4.198	82.9	55.4
08:53	4.207	83.1	55.5
08:54	4.212	83.2	55.5
08:55	4.214	83.2	55.6
08:56	4.214	83.2	55.7
08:57	4.212	83.2	55.7
08:58	4.215	83.3	55.8
08:59	4.230	83.5	55.7
Average			54.8
Total	3.958	78.1	

ORANGE COGEN
 BARTOW, FL
Aux Boiler Hourly Operations Report
 April 16, 2014 - Hour 9

Minute	Gas Flow klb/hr	Heat Input mmBtu/hr	Ambient Temp °F
09:00	4.233	83.5	55.8
09:01	4.223	83.4	55.9
09:02	4.215	83.3	55.9
09:03	4.200	83.0	56.0
09:04	4.201	83.0	56.0
09:05	4.197	82.9	56.1
09:06	4.192	82.8	56.1
09:07	4.200	83.0	56.2
09:08	4.201	83.0	56.3
09:09	4.211	83.2	56.3
09:10	4.224	83.4	56.4
09:11	4.228	83.5	56.4
09:12	4.234	83.5	56.5
09:13	4.227	83.5	56.6
09:14	4.223	83.4	56.6
09:15	4.223	83.4	56.7
09:16	4.224	83.4	56.8
09:17	4.236	83.6	56.8
09:18	4.252	84.1	56.9
09:19	4.269	84.4	57.1
09:20	4.308	85.0	57.2
09:21	4.350	86.0	57.3
09:22	4.334	85.5	57.3
09:23	4.138	81.7	57.4
09:24	3.956	78.1	57.5
09:25	3.896	76.9	57.6
09:26	3.870	76.4	57.6
09:27	3.887	76.7	57.7
09:28	3.883	76.7	57.7
09:29	3.848	76.0	57.8
09:30	3.795	74.9	58.0
09:31	3.750	74.0	58.0
09:32	3.733	73.7	58.0
09:33	3.726	73.5	58.1
09:34	3.728	73.6	58.1
09:35	3.709	73.2	58.3
09:36	3.717	73.3	58.3
09:37	3.715	73.3	58.4
09:38	3.719	73.4	58.4
09:39	3.719	73.4	58.5
09:40	3.720	73.4	58.4
09:41	3.743	73.9	58.4
09:42	3.757	74.1	58.5
09:43	3.782	74.8	58.6
09:44	3.802	75.2	58.7
09:45	3.795	75.0	58.7
09:46	3.744	74.0	58.9
09:47	3.711	73.4	58.8
09:48	3.681	72.8	58.9
09:49	3.667	72.5	59.1
09:50	3.689	72.8	59.0
09:51	3.702	73.0	59.1
09:52	3.731	73.6	59.1
09:53	3.728	73.6	59.2
09:54	3.744	73.9	59.3
09:55	3.745	73.9	59.3
09:56	3.731	73.6	59.4
09:57	3.737	73.7	59.4
09:58	3.723	73.5	59.3
09:59	3.750	74.0	59.4
Average			57.7
Total	3.948	77.9	

ORANGE COGEN
 BARTOW, FL
Aux Boiler Hourly Operations Report
 April 16, 2014 - Hour 10

Minute	Gas Flow klb/hr	Heat Input mmBtu/hr	Ambient Temp °F
10:00	3.824	75.5	59.3
10:01	3.879	76.6	59.3
10:02	3.924	77.5	59.2
10:03	3.946	77.9	59.3
10:04	3.997	78.9	59.3
10:05	4.075	80.5	59.4
10:06	4.153	82.0	59.6
10:07	4.057	80.1	59.5
10:08	3.795	74.9	59.6
10:09	3.463	68.4	59.5
10:10	3.243	64.0	59.6
10:11	3.107	61.3	59.5
10:12	2.329	46.0	59.5
10:13	1.637	32.3	59.6
10:14	1.314	26.0	59.7
10:15	1.063	21.0	59.7
10:16	0.711	14.1	59.9
10:17	0.381	7.5	59.9
10:18	Down	Down	60.1
10:19	Down	Down	59.9
10:20	Down	Down	59.9
10:21	Down	Down	59.9
10:22	Down	Down	59.9
10:23	Down	Down	59.9
10:24	Down	Down	60.1
10:25	Down	Down	60.1
10:26	Down	Down	60.2
10:27	Down	Down	60.3
10:28	Down	Down	60.4
10:29	Down	Down	60.4
10:30	Down	Down	60.4
10:31	Down	Down	60.5
10:32	Down	Down	60.5
10:33	Down	Down	60.6
10:34	Down	Down	60.8
10:35	Down	Down	60.8
10:36	Down	Down	60.7
10:37	Down	Down	60.8
10:38	Down	Down	60.8
10:39	Down	Down	60.9
10:40	Down	Down	60.9
10:41	Down	Down	61.1
10:42	Down	Down	61.0
10:43	Down	Down	61.0
10:44	Down	Down	61.1
10:45	Down	Down	61.1
10:46	Down	Down	61.2
10:47	Down	Down	61.5
10:48	Down	Down	61.5
10:49	Down	Down	61.4
10:50	Down	Down	61.5
10:51	Down	Down	61.7
10:52	Down	Down	61.7
10:53	Down	Down	61.6
10:54	Down	Down	61.6
10:55	Down	Down	61.7
10:56	Down	Down	61.9
10:57	Down	Down	62.0
10:58	Down	Down	62.1
10:59	Down	Down	62.3
Average			60.5
Total	0.882	17.7	

Appendix B: Method 9 Support Data

VE Field Documentation
VE Observers Certificate

RECORD OF VISUAL DETERMINATION OF OPACITY


SOURCE/PROCESS INFORMATION				OBSERVATION RECORD										
FACILITY NAME <i>Orange Lake</i>				DATE <i>4/16/14</i>		STACK A				STACK B				
SOURCE NAME <i>Auxiliary Boiler (003)</i>		PERMIT NUMBER <i>1050231-010-AU</i>		HOUR	MINUTE	0	15	30	45	0	15	30	45	
LOCATION ADDRESS <i>1901 Clear Springs Rd</i>				<i>920</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
CITY <i>Barton</i>		STATE <i>FL</i>	ZIP <i>33830</i>	<i>921</i>	<i>1</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
UNIT LOAD <i>base</i>		HEAT INPUT <i>tbd</i>		<i>922</i>	<i>2</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
CONTROL EQUIPMENT		OPERATING MODE <i>Normal</i>		<i>923</i>	<i>3</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
FUEL TYPE/RATE <i>Natural Gas</i>		PERMITTED RATE		<i>924</i>	<i>4</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
DESCRIBE EMISSION POINT <i>Circular grey stack</i>				<i>925</i>	<i>5</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
HEIGHT ABOVE GROUND LEVEL <i>50</i> FT		HEIGHT OF OBSERVATION POINT <i>0</i> FT		<i>930</i>	<i>10</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
EMISSIONS DESCRIPTION														
DESCRIBE EMISSIONS <i>START Clear stack heat trace END Clear heat trace</i>				<i>11</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
PLUME COLOR <i>clear</i>		PLUME TYPE <i>coning</i>		<i>12</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
WATER DROPLETS PRESENT <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Attached <input type="checkbox"/> Detached				<i>13</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
METEOROLOGICAL INFORMATION														
BACKGROUND <i>START blue sky END sky</i>		BACKGROUND COLOR <i>START blue END blue</i>		<i>14</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
SKY CONDITIONS - CLOUD COVER <i>START clear END clear</i>		AMBIENT TEMPERATURE <i>START 54 END 57</i>		<i>15</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
WIND SPEED <i>START 9-12 mph END 9-12 mph</i>		WIND DIRECTION <i>START NNE END NNE</i>		<i>16</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
OBSERVATION DATA SITE DIAGRAM														
SUMMARY OF AVERAGE OPACITY														
SET NUMBER	TIME		OPACITY		<i>1000</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	
	START	END	SUM	AVERAGE										
COMPLIANCE INFORMATION														
RANGE OF OPACITY READINGS				<i>40</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
MAXIMUM <i>0</i>		MINIMUM <i>0</i>		<i>45</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
HIGHEST 5 MINUTE AVERAGE <i>0.0</i>				<i>46</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
COMMENTS				<i>47</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
				<i>48</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
				<i>49</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
				<i>50</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
				<i>51</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
				<i>52</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
				<i>53</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
				<i>54</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
				<i>55</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
				<i>56</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
				<i>57</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>						
<i>58</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>										
<i>59</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>										
OBSERVER <i>D. Lopez</i>				DATE <i>4/16/14</i>		<i>1015</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>				
OBSERVER'S SIGNATURE <i>[Signature]</i>				<i>1016</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
METER IDENTIFICATION NUMBER <i>418882</i>				<i>1017</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
EXPIRATION DATE <i>8/7/2014</i>				<i>1018</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					
				<i>1019</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>	<i>0</i>					



VISIBLE EMISSIONS EVALUATOR

Derek Kopera

This is to certify that the above named observer has met the specifications of Federal Reference Method 9 and is qualified as a visible emissions evaluator. Maximum deviation on white and black smoke did not exceed 7.5% opacity and no single error exceeding 15% opacity was incurred during the certification test conducted by Eastern Technical Associates, Inc. of Raleigh, N.C. This certificate is valid for six months from date of issue.



418682

Certificate #

KOP804755

Student ID Number

2/5/2014

Date of Certification

Orlando, FL

Location

8/7/2014

Certification Expiration Date

TMPF11

Last Lecture

Marty Hughes

Director of Training