# State of Florida DEPARTMENT OF ENVIRONMENTAL REGULATION

### INTEROFFICE MEMORANDUM

	outing To District Offices o Other Than The Addres	
To:	Loctn.:	
To:	Loctn.:	
То:	Loctn.:	
From:	Date:	
Reply Optional [ ]	Reply Required [ ]	Into. Only [ ]
Date Due:	Date Due:	

/ÍO: John C. Brown, Jr., Northeast District office

FROM: Bill Thomas, Bureau of Air Quality Management

DATE: March 7, 1985

SUBJ: Application Packages to install ESP's on No. 4

Combination Boiler and No. 5 Power Boiler at

Georgia-Pacific Corporation

On February 28, 1985, the bureau received the above referenced application packages. Since each of the referenced sources was not permitted via a construction permit, their requests would not be considered a modification, pursuant to FAC Rule 17-2.100(105), which is also attached. Therefore, the bureau is transmitting the application packages to the district office for processing as a revision to their existing operating permits.

A fee per source should be appropriate. The applicant is awaiting a response from the department on fees and any additional information that might be necessary for processing their requests.

If there are any questions, please call me or Bruce Mitchell at SunCom 278-1344.

BT/BM/rw

Attachments

# **Georgia-Pacific Corporation**



Hudson Pulp & Paper Corp. A wholly-owned subsidiary

P.O. Box 919 Palatka, Florida 32077 Telephone (904) 325-2001

February 27, 1985

Mr. Bruce Mitchell
State of Florida
Department of Environmental Regulation
Bureau of Air Quality
Twin Towers Office Building
2600 Blair Stone Road
Tallahassee, Florida 32301

Dear Bruce:

Enclosed are 3 copies each of permit applications for adding particulate control devices to our No. 4 Combination Boiler and the No. 5 Oil Fired Power Boiler.

If there are any questions please contact me.

Sincerely,

W. R. Wilson

Environmental Supt.

mg enclosures

cc W. L. Baxter
John Brown, FDER, Jacksonville

### STATE OF FLORIDA

## **DEPARTMENT OF ENVIRONMENTAL REGULATION**

NORTHEAST DISTRICT

3426 BILLS ROAD JACKSONVILLE, FLORIDA 32207



BOB GRAHAM GOVERNOR VICTORIA J. TSCHINKEL SECRETARY G. DOUG DUTTON DISTRICT MANAGER

### APPLICATION TO OPERATE/CONSTRUCT AIR POLLUTION SOURCES

SOURCE TYPE: STEAM POWER BOILER OIL-FIRED	New <sup>1</sup> [X] Existing <sup>1</sup>
APPLICATION TYPE: [ ] Construction [X] Operati	
COMPANY NAME: GEORGIA-PACIFIC CORPORATION	•
Identify the specific emission point source(s) a	•
Kiln No. 4 with Venturi Scrubber; Peaking Unit N	
SOURCE LOCATION: Street STATE ROAD 216 (NORTH S	
	North 3283.4
· · · · · · · · · · · · · · · · · · ·	Longitude 81° 40' 45"W
APPLICANT NAME AND TITLE: GEORGIA-PACIFIC	
APPLICANT ADDRESS: P.O. BOX 919.PA	•
SECTION I: STATEMENTS BY A	
A. APPLICANT	II DIOMI AND BIOLINADA
	and the second of the second o
I am the undersigned owner or authorized rep	
I certify that the statements made in this a permit are true, correct and complete to the	pplication for a AIR EMISSION  best of my knowledge and belief. Further
I agree to maintain and operate the pollu	tion control source and pollution control
facilities in such a manner as to comply v Statutes, and all the rules and regulations	vith the provision of Chapter 403, Florida of the department and revisions thereof. I
also understand that a permit, if granted b	by the department, will be non-transferable
and I will promptly notify the department up establishment.	on sale or legal transfer of the permitted
*Attach letter of authorization Signe	ed:
<del></del>	Name and Title (Please Type)
Dates	Telephone No.
B. PROFESSIONAL ENGINEER REGISTERED IN FLORIDA	•
This is to cartify that the engineering feet	tures of this pollution control project have

This is to certify that the engineering features of this pollution control project have been designed/examined by me and found to be in conformity with modern engineering principles applicable to the treatment and disposal of pollutants characterized in the permit application. There is reasonable assurance, in my professional judgment, that

DER Form 17-1.202(1) Effective October 31, 1982

<sup>1</sup> See Florida Administrative Code Rule 17-2.100(57) and (104)

Signed Flavel Cally  Harold L. Culp, PE  Name (Please Type)  Ford, Bacon & Bavis, Inc.  Company Name (Please Type)  P.O. Box 1894, Monroe, LA 71210  Mailing Address (Please Type)  P.O. Box 1894, Monroe, LA 71210  Mailing Address (Please Type)  P.O. Box 1894, Monroe, LA 71210  SECTION III GENERAL PROJECT INFORMATION  A. Describe the nature and extent of the project. Refer to pollution control equipment, and expected improvements in source performance as a result of installation. State whether the project will result in full cappliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  8. Schedule of project covered in this application of tenetruction November 28, 1986. Hoddification-Addition of Control Equipment  C. Costs of pollution control system(s): (Notes Show breakdown of estimated costs only for individual components/units of the project eaving pollution control proposes. Information on actual costs shell be furnished with the application for operation persit.)  Estimated cost of multi-cell electrogratic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER persits, orders and notices associated with the esission point, including persit issuence and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OCC File No. 83-0803 - Florida Pept. of Environmental Regulation dated January 7, 1985.		the pollution control facilities, when properly maintained and operated, will discharge an effluent that complies with all applicable statutes of the State of Florida and the rules and regulations of the department. It is also agreed that the undersigned will furnish, if authorized by the owner, the applicant a set of instructions for the proper maintenance and operation of the pollution control facilities and, if applicable, pollution sources.
Harold L. Culp, PE Name (Please Type) Nord, Bacon & Davis, Inc. Company Name (Please Type) Pool. Box 1894, Monroe, LA. 71210 Mailing Address (Please Type) P.O. Box 1894, Monroe, LA. 71210  Mailing Address (Please Type) P.O. Box 1894, Monroe, LA. 71210  Mailing Address (Please Type)		
Prof. Bacon & Davis, Inc.  Company Name (Please Type)  P.O. Box 1894, Monroe, LA. 71210  Reiling Address (Please Type)  P.O. Box 1894, Monroe, LA. 71210  Reiling Address (Please Type)  P.O. Box 1894, Monroe, LA. 71210  Reiling Address (Please Type)  SECTION III GENERAL PROJECT INFORMATION  A. Describe the nature and extent of the project. Refer to pollution control equipment, and expected improvements in source performance as e result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  Start of Construction Pebruary 28, 1986 Completion of Construction November 28, 1986. Modification-Addition of Control Equipment (Notes Show breakdown of estimated costs only for Individual components/unite of the project serving pollution control purposes. Information on actual costs shell be furnished with the application for operation persit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER persits, orders and notices sessociated with the emission point, including persit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OSC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.		N. D. C. W.
STATE OF Caspany Name (Please Type)  P.O. Box 1894, Monroe, LA 71210  Natiling Address (Please Type)  P.O. Box 1894, Monroe, LA 71210  Natiling Address (Please Type)  SECTION II: GENERAL PROJECT INFORMATION  A. Describe the nature and extent of the project. Refer to pollution control equipment, and expected improvements in source performence as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  Start of Construction Pebruary 28, 1986 (Completion of Construction November 28, 1986. Modification-Addition of Control Equipment (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shell be furnished with the application for operation persuit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER persits, orders and notices associated with the emission point, including persit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986, Consent Order OCC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.		Mase (Please Type)
P.O. Box 1894, Monroe, LA 71210  Registration No. 29275  Date: March 21, 1980  SECTION III GENERAL PROJECT INFORMATION  A. Describe the nature and extent of the project. Refer to pollution control equipment, and expected laprovements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  Start of Construction February 28, 1986 Completion of Construction November 28, 1986 Modification-Addition of Control Equipment  C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shell be furnished with the application for operation perait.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986, Consent Order OCC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.		Ford Bacon & Davis Toc
P.O. Box 1894, Monroe, LA 71210  Reflection Registration No. 29275  Date: March 21, 1980 Telephone No. (318) 323-9000  SECTION II: GENERAL PROJECT INFORMATION  A. Describe the nature and extent of the project. Refer to pollution control equipment, and expected improvements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  Start of Construction Pebruary 28, 1986 Completion of Construction November 28, 1986. Modification-Addition of Control Equipment  Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shell be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986, Consent Order OSC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.		10 711 0 00 0 0 0 0 0 0 0 0 0 0 0 0 0 0
Section II. General Project Information  8. Describe the nature and extent of the project. Refer to pollution control equipment, and expected improvements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  8. Schedule of project covered in this application (Construction Permit Application Only)  Start of Construction February 28, 1986 Completion of Construction November 28, 1986.  Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shall be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash  removal and vertical stack with all installed appurtenances = \$2,000,000.  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Pept. of Environmental Regulation dated January 7, 1985.		P.O. Roy 1804 Names 14 71010
SECTION II: GENERAL PROJECT INFORMATION  A. Describe the nature and extent of the project. Refer to pollution control equipment, and expected isprovements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  Start of Construction February 28, 1986 Completion of Construction November 28, 1986 Modification-Addition of Control Equipment C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shell be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OCC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.		
SECTION II: GENERAL PROJECT INFORMATION  1. Describe the nature and extent of the project. Refer to pollution control equipment, and expected improvements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  Start of Construction Pebruary 28, 1986 Completion of Construction November 28, 1986. Modification-Addition of Control Equipment C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shell be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  OCR Form 17-1.202(1)	• • •	
A. Describe the nature and extent of the project. Refer to pollution control equipment, and expected improvements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  Start of Construction February 28, 1986 Completion of Construction November 28, 1986. Modification-Addition of Control Equipment  C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shell be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000.  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  OCR Form 17-1.202(1)	10	rida Registration No. 29275 Date: March 21, 1980 Telephone No. (318) 323-9000
and expected isprovements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary.  (See Attached Supplementary Report)  8. Schedule of project covered in this application (Construction Permit Application Only)  Start of Construction February 28, 1986 Completion of Construction November 28, 1986 Modification-Addition of Control Equipment  Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shall be furnished with the application for operation perait.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash  removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Pept. of Environmental Regulation dated January 7, 1985.		SECTION II: GENERAL PROJECT INFORMATION
B. Schedule of project covered in this application (Construction Permit Application Only)  Start of Construction February 28, 1986 Completion of Construction November 28, 1986 Modification-Addition of Control Equipment  C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/unite of the project serving pollution control purposes. Information on actual costs shall be furnished with the application for operation perait.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  DER form 17-1.202(1)	۱.	and expected improvements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if
B. Schedule of project covered in this application (Construction Permit Application Only)  Start of Construction February 28, 1986 Completion of Construction November 28, 1986 Modification-Addition of Control Equipment  C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for Individual components/unite of the project erving pollution control purposes. Information on actual costs shall be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OCC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  DER Form 17-1.202(1)		(See Attached Supplementary Poport)
Start of Construction February 28, 1986 Completion of Construction November 28, 1986  Modification-Addition of Control Equipment  C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shall be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash  removal and vertical stack with all installed appurtenances = \$2,000,000  O. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Pept. of Environmental Regulation dated January 7, 1985.  DER form 17-1.202(1)		(Job Institution of Ottp://www.neports
Start of Construction February 28, 1986 Completion of Construction November 28, 1986  Modification-Addition of Control Equipment  C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shall be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash  removal and vertical stack with all installed appurtenances = \$2,000,000  O. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Pept. of Environmental Regulation dated January 7, 1985.  DER form 17-1.202(1)		
Modification-Addition of Control Equipment C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shall be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OCC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  DER form 17-1.202(1)	8.	Schedule of project covered in this application (Construction Permit-Application Only)
C. Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shall be furnished with the application for operation permit.)  Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,000,000  Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  DER form 17-1.202(1)		Start of Construction February 28, 1986 Completion of Construction November 28, 1986 Modification-Addition of Control Regionest
removal and vertical stack with all installed appurtenances = \$2,000,000  D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  DER form 17-1.202(1)	¢.	Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on sctual costs shall be furnished with the application for operation
D. Indicate any previous DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  DER Form 17-1.202(1)		Estimated cost of multi-cell electrostatic precipitator, ducting, ash
point, including permit issuance and expiration dates.  Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OCC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  OCR Form 17-1.202(1)		removal and vertical stack with all installed appurtenances = \$2,000,000
Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.  Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  OER Form 17-1.202(1)		
Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985.  OER Form 17-1.202(1)	D.	
dated January 7, 1985.  DER Form 17-1.202(1)		Permit No. A054-45320 dated January 22, 1982, expires September 30, 1986.
DER FORM 17-1.202(1)		Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation
		dated January 7, 1985.

	this is a new source or major modification, answer the following questions or No. NO.	ions.
ĺ.	Is this source in a non-attainment area for a particular pollutant?	NO
	s. If yes, has "affset" been applied?	
	b. If yes, has "Lowest Achievable Emission Rate" been applied?	Trap age
	c. If yes, list non-attainment pollutants.	
2.	Does best available control technology (BACT) apply to this source? If yes, see Section VI.	NO
3.	Does the State "Prevention of Significant Deterioristion" (PSD) requirement apply to this source? If yes, see Sections VI and VII.	по
١.	Do "Standards of Performance for New Stationary Sources" (NSPS) apply to this source?	NO
5.	Do "National Emission Standards for Hazardous Air Pollutants" (NESHAP) apply to this source?	NO
	"Reasonably Available Control Technology" (RACT) requirements apply this source?	NO
	a. If yea, for what pollutants?	

DER Form 17-1.202(1) Effective October 31, 1982

### SECTION III: AIR POLLUTION SOURCES & CONTROL DEVICES (Other than Incinerators)

A. Raw Materials and Chemicals Used in your Process, if applicable:

	COIICAM	inants	Utilization	
Description	Type	% Wt	Rate - lba/hr	Relate to Flow Diagram
			***************************************	

- B. Process Rate, if applicable: (See Section V, Item 1) For Information Only
  - 1. Iotal Process Input Rate (lbs/hr): To 31,550 lbs/hr No. 6 Oil plus Combustion Air
  - 2. Product Weight (1bs/hr): 475,000 lbs/hr, 1275 psig, 900 F Superheated Steam Maximum
- C. Airborne Contaminants Emitted: (Information in this table must be submitted for each emission point, use additional sheets as necessary)

Name of	Eniss	ionl	Allowed <sup>2</sup> Emission Rate per	Requested Allowable <sup>3</sup> Emission	Potenti Emissi		Relate to Flow	
Contaminant	Maxiaua lbs/hr	Actual T/yr *	Rule 17-2	lbs/hr	lbs/yr	I/yr *	Diagram Stack	
Particulates	56.8	248.8	0.1 lbs/MBTU	56.8	497,568	248.8	Stack	
so <sub>2</sub>	1564	6850	2.751bs/พืชบ	1564	13,814,520	6907	Stack	
Fuel NO(As NO	200	876	N/A	N/A	1,752,000	876	Stack	
• co	0.15	0.66	N/A	N/A	1314	0.66	Stack	
Methane Hydrocarbons	7.6	33.3	N/A	N/A	66,751	33.3	Stack	
Opacity	20%, 40%	2M	20%, 40% 2M	20%, 40% 2M	30	<b>%</b>	Stack	

1 See Section V, Item 2. \*At 8760 hrs/yr No Sampling data - factored from AP-42 Chap. 1

Tab

<sup>&</sup>lt;sup>2</sup>Reference applicable emission standards and units (e.g. Rule 17-2.600(5)(b)2. Table II, E. (1) - 0.1 pounds per million BIU heat input)

<sup>3</sup>Calculated from operating rate and applicable standard.

<sup>&</sup>lt;sup>4</sup>Emission, if source operated without control (See Section V, Item 3).

### D. Control Devices: (See Section V, Item 4)

Name and Type (Model & Serial No.)	Contaminant	Efficiency	Range of Particles Size Collected (in microns) (If applicable)	Basis for Efficiency (Section V Item 5)
Electrostatic Pre-	Particulates	Up to 90%	1-100	Cost Effectiv
cipitator (Not				Design Basis
Selected From Vendor				
Yet. Equipment Bids ~			*****	
Guaranteed Performance				
Data Not Yet Received)				

### £. fuels

	Consum	ption*	
Type (8e Specific)	avg/hr max./hr		Maximum Heat Input (MMBTU/hr)
No. 6 Fuel Oil	2750 +	3810	568.9
	·		

\*Units: Natural Gas--MMCF/hr; Fuel Oils--gallons/hr; Coal, wood, refuse, other--lbs/hr:

fuel Analysis: (See Attached Report)

Percent Sulfur: 2½ Percent Ash: 0.15±

Density: 8.28 (10.9°AP1) lbs/gal Typical Percent Nitrogen: 0.54

Heat Capacity: 18,350 BTU/lb 151,938 BTU/gal

Other Fuel Contaminants (which may cause air pollution): Vanadium

f. If applicable, indicate the percent of fuel used for space heating.

Annual Average —— Maximum —— Pulp Mill

G. Indicate liquid or solid wastes generated and method of disposal.

35-50 lbs/hr ash to be collected and disposed of in a controlled landfill.

	ht:	232	bove Grad	le ft. s	tack Diame	teri	9	_ft
						aperature:	,	o f
ater Vepo	r Content:	10	-12	× v	elocity: _		60.6	FF
					OR INFORMA			
	[					N/A	<del></del>	
Type of Weste	Type () (Plastics)				(Patholoical)		) B (2011q BA-bi LAbe Al	od.;
Actual lb/hr							,	
inciner - ated								
Uncon- trolled (lbe/hr)								
escriptio	on of Yaste				N/A			·····
						apacity (lbs	/hr)	
pproximal	te Number of	Hours of	Operation	per day	da	y/wk	wks/yr	
anufactui			<del></del>	<del></del>				
ate Consi	tructed			Hode:	1 No			
		Volume		lelease	fu Type	el BIU/hr	Temperature (°f)	)
		(ft) <sup>3</sup>				3107.113		
Primary (	Chamber	(ft) <sup>2</sup>						
	Chamber y Chamber	(ft)?						-
Secondary	Chamber			nater:			Yemp.	
Secondary	y Chamber	ft.	Stack Dia				,	
tack Heidas Flow 1	y Chamber ght:	ft.	Stack Dia _ACFM	city, aub	DSCFM mit the emi	Stack	,	f

DER form 17-1.202(1) Effective November 30, 1982

Brief description of	cherating che	racteriatic	s of control	devices:	
		N/A			
			·		
					<del>, 13 13 13 14 14 14 14 14 14 14 14 14 14 14 14 14 </del>
	777				
Ultimate disposal of ash, etc.):	f any effluent	other than	that emitted	from the stace	ck (scrubber water,
		N/A			
		.,	<del></del>		
			<del></del>	<del></del>	
	212 214 214 21 21 2 2 2 2 2 2 2 2 2 2 2				

NOTE: Items 2, 3, 4, 6, 7, 8, and 10 in Section V must be included where applicable.

### SECTION V: SUPPLEMENTAL REQUIREMENTS

Please provide the following supplements where required for this application.

- 1. Total process input rate and product weight -- show derivation [Rule 17-2.100(127)]
- 2. To a construction application, attach basis of emission estimate (e.g., design calculations, design drawings, pertinent manufacturer's test data, etc.) and attach proposed methods (e.g., FR Part 60 Methods 1, 2, 3, 4, 5) to show proof of compliance with applicable standards. To an operation application, attach test results or methods used to show proof of compliance. Information provided when applying for an operation permit from a construction permit shall be indicative of the time at which the test was made.
- 3. Attach basis of potential discharge (e.g., emission factor, that is, AP42 test).
- 4. With construction permit application, include design details for all air pollution control systems (e.g., for baghouse include cloth to air ratio; for acrubber include cross-section sketch, design pressure drop, etc.)
- 5. With construction permit application, attach derivation of control device(s) efficiency. Include test or design data. Items 2, 3 and 5 should be consistent: actual emissions = potential (1-efficiency).
- 6. An 8 1/2" x 11" flow diagram which will, without revealing trade secrets, identify the individual operations and/or processes. Indicate where raw materials enter, where solid and liquid waste exit, where gaseous emissions and/or airborne particles are evolved and where finished products are obtained.
- 7. An 8 1/2" x li" plot plan showing the location of the establishment, and points of airborne emissions, in relation to the surrounding area, residences and other permanent structures and roadways (Example: Copy of relevant portion of USGS topographic map).
- 8. An 8 1/2" x 11" plot plan of facility showing the location of manufacturing processes and outlets for airborne emissions. Relate all flows to the flow diagram.

DER form 17-1.202(1) Effective November 30, 1982

9.	The appropriate	application fee	in accordance w	ith Rule 17-4.05.	The check	should be
	made payable to	the Department of	Environmental	Regulațion.		

10. With an application for operation permit, attach a Certificate of Completion of Construction indicating that the source was constructed as shown in the construction permit.

	SECTION VI: BEST AVA	ILABLE CONTROL TECHNOLOGY
A.	Are standards of performance for new a applicable to the source?	tationary sources pursuant to 40 C.F.R. Part 60
	[ ] Yes [X] No	
	Contaminant	Rate or Concentration
8.	Has EPA declared the best available coyes, attach copy)	ontrol technology for this class of sources (li
	[ ] Yes [X] No	
	Contaminant	Rate or Concentration
c.	What emission levels do you propose as	best available control technology?
	Contaminant	Rate or Concentration
-	N/A	
		·
D.	Describe the existing control and trea	tment technology (if any).
	1. Control Device/System:	2. Operating Principles:
	3. Efficiency: •	4. Capital Costs:
*E	xplain method of determining	

Page 8 of 12

DER Form 17-1.202(1)


Effective November 30, 1982

	_					
	5.	Useful Life:		6.	Operating Costs:	
	7.	Energy:		8.	Maintenance Cost:	
	9.	Emissions:				
		Contaminant			Rate or Concentration	
						<del></del>
	10.	Stack Parameters		<del>,</del>		<del>,</del>
		·	<b>a.</b>			
	8.	Height:	ft.		Diameter:	ft.
٠	<b>c.</b>	Flow Rate:		4.	Temperature:	°F.
	е.	Velocity:	FPS			
E.		cribe the control and treatment additional pages if necessary).		iojog	y available (As many types as a	pplicable,
	1.,					
:	8.	Control Device:		b.	Operating Principles:	
	c.	Efficiency: 1		d.	Capital Cost:	
	e.	Vseful Life:		f.	Operating Cost:	
	g.	Energy: 2		h.	Maintenance Cost:	
	i.	Availability of construction ma	teria	la ar	nd process chemicals:	
	j.	Applicability to manufacturing	proce	8888	r	
	k.	Ability to construct with cont within proposed levels:	rol de	evice	, install in available space, a	nd operate
	2.					
	<b>a</b> .	Control Device:		ь.	Operating Principles:	
	c.	Efficiency: 1		d.	Capital Cost:	
	е.	Useful Life:		f.	Operating Cost:	
	g.	Energy: <sup>2</sup>		h.	Maintenance Cost:	
	i.	Availability of construction me	teria	ls a	nd process chemicals:	
		in method of determining efficient to be reported in units of elec		1 ροι	wer - KWH design rate.	

Applicability to manufacturing processes: Ability to construct with control device, install in available space, and operate within proposed levels: 3. Control Devices Operating Principles: Efficiencyil c. d. Capital Cost: Useful Life: Operating Cost: Energy: 2 Maintenance Cost: g. Availability of construction materials and process chemicals; Applicability to manufacturing processes: Ability to construct with control device, install in available space, and operate within proposed levels: 4. Operating Principles: Control Device: Efficiency: 1 Capital Costs: Useful Life: Operating Cost: Energy: 2 h. Maintenance Cost: Availability of construction materials and process chemicals: Applicability to manufacturing processes: Ability to construct with control device, install in available space, and operate within proposed levels: Describe the control technology selected: 2. Efficiency: 1 1. Control Device: Useful Life: Capital Cost: Energy:2 Operating Cost: Hanufacturer: Naintenance Cost: 7. Other locations where employed on similar processes: 9. a. (1) Company: (2) Hailing Address: (4) State: (3) City:

 $^1\text{Explain}$  method of determining efficiency.  $^2\text{Energy}$  to be reported in units of electrical power - KWH design rate.

DER Form 17-1.202(1) Effective November 30, 1982



(5) Environmental Manager:	
(6) Telephone No.:	
(7) Emissions: l	
Contaminant	Rate or Concentration
(8) Process Rate: 1	
b. (1) Company:	
(2) Mailing Address:	
(3) City:	(4) State:
(5) Environmental Manager:	
(6) Telephane No.:	
(7) Emissions: 1	
Contaminant	Rate or Concentration
(8) Process Rate: 1	
10. Reason for selection and descript	ion of systems:
Applicant must provide this information available, applicant must state the reaso	when available. Should this information not be on(s) why.
SECTION VII - PREVENTIO	N OF SIGNIFICANT DETERIORATION
A. Company Monitored Data	N/A
1na. sitesTS	P Wind spd/dir
Period of Monitoring month	day year month day year
Other data recorded	
Attach all data or statistical summari	es to this application.
*Specify bubbler (8) or continuous (C).	
DER form 17-1.202(1) Effective November 30, 1982	age 11 of 12

### SUPPLEMENTAL REPORT

INSTALLATION OF AN ELECTROSTATIC PRECIPITATOR ON THE NUMBER 5 POWER BOILER AT THE PALATKA, FLORIDA MILL OF GEORGIA-PACIFIC CORPORATION.

## Background

The Number 5 boiler was erected in 1965 and is certified by an existing Operating Permit. The boiler fires Number 6 residual fuel oil exclusively and to date is not equipped with any emission control equipment. Permit-wise (A054-45320) the boiler has been rated at a maximum heat input rate of 465 MM BTU/Hr, thus its current emission rate is limited by this value.

The boiler has essentially met necessary emission criteria over the years but it's been found difficult to meet existing requirements using standard grades of Bunker C oils. Specific lower ash-sulfur oils have been purchased lately for the boiler enabling it to meet requirements on a more consistent basis.

Due to stack sampling difficulties and some alleged violations, various mutually acceptable solutions were arrived at recently by the Company and the Florida Department of Environmental Regulation which were contained in a January 1985 Consent Order. The Company has submitted a schedule for installing new emission control equipment on the boiler along with various intervals of stack monitoring and reportings of performance.

# Proposed Project

Despite the knowledge that particulate removal equipment for oil based boiler flue gas streams is not always required to meet current emission standards (0.1 lbs/MM BTU/hr input) the Company has unilaterally decided to employ the best available control technology on this boiler at this time. This will allow the Company greater latitude in the selection of available, commercially plentiful and economic oil supplies without concern for random firing conditions that could encroach on current emission limits.

The Company has initiated the necessary engineering, planning, bid selection and procurement work necessary to install a high Intensity, multi-field, rigid frame electrostatic precipitator on this boiler per a schedule previously approved by the Department of Environmental Regulation.

# Facility Details

A study of the present steaming facilities is underway including a computerized analysis of combustion conditions (see Exhibit I). With

1

# TABLE I

# TYPICAL FUEL OIL ANALYSIS OF SUPPLIES USED BY GEORGIA-PACIFIC

# PALATKA MILL\*

Degrees API at 60°F	10.9
Specific Gravity at 60°F	0.99
Flash Point, °F	178
BS & W, %	1.65
Viscosity, SFS at 122°F	275
Asphaltene, %	9.9
Ash, %	0.15
Carbon, %	85.7
Hydrogen, %	10.6
Nitrogen, %	0.54
Sulfur, %	2.5
Oxygen, %	0.6
Vanadium, ppm	550
BTUs per pound	18,350

<sup>\*</sup>Analyzed by Fuel Engineering Company of New York in Thornwood, New York in 1984.

fuel oil, the unit has been found to demonstrate the following combustion design related characteristics:

1275 psig steam at 900°F = 1437.4 BTU/lb Feedwater at 445°F saturated = -424.1 BTU/lb

1013.3 BTU/Ib

Heat Input 1013.3 X 475,000 lbs/hr maximum firing capacity 84.6% efficiency

= 568,933,220 BTU/hr heat input with gross fuel requirement of 31,550 lbs/hr.

As noted in Section III (p.4) of the attached Application, under current Florida Regulations, the boiler particulate emission allowable is 56.8 lbs/hr rather than the 46.5 lbs/hr cited in the original permit.

Similarly SO<sub>2</sub> allowables (2.75 lbs/MM BTU/hr input) are 1564 lbs/hr contrasted to the former 1279 lbs/hr allowed. NO, CO and methane hydrocarbon values are also listed in Section III for Departmental purposes.

Despite these more applicable allowables, the Company is requiring that precipitator suppliers-bidders meet a particulate requirement of 0.08 lbs/MM BTU/hr at a flue gas flow of 267,000 acfm or about 15 percent over that derived from the combustion evaluation.

A simplified schematic of the proposed installation is depicted by Sketch C-1712-1 attached. The general plot plan of the entire mill is shown in Sketch C-1712-2 and the immediate boiler area layout is illustrated by Sketch C-1712-3.

An adjacent, similarly sized modern precipitator will be ducted together with this boiler (serving Number 4 combination fuel boiler certified by a separate Permit) for standby treatment purposes. The precipitator serving this boiler will be equipped with isolation dampers, a complete ash removal system and a separate 232 foot (above grade) stack outfitted with the necessary platforms, sampling ports, monoralis, etc. required for monitoring purposes.

A typical analysis of the fuel oil expected to be used in this service is listed in Table I. This and similar grades of oil will be purchased and should fall within the ranges shown.

		. ·	
	8.	Was instrumentation EPA referenced of	or its equivalent? [ ] Yes [ ] No
٠.	b.	Was instrumentation calibrated in a	cordance with Department procedures?
		[ ] Yes [ ] No [ ] Unknown	
В.	Het	eorological Data Used for Air Quality	Modeling
	1.	Year(s) of data from	y year sonth day year
	2.	Surface data obtained from (location	1)
	3.	Upper air (mixing height) data obta	ined from (location)
	4.	Stability wind rose (STAR) data obta	ined from (location)
c. ·	Comp	puter Hodels Used	*
	1.		Hodified? If yes, attach description.
			Modified? If yes, attach description.
	3.		Hodified? If yes, attach description.
	4.		Modified? If yes, attach description.
		ach copies of all final model runs sole output tables.	howing input data, receptor locations, and prin-
D.	Арр	licants Maximum Allowable Emission D	ata
	Pol	lutant Emission R	ato
		TSP ·	grams/sec
		so <sup>2</sup>	grams/sac
٤.	Emi	ssion Data Used in Modeling	
			ion data required is source name, description of M coordinates, stack data, allowable emissions,

2. Instrumentation, Field and Laboratory

and normal operating time.

- f. Attach all other information supportive to the PSD review.
- Discuss the social and economic impact of the selected technology versus other applicable technologies (i.e., jobs, payroll, production, taxes, energy, etc.). assessment of the environmental impact of the sources.
- H. Attach scientific, engineering, and technical material, reports, publications, jour-nals, and other competent relevant information describing the theory and application of the requested best available control technology.

NO = 15.77 t/hr oil X 0.54% X 2.14 X 0.55 (NO is 95% NO) (N→NO) (Conversion) = 10.02 = 0.100 tons/hr NO = 200 lbs/hr NO

Potential emission, uncontrolled = 200 lbs/hr X 8760 hr/yr = 1,752,000 lbs/yr or = 876 tons/yr of fuel derived NO.

CO

As taken from EPA AP-42 Chap. 1 data.
0.04 (3.81 M gal/hr oil) = 0.15 lbs/hr
= 1314 lbs/yr or
0.66 tons/yr of CO

Same for potential emission, uncontrolled.

## Methane Hydrocarbons

As taken from EPA AP-42 Chap. 1 data.

2(3.81 M gal/hr oil) = 7.62 lbs/hr

= 66,751 lbs/yr or

33.3 tons/yr of m. hydrocarbons

Same for potential emission, uncontrolled.

## Opacity .

Per current State of Florida Regulations.

Other elements in the fuel oil will be converted through combustion to their basic oxidative states.

During operations, stack emissions will be analyzed per Permit requirements. EPA Standard Reference Methods (Method 1, 2, 3, 4, 5, 6, 7, 9, 10, 17, etc) would be utilized as may be required and applicable.

## Closure

Georgia-Pacific Corporation intends to employ the best available control technology at this time to reduce particulate and related emissions from their Number 5 Power Boller. A field erected, rigid frame electrostatic precipitator will be used. Internal collector (gas) velocities, specific (plate) collection area, wire length, rapper parameters and power inputs will be selected for the equipment to ensure appropriate design sizing. Full compliance with current State emissions requirements will be ensured.

Per attached Exhibit I the Company requests the appropriate heat input rating (BTU/hr) be established for this boiler and the related, allowable emission rates per Rule 17-2 be authorized as contained within the submitted Application Form 17-1.202(1).

cs/D985/A

### Air Emissions

Although hydrocarbon-based particulate capture is more rigorous than inorganic ash removal using charged electrode technology, it is expected this technical application will ensure complete compliance with present particulate emission limits. Up to 90% removals under this low loading regime is expected.

Some minor SO<sub>2</sub> removals will also be experienced as some 5% of the carbonaceous sulfur based residue will be removed along with the captured ash agglomerates. Visual opacity levels will also be positively affected.

Derivation of various values used to develop the Table in Section III (C) of the Application are as follows:

## <u>Particulates</u>

568.9 MM BTU/hr input at 0.1 lbs/MM BTU = 56.8 lbs/hr Ash = 31,550 lbs/hr oil X  $\frac{0.15\%}{100}$  ash = 47.3 lbs/hr plus soot blows

Precipitator to remove up to 90%

Potential emission, uncontrolled = 56.8 lbs./hr X 8760 hrs/yr = 497.568 lbs/yr or 248.8 tons/yr

SO<sub>2</sub>

568.9 MM BTU/hr input at 2.75 lbs/MM BTU = 1564 ibs/hr  $SO_2 = \frac{31,550}{2,000}$  t/hr oli X 2.5% S X 2 x .95 (S-+SO<sub>2</sub>) (5% in ash dropout)

=  $\frac{74.9}{100}$  = 0.749 tons/hr SO<sub>2</sub> = 1498 lbs/hr SO<sub>2</sub>

and 1577 lbs/hr SO2 with no ash dropout.

Potential emission, uncontrolled = 1577 lbs/hr X 8760 hrs/yr = 13,814,520 lbs/yr or 6907 tons/yr of SO<sub>2</sub>

Fuel NO (excludes thermal NO)

Federal Criteria 0.3 lbs/MM BTU = 170.6 lbs/hr as  $NO_X$  (NO +  $NO_2$ )

, 🔗		· 4	
<b>E</b>	タボルボルルボボルトル ママ・マ・マ・マ・マ・マ・マ・マ・マ・マ・ア・ス・ア・ス・ア・ス・ア・ス・ア・ス		
•			
, •	TOTAL HEAD FOR FO FAN (INCHES H20) 19: 2000		
•	PERCENT CEAKAGE FOR FO FAN 0.5000  PERCENT CEAKAGE FOR FO FAN 1.05000		
•	TOTAL VOLUME OF COMBUSTION AIR (CFM)		
•			
•	TOTAL HEAD FOR 10 FAN (INCHES HZO) 10.0000		
	PERCENT CEAKAGE FOR LOTEAN		
•	TOTAL VOLUME OF FLUE GAS (CFM) — ACTUAL 231439,8125 HORSEPOHER FOR INDUCED ORAFT FAN 503.1672		
•			
•		<u> </u>	
31 32			
<b>3</b>		* * *	
•			
<b>3</b>		<u>.</u>	
•			
<b>3</b>		17. <del>*</del>	
6			
			À


\*\*\*\* #BOILER EFFICIENCY\* \*\*\*\*\*\*\*\*\*\*


3			War to Burney			
٠	" EYIT CAS TEMPE	TIBLE IN ASH	2.0000 			
	PERCENT RAGIAT	TEMPERATURE (FAHRENHEIT)	0.3800 and 1100000 and 1100000 and 1100000 and 1100000 and 1100000 and 11000000 and 11000000 and 11000000 and 11000000 and 110000000 and 110000000 and 110000000 and 110000000 and 1100000000000000000000000000000000000			
1 24	6	TA TENNETH TO				
3 34 2 4	ENTHALPY OF WA	TEX VAPOR AL 1 PSIA AND EXILET QUID WATER AT COMBUSTION 645 T	HP 1252,5073			
t ,,	HEAT LOSS DUE	IO_DRY_GAS	7,5049%			
70	HEAT LOSS DUE E HEAT LOSS DUE HEAT LOSS DUE	TO HE AND FUEL HEQ. TO LIR MOISTURE TO COMBUSTIBLE IN REFUSE	0 (1866) 0 (1866)			
	HEAT LOSS DUE	TO RADIATION TO UNMEASURED LOSSES	1,0001			
, <u>,</u>			B(022			
, , , , , , , , , , , , , , , , , , ,	BOILER EFFICIE	NCY	84.50782			
33 37 33					400	
1 2	,					
5 1 6						
, 1						
, ,						
,   1	į.					
				dia dia managaran di managaran d Managaran di managaran di managar		
. 2	je K	Tempologica (A. Callager 1994 (A. Ballager) 1994 (A	- Company of the state of the s		Bakkanda pare ramangan karaban kinangan da managa	70 71
•						
•	15		*.			


	**************************************	
9		
	# TOTALS FOR ALL FUELS #	
	TOTAL FUEL RATE (LBS PER HOUR) 31557	0000
	TOTAL ITHEORETICAL PLUS EXCESSI COMBUSTION AIR 525267	· ·
•	ATATOTAL COMBUSTION AIR FOR THE STATE OF THE	56 25 E E E E E E E E E E E E E E E E E E
	TOTAL FLUE PRODUCT COZ	
•	TOTAL FUEL SULFUR 2708910  TOTAL FUEL OXYGEN 2708910	
<b>3</b>	TOTAL FUEL CARBON	
3		
3		
3		
3		
3		
3		
3		
ે નિ -		

	EUEL MANES AS EUELLOIL			
	FUEL USE RATE AS A WEIGHT PERCENTAGE	100±0000 18400±000		
	CONSTITUENT PERCENT	<u>K</u>		
*	32 SULFUR 2.50% 33 CARBON 85.85% 30 HYDROGEN 10.80%			
<b>)</b>	29 NITROGEN 0.70%: 0.70%: 0.15			
•	TOTAL PERCENTAGE 100.00%	21.4000%		
* <b>X</b>	THEORETICAL AIR LES PER POUND FUEL)	\$[6:6466 \$1.971974	The state of the s	
<i>}</i>	AT 121.40% THEORETICAL AIR: TOTAL DRY GAS LLBS PER POUND FUEL)	18.4775		
•	FLUE PRODUCT HEO (LBS PER POUND FUEL) PRODUCT CO 2 (LBS PER POUND FUEL) FLUE PRODUCT NITROCEN (CBS PER POUND FUEL)			
<u>.</u>	PERCENT FUEL HYDROGEN	10.8000		
) 2	PERCENT FUEL OXYGEN PERCENT FUEL CARBON			
3 5				
3 2				
3				
2 2				
7				
3				
9		A service was serviced as the service of the servic	Carlos (1881), Carlos Carlos (1881),	
)				
•				

e-combostions calculate a locked BOILER EEFTGIENCY GENT NAME AND SECRET ASPACE OF THE SECRET ASPACE OF USER INITIALS 







### STATE OF FLORIDA

## DEPARTMENT OF ENVIRONMENTAL REGULATION

NORTHEAST DISTRICT

3426 BILLS ROAD JACKSONVILLE, FLORIDA 32207



BOB GRAHAM GOVERNOR VICTORIA J. TSCHINKEL SECRETARY

> G. DOUG DUTTON DISTRICT MANAGER

APPLICATION TO OPERATE/CONSTRUCT AIR POLICATION Fuel  SOURCE TYPE: Steam Power Boiler [ ] New 1 [ ]	
APPLICATION TYPE: [ ] Construction [ X] Operation [ ] Mo	dification (To A054-58340)
COMPANY NAME: Georgia-Pacific Corporation	COUNTY: Putnam
Identify the specific emission point source(s) addressed i	n this application (i.e. Lime
Kiln No. 4 with Venturi Scrubber; Peaking Unit No. 2, Gas	
SOURCE LOCATION: Street State Road 216 (North Side)	City Palatka
UTM: East 434.0	North3283.4
Latitude 29° 41' 00"N	Longitude 81° 40' 45"W
APPLICANT NAME AND TITLE: Georgia-Pacific Corporation	
APPLICANT ADDRESS: P.O. Box 919 Palatka, Flor	ida 32077
SECTION I: STATEMENTS BY APPLICANT A	ND ENGINEER
A. APPLICANT	
I am the undersigned owner or authorized representativ	e* of Georgia-Pacific Corp.
I certify that the statements made in this application permit are true, correct and complete to the best of m I agree to maintain and operate the pollution contraction facilities in such a manner as to comply with the p Statutes, and all the rules and regulations of the depalso understand that a permit, if granted by the depand I will promptly notify the department upon sale or establishment.	y knowledge and belief. Further ol source and pollution contro rovision of Chapter 403, Floridartment and revisions thereof.
*Attach letter of authorization Signed:	
Name and	Title (Please Type)
Date:	Telephone No.
B. PROFESSIONAL ENGINEER REGISTERED IN FLORIDA (where req	uired by Chapter 471, F.S.)

1 See Florida Administrative Code Rule 17-2.100(57) and (104)

DER Form 17-1.202(1) Effective October 31, 1982

This is to certify that the engineering features of this pollution control project have been designed/examined by me and found to be in conformity with modern engineering principles applicable to the treatment and disposal of pollutants characterized in the permit application. There is reasonable assurance, in my professional judgment, that

the pollution control facilities, when properly maintained and operated, will discharge an effluent that complies with all applicable statutes of the State of Florids and the rules and regulations of the department. It is also agreed that the undersigned will furnish, if authorized by the owner, the applicant a set of instructions for the proper maintenance and operation of the pollution control facilities and, if applicable, pollution sources. MINING ROLD Flaves 1 bulk AROLD L Harold L. Culp, PE Name (Please Type) PE 0029275 Ford, Bacon & Davis, Inc. Company Name (Please Type) P.O. Box 1894, Monroe, LA 71210 Mailing Address (Please Type) Florida Registration No. Dete: March 21, 1980 Telephone No. (318) 323-9000 29275 SECTION II: GENERAL PROJECT INFORMATION Describe the nature and extent of the project. Refer to pollution control equipment, and expected improvements in source performance as a result of installation. State whether the project will result in full compliance. Attach additional sheet if necessary. (See Attached Supplementary Report) Schedule of project covered in this application (Construction-Permit-Application-Only) Start of Construction February 28, 1986 Completion of Construction November 28, 1986 Modification-Addition of Control Equipment Costs of pollution control system(s): (Note: Show breakdown of estimated costs only for individual components/units of the project serving pollution control purposes. Information on actual costs shall be furnished with the application for operation permit.) Estimated cost of multi-cell electrostatic precipitator, ducting, ash removal and vertical stack with all installed appurtenances = \$2,150,000 Indicate any prayious DER permits, orders and notices associated with the emission point, including permit issuance and expiration dates. Permit No. A054-58340 Dated December 8, 1982, expires September 30, 1987. Consent Order OGC File No. 83-0803 - Florida Dept. of Environmental Regulation dated January 7, 1985

Page 2 of 12

DER Form 17-1,202(1)

Effective October 31, 1982

	power plant, hrs/yr 8760; if seasonal, describe: N/A	<del></del>
	this is a new source or major modification, answer the following questies or No) No	ions.
1.	Is this source in a non-attainment area for a particular pollutant?	No
	a. If yes, has "offset" been applied?	
	b. If yes, has "Lowest Achievable Emission Rate" been applied?	
	c. If yes, list non-attainment pollutants.	<del>,</del>
2,	Does best available control technology (BACT) apply to this source?  If yes, see Section VI.	No
3.	Does the State "Prevention of Significant Deterioriation" (PSD) requirement apply to this source? If yes, see Sections VI and VII.	No
4.	Do "Standards of Performance for New Stationary Sources" (NSPS) apply to this source?	No
5.	Do "National Emission Standards for Hazardous Air Pollutants" (NESHAP) apply to this source?	No
	"Reasonably Available Control Technology" (RACT) requirements apply this source?	No

b. If yes, in addition to the information required in this form, any information requested in Rule 17-2.650 must be submitted.

Attach all supportive information related to any answer of "Yes". Attach any justification for any answer of "No" that might be considered questionable.

## SECTION III: AIR POLLUTION SOURCES & CONTROL DEVICES (Other than Incinerators)

Raw Materials and Chemicals Used in your Process, if applicable:

Not Applicable Per Definition - Rule 17-2.100 (127), Process Weight Contaminants Utilization Description Type % Wt Rate - 1bs/hr Relate to Flow Disgram

- Process Rate, if applicable: (See Section V, Item 1) For Information Only To 97,900 lbs/hr Bark and/or 26,426 lbs/hr 1. Total Process Input Rate (lbs/hr): No. 6 Oil Plus Combustion Air
  - 2. Product Weight (lbs/hr): 360,000 lbs/hr, 1275 psig, 900°F Superheated Steam
- Airborne Contaminants Emitted: (Information in this table must be submitted for each emission point, use additional sheets as necessary)

	Name of	£a:	issionl	Allowed <sup>2</sup> Emission Rate per	Requested Allowable <sup>3</sup> Emlssion	Potenti Emissi		Relate to Flow
	Contaminant	Maxim lbs/		Rule 17-2	lbs/hr	lbs/yr	I/yr	Diagram
	Particulates Particulates	(0il) 4 (Bark)	3.3 190 30.1 570	0.1 lbs/ $\tilde{M}$ BTU 0.3 lbs/M BTU	43.3 130.1	379,308 1,314,000	190 657	Stack Stack
	so <sub>2</sub> (0i1)	1254	5492	2.751bs/MBTU	1254	11,571,960	5786	Stack
	Fuel NO(As NO)	168	736	N/A	N/A	1.471.680	736	Stack
١	CO (Bark)	97.9	429	N/A	N/A	857,604	429	Stack
ı	Methane Hydrocarbons Opacity	97.9 30%, 40	429 0% 2m	N/A 30%, 40% 2m	N/A 30%, 40% 2m	857, 604 40%	429	Stack

<sup>1</sup> See Section V, Item 2. \*At 8760 hrs/hr △ No Sampling Data - factored from AP-42 Chap. Reference applicable emission standards and units (e.g. Rule 17-2.600(5)(b)2. Table II,

 <sup>(1) - 0.1</sup> pounds per million BIU heat input)
 SO<sub>2</sub>-From oil only - used very infrequently, no SO<sub>2</sub> from bark.
 Calculated from operating rate and applicable standard.

AEmission, if source operated without control (See Section V, Item 3).

### D. Control Devices: (See Section V, Item 4)

Name and Type (Model & Serial No.)	Contaminant	Efficiency	Range of Particles Size Collected (in microns) (If applicable)	Basis for Efficiency (Section V Item 5)
Electrostatic	Particulates	Up to 95%	1/2 - 60	Cost Effective
Precipitator				Design Basis
(Not Selected Yet,				
Bids-Guaranteed				
Performance Data Not				
Yet Received)				

### E. Fuels

Type (Be Specific)	Consum			
	avg/hr	max./hr	Maximum Heat Inpu (MMBTU/hr)	
No. 6 Fuel Oil	Supplemental - Varies	3192	433.8	
Bark (Wood)	80,000 <u>+</u>	97,900	433.7	

\*Units: Natural Gas--MMCF/hr; Fuel Oils--gallons/hr; Coal, wood, refuse, other--lbs/hr.

Fuel Applysia. /a			
Fuel Analysis: (See Attached Report)			
Percent Sulfur: 2 1/2 (oil) 0 (Bark)	Percent Ash: 0.15+(oi1),	2.0 <sup>+</sup> (Bark)	
Density: 8.28 (oil), 21 lbs/cf (Bark) lbs/ga	l Typical Percent Nitrogen:	0.54 (oil), 0.1	(Bark
Heat Capacity: 18,350(oil), 4500(Bark) BTU/1	b 151,938 (oil)	BTU/gal	
Other Fuel Contaminants (which may cause air	pollution): Vanadium		
f. If applicable, indicate the percent of f	uel used for space heating.	Unknown Paper and	Pulp
Annual Average	Maximum	Mill	
G. Indicate liquid or solid wastes generate	d and method of disposal.		
100-900 lbs/hr ash to be collected from	the precipitator (excluding	mechanical	
dust collectors) and disposed of in a co	ontrolled landfill.		
	,		
	<del></del>		

tack Height:	232 A	oove Grade	ft. S	tack Diamet	er:	9	f
as flow Rate: 19	08,000 ACFM_	87,000	_DSCFM G	as Exit Tem	perature:	440	a
ater Vapor Conte	nt:1	8-21	% V	olocity:		51.9	F
				DR INFORMAT	,		
Type of Type Waste (Plast	O Type I ics) (Rubbish)			I Type IV (Pathological)		s (Solid By-p	
Actual lb/hr Inciner- ated							
Uncon- trolled (lbs/hr)							
escription of Wa	ste		N/A	<del></del>			
otal Weight Incl				Design C	nacity (lbe	/hr)	
Approximate Numbe	·						
lanufacturer	<del></del>			. :			
ste Constructed	<del></del>		Model	No	•		
	Volume (ft) <sup>3</sup>	Heat R	elease /hr)	Fu Type	el BTU/hr	Temperatur (°F)	0
Primary Chamber							
Secondary Chambe	ft.	Stack Dia	mter:		Stack	Temp.	
						·	
tack Height:		_ACFH	······································		•		
itack Height:	ns per day de:	ign capac	ity, subm	it the emi			ata
Secondary Chambe  Stack Height:  Gas Flow Rate:  #If 50 or more to dard cubic foot d	ns per day de ry gas correc	sign capac ted to 50%	ity, subm	it the emi	sions rate	in grains per	ata

Page 6 of 12

Effective November 30, 1902

Brief description	of ope	rating ch	aracte	ristic	cs of	control	devi	:09:			
				N/A							<u> </u>
ltimate disposal sh, etc.):	of any	effluent	ather	than	that	emitted	from	the	stack	(scrubber	water,
	•			N/A							
					<del></del>						
	<del></del>	<del></del>									
	<del></del>									· · · · · · · · · · · · · · · · · · ·	

NOTE: Items 2, 3, 4, 6, 7, 8, and 10 in Section V must be included where applicable.

#### SECTION V: SUPPLEMENTAL REQUIREMENTS

Please provide the following supplements where required for this application.

- 1. Total process input rate and product weight -- show derivation [Rule 17-2.100(127)]
- 2. To a construction application, attach basis of emission estimate (e.g., design calculations, design drawings, pertinent manufacturer's test data, etc.) and attach proposed methods (e.g., FR Part 60 Methods 1, 2, 3, 4, 5) to show proof of compliance with applicable standards. To an operation application, attach tast results or methods used to show proof of compliance. Information provided when applying for an operation permit from a construction permit shall be indicative of the time at which the test was made.
- Attach basis of potential discharge (e.g., emission factor, that is, AP42 test).
- 4. With construction permit application, include design details for all air pollution control systems (e.g., for baghouse include cloth to air ratio; for scrubber include cross-section sketch, design pressure drop, etc.)
- 5. With construction permit application, attach derivation of control device(s) efficiency. Include test or design data. Items 2, 3 and 5 should be consistent: actual emissions = potential (1-efficiency).
- 6. An 8 1/2" x 11" flow diagram which will, without revealing trade secrets, identify the individual operations and/or processes. Indicate where raw materials enter, where solid and liquid waste exit, where gaseous emissions and/or airborne particles are evolved and where finished products are obtained.
- 7. An 8 1/2" x 11" plot plan showing the location of the establishment, and points of air-borne emissions, in relation to the surrounding area, residences and other permanent structures and roadways (Example: Copy of relevant portion of USGS topographic map).
- 8. An 8 1/2" x 11" plot plan of facility showing the location of manufacturing processes and outlets for airborne emissions. Relate all flows to the flow diagram.

DER Form 17-1.202(1) Effective November 30, 1982

he appropriate application fee in accordance with Rule 17-4.05. The check should ade payable to the Department of Environmental Regulation.	b e
ith an application for operation permit, attach a Certificate of Completion of Co truction indicating that the source was constructed as shown in the constructi	

	SECTION VI: BEST	AVAILABLE CONTROL TECHNOLOGY
Α.	Are standards of performance for ne applicable to the source?	w stationary sources pursuant to 40 C.F.R. Part 60
	[ ] Yes [X] No	
	Contaminant	Rate or Concentration
-		
в.	Has EPA declared the best available yes, attach copy)	e control technology for this class of sources (If
	[ ] Yes [X] No	
	Contaminant	Rate or Concentration
<del></del>		
c.	What emission levels do you propose	as best available control technology?
	Contaminant	Rate or Concentration
****	N/A	
٥.	Describe the existing control and to	reatment technology (if any).
	1. Control Device/System:	2. Operating Principles:
	3. Efficiency:*	4: Capital Costs:
* E	xplain method of determining	
	R Form 17-1.202(1) fective November 30, 1982	Page 8 of 12

	5.	Useful Life:		6.	Operating Costs:	
	7.	Energy:		8.	Maintenance Cost:	
	9.	Emissions:				
		Contaminant			Rate or Concentration	
	····	1				
		·				
	10.	Stack Parameters				
	a.	Height:	ft.	b.	Diameter:	ft.
	c.	Flow Rate:	ACFM	d.	Temperature:	°F.
	e.	Velocity:	FPS			
Ε.		cribe the control and treatment additional pages if necessary).	techn	olog	y available (As many types as applicat	ole,
	1.	•				
	a.	Control Device:		b.	Operating Principles:	
	c.	Efficiency:1		d.	Capital Cost:	
	e.	Useful Life:		f.	Operating Cost:	
	g.	Energy: 2		h.	Maintenance Cost:	
	i.	Availability of construction ma	terial	ls an	d process chemicals:	
	j.	Applicability to manufacturing	proces	ses:		
	ķ.	Ability to construct with contract within proposed levels:	rol de	vice	, install in available space, and ope	rate
	2.	(x,y) = (x,y) + (x,y) + (x,y) = (x,y) + (x,y) + (x,y) + (x,y) = (x,y) + (x,y				
	8.	Control Device:		b.	Operating Principles:	
	c.	Efficiency: 1		d.	Capital Cost:	
	е.	Useful Life:		f.	Operating Cost:	
		Energy: 2		h.	Maintenance Cost:	
	g.	chary,				

Applicability to manufacturing processes: Ability to construct with control device, install in available space, and operate within proposed levels: 3. Control Davice: Operating Principles: a. Efficiency: 1 Capital Cost: c. Useful Life: Operating Cost: Energy: 2 g. Maintenance Cost: Availability of construction materials and process chemicals: Applicability to manufacturing processes: Ability to construct with control device, install in available space, and operate within proposed levels: 4. Control Device: Operating Principles: Efficiency: 1 Capital Costs: c. Operating Cost: Useful Life: Energy: 2 h. Maintenance Cost: Availability of construction materials and process chemicals: Applicability to manufacturing processes: Ability to construct with control device, install in available space, and operate within proposed levels: F. Describe the control technology selected: Efficiency: 1 1. Control Device: Useful Life: 3. Capital Cost: Energy: 2 5. Operating Cost: Manufacturer: 7. Maintenance Coat: Other locations where employed on similar processes: a. (1) Company: (2) Meiling Address: (4) State: (3) City: 1 Explain method of determining efficiency. <sup>2</sup>Energy to be reported in units of electrical power - KWH design rate.

Page 10 of 12

DER Form 17-1.202(1)

Effective November 30, 1982

(5) Environmental Maneger:	
(6) Telephone No.:	
(7) Emissions: 1	
Contaminant	Rate or Concentration
(8) Process Rate: 1	
b. (1) Company:	
(2) Mailing Address:	
(3) City:	(4) State:
(5) Environmental Manager:	
(6) Telephone No.:	
(7) Emissions: 1	
Contaminant	Rate or Concentration
(8) Process Rate: 1	· · · · · · · · · · · · · · · · · · ·
10. Reason for selection and descrip	tion of systems:
<sup>1</sup> Applicant must provide this information available, applicant must state the reas	
	ON OF SIGNIFICANT DETERIORATION
A. Company Monitored Data	N/A
1no. sitesT	SP Wind spd/dir
Period of Monitoring month	/ / to / / day year month day year
Other data recorded	
Attach all data or statistical summar	ies to this application.
*Specify bubbler (B) or continuous (C).	
DER Form 17-1.202(1) Effective November 30, 1982	age 11 of 12

	4.	Institute intaction, Field	a sua Esporstory				
	8.	Was instrumentation E	PA referenced or its	quivalent?	[ ] Yes	[ ] No	
	٥.	Was instrumentation c	alibrated in accordance	e with Depa	artment p	rocedures?	
		[ ] Yes [ ] No [ ]	Unknown				
3.	Met	eorological Data Used	for Air Quality Hodeli	ng			
	1.	Year(s) of date	from / / month day year	to	day yea	<u>-</u>	
	2.	Surface data obtained	from (location)				
	3.	Upper air (mixing hei	gḥt) dạta obtainad fro	m (location	1)		
	4.	Stability wind ross (	STAR) data obtained fr	om (locatio	on)(no		
С.	Com	puter Modela Uaed	•				
	1.			Modified?	If yea,	sttsch desc	ription.
	2.			Modified?	lf yes,	attach desc	ription.
	3.			Modifiad?	If yes,	attach desc	ription.
	4.	•		Modified?	If yes,	attach desc	ription.
		ach copies of all fine le output tables.	l model rune showing i	nput data,	receptor	locations,	and prin-
٥.	Αρρ	licants Maximum Allows	ble Emission Data		`		
	Pol	lutant	Emission Rate	•			
		TSP	•	91:	ama/sec		
		502		gr	ams/sec		
Ξ.	£ m i	ssion Data Used in Hod	eling				
	poi	ach list of emission s nt source (on NEDS poi I normal operating time	int number), UTM coord				•
۴.	Att	ach ali other informat	ion supportive to the	PSD review.			
Ģ.	ble	cuss the social and ec technologies (i.e., sessment of the environ	jobs, payroll, produ	iction, tax			

the requested best available control technology.

H. Attach scientific, engineering, and technical material, reports, publications, journals, and other competent relevant information describing the theory and application of

#### SUPPLEMENTAL REPORT

INSTALLATION OF AN ELECTROSTATIC PRECIPITATOR ON THE NUMBER 4 COMBINATION POWER BOILER AT THE PALATKA, FLORIDA MILL OF GEORGIA-PACIFIC CORPORATION.

#### Background

The Number 4 boiler was erected in 1965 and is certified by an existing operating permit. The boiler fires a combination of Number 6 residual fuel oil and bark (wood). The major fuel used in this boiler is bark due to its economic availability. The flue gas is treated for particulate removal at the present time through the use of three sets of mechanical collectors in series. Despite their pressure drops these have been found to be effective devices. Permit-wise (A054-58340) the boiler has been rated at a maximum heat input rate of 425 MM BTU/hr on bark (per original permit of December 8, 1982) and 360 MM BTU/hr on oil thus its current emission rate is limited by these values.

The boiler has essentially met necessary emission criteria over the years but it's been found difficult to meet existing requirements when operating at maximum capacity on bark, despite its multiple set of mechanical collectors.

Due to stack sampling difficulties and some alleged violations, various mutually acceptable solutions were arrived at recently by the Company and the Florida Department of Environmental Regulation which were contained in a January 1985 Consent Order. The Company has submitted a schedule for installing additional emission control equipment on the boiler along with various intervals of stack monitoring and reportings of performance.

## Proposed Project

To ensure reliable, continuous removals of bark related sands and char the Company has decided to employ the best available control technology on this boiler at this time. This will allow the Company greater latitude in the selection of available bark and commercially plentiful oil supplies without concern for random firing conditions that could encroach on current emission limits.

The Company has initiated the necessary engineering, planning, bid selection and procurement work necessary to install a high intensity, multi-field, rigid frame electrostatic precipitator on this boiler per a schedule previously approved by the Department of Environmental Regulation.

#### Facility Details

A study of the present steaming facilities is underway including a computerized analysis of combustion conditions (see Exhibit I and II). With bark and fuel oil, the unit has been found to demonstrate the following combustion design related characteristics:

1275 psig steam at 900°F = 1437.4 BTU/Ib Feedwater at 445°F saturated = -424.1 BTU/Ib

1013.3 BTU/lb

Bark Heat Input 1013.3 X 300,000 lbs/hr capacity on bark only 70.09% efficiency

= 433,713,000 BTU/hr heat input with gross fuel requirement of 97,900 lbs/hr.

Fuel Oil Heat Input 1013.3 X 360,000 lbs/hr capacity on oil only 84.08% efficiency

= 433,858,230 BTU/hr heat input with gross fuel requirement of 26,426 lbs/hr

As noted in Section III (p.4) of the attached Application, under current Florida regulations, the boiler particulate emission allowable firing bark is 130.1 lbs/hr rather than the maximum 114 lbs/hr cited in the present permit.

Similarly SO<sub>2</sub> allowables from oil (2.75 lbs/MM BTU/hr input) are 1192.9 lbs/hr contrasted to the 962.5 lbs/hr permit limit. NO, CO and methane hydrocarbon values are also listed in Section III for Departmental purposes.

Despite these more applicable allowables, the Company is requiring that precipitator suppliers-bidders meet a particulate requirement of 0.25 lbs/MM BTU/hr at a flue gas flow of 30 percent over the base flow of 198,000 acfm derived from the combustion evaluation. However to allow appropriate standby capacity for the adjacent power boiler a peak design flow of 267,000 acfm is being used.

A simplified schematic of the proposed installation is depicted by Sketch C-1712-1 attached. The general plot plan of the entire mill is shown in Sketch C-1712-2 and the immediate boiler area layout is illustrated by Sketch C-1712-3.

An adjacent, similarly sized modern precipitator will be ducted together with this boiler (serving Number 5 power boiler certified by a separate Permit) for standby treatment purposes. The precipitator serving this

boiler will be equipped with isolation dampers, a complete ash removal system and a separate 232 foot (above grade) stack outfitted with the necessary platforms, sampling ports, monorails, etc. required for monitoring purposes.

A typical analysis of the wood waste (bark) and fuel oil expected to be used in this service is listed in Table I. These and similar grades of fuel will be purchased and should fall within the ranges shown.

## TABLE I

## TYPICAL FUEL OIL ANALYSIS OF SUPPLIES USED BY GEORGIA-PACIFIC

## PALATKA MILL\*

Degrees API at 60°F	10.9
Specific Gravity at 60°F	0.99
Flash Point, °F	178
BS & W, %	1.65
Viscosity, SFS at 122°F	275
Asphaltene, %	9.9
Ash, %	0.15
Carbon, %	85.7
Hydrogen, %	10.6
Nitrogen, %	0.54
Sulfur, %	2.5
Oxygen, %	0.6
Vanadium, ppm	550
BTUs per pound	18,350

<sup>\*</sup>Analyzed by Fuel Engineering Company of New York in Thornwood, New York in 1984.

## TABLE I (CONTINUED)

# TYPICAL WOOD (HOGGED BARK) ANALYSIS OF SUPPLIES RECEIVED BY GEORGIA-PACIFIC

## PALATKA MILL\*

Weight, lbs/cf	21 +
Dry Ash, %	2 +
Fixed Carbon, %	25.2
Hydrogen, %	3.1
Moisture, %	50.0
Oxygen, %	21.5
Volatile Matter, %	79
Nitrogen, %	0.1
Sulfur, %	0
Heating Value As Fired, BTU/Ib	4500

<sup>\*</sup> Analyzed By Georgia-Pacific Corporation

allowed.

#### Air Emissions

With the main particulate loading comprised of inorganic sand and carbonaceous char, it is expected this technical application will ensure complete compliance with present particulate emission limits. Up to 95% removals under this loading regime are expected.

Some minor SO<sub>2</sub> removals (when oil is burned) will also be experienced as about 5% of the carbonaceous sulfur based residue will be removed along with the captured ash agglomerates. Visual opacity levels will also be positively affected.

Derivation of various values used to develop the Table in Section III (C) of the Application are as follows:

## Particulates (Using Bark)

433.7 MM BTU/hr input at 0.3 lbs/MM BTU = 130.1 lbs/hr Ash = 97,900 lbs/hr bark  $\frac{X}{100}$  2% ash = 1958 lbs/hr plus soot blows

Precipitator to remove up to 95% leaving 98-124 lbs/hr
Potential emission, uncontrolled = 150 lbs./hr X 8760 hrs/yr
(Using existing triple set = 1,314,000 lbs/yr or of installed mechanical 657 tons/yr collectors.
Without collectors = 8760 tons/yr)
Ash = 26,426 lbs/hr oil X 0.15% ash = 39.6 lbs/hr < 43.3 lbs/hr

## SO<sub>2</sub> (Using No. 6 Fuel Oil)

433.8 MM BTU/hr input at 2.75 lbs/MM BTU = 1192.9 lbs/hr  $SO_2 = \frac{26,426}{2,000}$  t/hr oil X 2.5% S X 2 x .95 (S-+SO<sub>2</sub>) (5% in ash dropout)

 $=\frac{62.7}{1008}$  = 0.627 tons/hr SO<sub>2</sub>

=  $1254 lbs/hr SO_2$ 

and 1321 lbs/hr SO2 with no ash dropout.

Potential emission, uncontrolled = 1321 lbs/hr X 8760 hrs/yr = 11,571,960 lbs/yr or 5786 tons/yr of SO<sub>2</sub>

## Fuel NO (excludes thermal NO using oil)

Federal Criteria 0.3 lbs/MM BTU = 130.1 lbs/hr as  $NO_{\times}$  (NO +  $NO_{2}$ )

= 736 tons/yr of fuel derived NO.

NO = 13.21 t/hr oil X 0.54% N X 2.14 X 0.55

(NO is 95% NO) (N NO) (Conversion)

(CE4-34)

= 8.39 = 0.084 tons/hr NO

= 168 lbs/hr NO

Potential emission, uncontrolled = 168 lbs/hr X 8760 hr/yr

= 1,471,680 lbs/yr or

## CO, Methane Hydrocarbons (Using Bark)

As taken from EPA AP-42 Chap. 1 data. Same factor for both emissions.

97,900 tons/hr (2 lbs/ton) = 97.9 lbs/hr

2,000 = 857,604 lbs/yr or

= 429 tons/yr of CO and

429 tons/yr of Methane Hydrocarbons

#### Opacity

Per current State of Florida Regulations.


Other elements in the fuel will be converted through combustion to their basic oxidative status.


During operations stack emissions will be analyzed per Permit requirements. EPA Standard Reference Methods (Method 1, 2, 3, 4, 5, 6, 7, 9, 10, 17, etc) would be utilized as may be required and applicable.


## Closure

Georgia-Pacific Corporation intends to employ the best available control technology at this time to reduce particulate and related emissions from their Number 4 Combination Boiler. A field erected, rigid frame electrostatic precipitator will be used. Internal collector (gas) velocities, specific (plate) collection area, wire length, rapper parameters and power inputs will be selected for the equipment to ensure appropriate design sizing. Full compliance with current State emission requirements will be ensured.

Per attached Exhibit I and II the Company requests the appropriate heat input rating (BTU/hr) be established for this boiler and the related, allowable emission rates per Rule 17-2 be authorized as contained within the submitted Application Form 17-1.202(1).







NO. 4 COMBINATION BOILER USING NO. 6 FUEL OIL ONLY AT FULL COAD RATING OF 360,000 16s/hr. EXHIBIT I MONROE, LA. 

0 0 CON BUSTIONS CALCULATION S BOILER EFFICIENCY FAN, SIZING JOB NUMBER ---- C1712 - GECRGIA PACIFIC PALATKA, FL CLIENT NAME ---USER INITIALS ---DATE OF RUN ----- 02/06/85 TIME OF RUN ----- 09:38:05

# C U M B U S ; I U N C A C C U C A ? I O N	•	
FUEL NAME: QIL #6		
BTU'S PER POUND OF FUEL	100-0000	
CONSTITUENT PERCENT 32 SULFUR 2.50%		
33 CARBUN 85.85% , 30 HYDROGEN 10.80% . 29 NITROGEN 0.70%		
O.15% TOTAL PERCENTAGE 100-00%		
PERCENT EXCESS AIR	21.4000\$	
THEORET ICAL AIR (LBS PER POUND FUEL)	13.7122	
TOTAL DRY GAS (LBS PER POUND FUEL)	16.6775 1.1816	
PRODUCT OUZ (LBS PER POUND FUEL)  FLUE PRODUCT NITROGEN (LBS PER POUND FUEL)	3.1955 12.8032	
PERCENT FUEL NYDROGEN  PERCENT FUEL SULFUR  PERCENT FUEL OXYGEN	2.5000 0.0 85.8500	
PERCENT FUEL CARBON	0.20.000	

<b>3</b>		
•		
* C UM 8 U S T 1 U N C A L C U L A	1 1 U K 5 *	
TOTALS FOR ALL FU	ELS #	
**************************************	*****	
	364338.0230	
TOTAL THEORETICAL PLUS EXCESS) CONSUSTION AIR	•	
TOTAL FLUE DRY GAS TOTAL FLUE PRODUCT H20 TOTAL FLUE PRODUCT CG2 TOTAL FLUE PRODUCT NITROGEN	31225.0000 84444.0000	
TOTAL FILEL HYDROGEN		
TOTAL FUEL SULFUR  YOTAL FUEL OXYGEN  TOTAL FUEL CARBON	<del>~</del>	
7		
		)
		. •

ê		•	
3			
•	******************		
ں	* BUILER EFFICIENCY* ***********************************		
	PERCENT COMBUSTIBLE IN ASH	2.0000	
•	COMBUSTION AIR TEMPERATURE (FAHRENHEIT)  PERCENT RADIATION LOSSES	425.0000 80.0000 0.4000	
Ð	PERCENT MANUFACTURER S UR UNMEASURED LOSSES	1.5000	
	ENTHALPY OF WATER VAPOR AT 1 PSIA AND EXIT TEMP		The control of the co
•	ENTHALPY OF LIQUID WATER AT COMBUSTION GAS TEMP	48.0000	
3	HEAT LOSS DUE TO DRY GAS	7.50494 6.3184 <b>8</b>	
	HEAT LOSS DUE TO AZE MOTSTURE  HEAT LOSS DUE TO COMBUSTIBLE IN REFUSE  HEAT LOSS DUE TO RADIATION  HEAT LUSS DUE TO UNMEASURED LOSSES	0.1866\$ 0.0023\$ 0.4000\$	
2 A	TOTAL HEAT LOSSES	15.9122	
•	BOILER EFFICIENCY	84-08787	
<b>9</b> ×			
<b>3</b>			
•			
			17 186.3 2世紀 - 188.4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
<b>3</b> 4			
3			
	The state of the s	The state of the s	<u> 1988 - North Control of the Contro</u>

•							•	
		*****	****					
::		*********	1 + + + + + + + + + + + + + + + + + + +					•
PERCENT	FFFICIENCY CF	TINCHES H201		81.6000				***
PERCENT TOTAL VO	SAFETY FACTOR	O FAN		0.5000 11.2332.1879 162.4067	**************************************			
		DRAFT FAN		10:0000	を では、 の の の の の の の の の の の の の			
PERCENT PERCENT	EFFICIENCY CF	TINCHES H201 ID FAN D FAN FOR 10 FAN		71.5000 0.5000 10.0000				
TOTAL VO HURSEPOW	LUME OF FLUE ER FOR INDUCE	GAS (CFM) AC D DRAFT FAN NEGLECTING	TUAL	193827-1875 +26.4197 +CTORS)				
					<u> X.</u>			
						. 17 		

NO. 4 COMBINATION BOILER USING MAXIMUM BARK FEED ONLY AT LOAD OF 300,000 15/hr. EXHIBIT

\* COMBUSTION CALCULATIONS \* FAN SIZING 108 NUMBER ----- C1712 CLIENT NAME ----- GEORGIA PACIFIC USER INITIALS ---- ADS \_DATE\_OF\_RUN\_---- 02/05/85\_ TIME OF RUN ----- 09:28:01

			-				
		*****	****	***			
	* C O M 8 U S	TION. CALC	U L A T I O N	S *		1	
•	UEL NAME BARK (WOOD)						
<b>F</b>	FUEL USE RATE AS A WEIGH	T PERCENTAGE		100.0000 4500.0000	·		
	CONSTITUENT	FUEL PERCENT 50.00%					
3	28 HATER VAPOR 33 CARBON 30 Hydrogen	23-40% 3-10%					
3	31 OXYGEN 34 ASH	21.50%					
	ERCENT EXCESS AIR	100-008		28.1000%			140 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -
ī	OTAL AIR (LBS PER POUND HEGRET ICAL AIR (LBS PER	FUEL)		3.6321 2.8353			
	T 128.10% THEORETICAL A	IR: R POUND FUEL)		3.8336	Reservation (Fig. 4 by 1)	The section of the professional and the section of	The second of th
	FLUE PRODUCT HZO (LBS PER FLUE PRODUCT NITROGEN	POUND FUEL)	L)	0.8243 0.8574 2.7920			
و	ERCENT FUEL HYDROGEN	<del>, </del>		3.1000 0.0	<u>Maria, Parria di Santa di San</u>		
₽	ERCENT FUEL OXYGEN			21.5000			
			· · · · · · · · · · · · · · · · · · ·		<u>*************************************</u>		
<u> </u>							
		<u> 14년</u>			<u> </u>		
· · · · ·				<u> </u>			
<u> </u>		<u>andri di di</u>			ego (1911) sesat (	<u> - 1 - 1975年 (報答表面) 蒙</u>	

**\*** \* COMBUSTION CALCULATIONS \* \* TOTALS FOR ALL EUELS . \*\*\*\*\*\*\*\*\*\* 97900.00001 TOTAL FUEL RATE (LBS PER HOUR) -277578.6875 THEORETICAL COMBUSTION AIR -TOTAL (THEORETICAL PLUS EXCESS) COMBUSTION AIR -----355578.0000 AL TOTAL COMBUSTION AIR ... 375311.0000 TOTAL FLUE DRY GAS -----80695.3750 TOTAL FLUE PRODUCT H20 ----TOTAL FLUE PRODUCT CO2 -----83937.0625 TOTAL FLUE PRODUCT NITROGEN ------ 273332.7500 TOTAL FUEL HYDROGEN ---303489.9170 0.0 TOTAL FUEL SULFUR ----TOTAL FUEL DXYGEN - 2104849.6094 2290858 9844 TOTAL FUEL CARBON ----

<b>C</b>			
<b>5</b>	****		
2	* BOILER EFFICIENCY *		
<b>.</b>	PERCENT COMBUSTIBLE IN ASH	2.0000	
12	EXIT GAS TEMPERATURE (FAHRENHEIT)  COMBUSTION AIR TEMPERATURE (FAHRENHEIT)  PERCENT RADIATION LOSSES	429.0000 80.0000 	) 55 64 95
	PERCENT MANUFACTURER'S OR UNMEASURED LOSSES	1.5000	
	ENTHALPY OF WALER VAPOR AT 1 PSIA AND EXIT TEMPENTHALPY OF LIQUID WATER AT COMBUSTION GAS TEMP	1250a1426 48a0000	
<b>9</b>	HEAT LOSS DUE TO DRY GAS	6.9516 <b>%</b> 20.7582 <b>%</b>	76 30 34 27
	HEAT LOSS DUE TO AIR MOISTURE		
	TOTAL HEAT LOSSES	1.5000\$ 	1
33 32	BOILER EFFICIENCY	70-0983	
			40 A
•			A
<b>D</b>			
		e No.	
<b>3</b>		en e	

	*******									
		) k			·	·	•		· .	
PERCENT FEETCLENCY OF FO	) FAN		81.6000	<b>)</b>						
PERCENT SAFETY FACTOR FO	OR FO FAN		10.0000							
TOTAL VOLUME OF COMBUST I HORSEPOWER FOR FORCED OF	ION AIR (CFM)	, , , , , , , , , , , , , , , , , , , ,	90562-4375						•	
PERCENT EFFICIENCY OF 10	) FAN		71-5000	,						
PERCENT SAFETY FACTOR FO	OR 10 FAN		10.0000	)						
HORSEDOMER FOR INDUCED D	RAFT FAN		197681.0000 521.8777	) 7						
(MCS GESCA)										
							•			
	·	·						No. of Co. Co. State State Server & C.		9 9
		<u> </u>	12. The state of t							
	TOTAL HEAD FOR FD FAN ( PERCENT EFFICIENCY OF FO PERCENT LEAKAGE FOR FD I PERCENT SAFETY FACTOR FO  TOTAL VOLUME OF COMBUST HORSEPOWER FOR FORCED DO  TOTAL HEAD FOR ID FAN ( PERCENT EFFICIENCY OF ID PERCENT LEAKAGE FOR ID I PERCENT SAFETY FACTOR FO  TOTAL VOLUME OF FLUE GAS HORSEPOWER FOR INDICED OF	TOTAL HEAD FOR FO FAN (INCHES H20)  PERCENT EFFICIENCY OF FO FAN  PERCENT LEAKAGE FOR EO FAN  TOTAL VOLUME OF COMBUSTION AIR (CFM)  HORSEPOWER FOR FORCED DRAFT FAN  TOTAL HEAD FOR ID FAN (INCHES H20)  PERCENT EFFICIENCY OF ID FAN  PERCENT LEAKAGE FOR ID FAN  PERCENT LEAKAGE FOR ID FAN  TOTAL VOLUME OF FLUE GAS (CFM)  TOTAL VOLUME OF FLUE GAS (CFM)	TOTAL HEAD FOR FD FAN (INCHES H20)  PERCENT EFFICIENCY OF FD FAN  PERCENT LEAKAGE FOR FD FAN  PERCENT SAFETY FACTOR FOR FD FAN  TOTAL VOLUME OF COMBUSTION AIR (CFM)  HORSEPOWER FOR FORCED DRAFT FAN  TOTAL HEAD FOR ID FAN (INCHES H20)  PERCENT EFFICIENCY OF 10 FAN  PERCENT LEAKAGE FOR ID EAN  PERCENT SAFETY FACTOR FOR 1D FAN  TOTAL VOLUME OF FLUE GAS (CFM)	TOTAL HEAD FOR FD FAN (INCHES H20)  PERCENT EFFICIENCY OF FD FAN  PERCENT LEAKAGE FOR ED FAN  D.5000  TOTAL VOLUME OF COMBUSTION AIR (CFM)  PERCENT SAFETY FACTOR FOR FD FAN  TOTAL VOLUME OF COMBUSTION AIR (CFM)  PERCENT EFFICIENCY OF 10 FAN  PERCENT EFFICIENCY OF 10 FAN  PERCENT LEAKAGE FOR ID FAN  PERCENT LEAKAGE FOR ID FAN  TOTAL VOLUME OF FLUE GAS (CFM)  TOTAL VOLUME OF FLUE GAS (CFM)	TOTAL HEAD FOR FD FAN (INCHES H20) 6.4000 PERCENT EFFICIENCY OF FD FAN 81.6000 PERCENT LEAKAGE EOR ED FAN 0.5000 PERCENT SAFETY FACTOR FOR FD FAN 10.0000  TOTAL VOLUME OF COMBUSTION AIR (CFM) 90562.4375 HORSEPOMER FOR FORCED DRAFT FAN 111.7292  TOTAL HEAD FOR ID FAN (INCHES H20) 12.0000 PERCENT EFFICIENCY OF 10 FAN 71.5000 PERCENT LEAKAGE EOR 10 EAN 0.5000 PERCENT SAFETY FACTOR FOR 10 FAN 10.0000  TOTAL VOLUME OF FLUE GAS (CFM) ACTUAL 197681.0000	TOTAL HEAD FOR FD FAN (INCHES H2D) 6.4000  PERCENT EFFICIENCY OF FD FAN 81.6000  PERCENT LEAKAGE EOR ED FAN 9.5000  PERCENT SAFETY FACTOR FOR FO FAN 10.0000  TOTAL VOLUME OF COMBUSTION AIR (CFM) 90562.4375  HORSEPOMER FOR FORCED DRAFT FAN 111.7292  TOTAL HEAD FOR ID FAN (INCHES H2D) 12.0000  PERCENT EFFICIENCY OF 1D FAN 71.5000  PERCENT LEAKAGE FOR ID FAN 0.5000  PERCENT SAFETY FACTOR FOR ID FAN 10.0000  TOTAL VOLUME OF FLUE GAS (CFM) 10.0000	TOTAL HEAD FOR FD FAN (INCHES H20) 6.4000 PERCENT EFFICIENCY OF FD FAN 81.6000 PERCENT LEAKAGE FOR ED FAN 9.5000 PERCENT SAFETY FACTOR FOR FD FAN 10.0000  TOTAL VOLUME OF COMBUSTION AIR (CFM) 90562.4375 HORSEPOMER FOR FORCED DRAFT FAN 111.7292  TOTAL HEAD FOR ID FAN (INCHES H20) 12.0000 PERCENT EFFICIENCY OF 10 FAN 71.5000 PERCENT LEAKAGE FOR 10 FAN 71.5000 PERCENT SAFETY FACTOR FOR ID FAN 10.0000  TOTAL VOLUME OF FLUE GAS (CFM) 10.0000	TOTAL HEAD FOR FD FAN (INCHES H20)	TOTAL HEAD FOR FD FAN (INCHES H20)	TOTAL HEAD FOR FD FAN (INCHES H2O) 6.4000 PERCENT EFFICIENCY OF FD FAN 9.5000 PERCENT LEAKAGE EDR ED FAN 9.5000  PERCENT SAFETY FACTOR FOR FD FAN 10.0000  TOTAL VOLUME OF COMBUSTION AIR (CFM) 90562-4375 HORSEPOWER FOR FÜRCED DRAFT FAN 111.7292  TOTAL HEAD FOR ID FAN (INCHES H2O) 12.0000 PERCENT EFFICIENCY OF 10 FAN 71.5000 PERCENT LEAKAGE EDR LD EAN 9.5000 PERCENT SAFETY FACTOR FOR ID FAN 10.0000  TOTAL VOLUME OF FLUE GAS (CFM) 197681.0000  TOTAL VOLUME OF FLUE GAS (CFM) 77777