



Dept. Of Environmental Protection

JAN 06 2011

Southwest District

KA 690-10-03
January 4th, 2011

David Zell
Engineering Specialist IV
Florida Department of Environmental Protection
Southwest District
13051 N. Telecom Parkway
Temple Terrace, FL 33637-0926

Re: Initial Title V Air Operation Permit Application – Project No. 1190042-007-AV
American Cement Company, LLC
Sumterville Cement Plant
Request for Additional Information

Dear Mr. Zell:

Per your request for additional information to the initial Title V air operation permit application, below are the responses to the questions. Please refer to the attachments where it is indicated. RO and PE certifications statement are also included in the attachment 1.

1. Facility Process Flow Diagram Attachment – The Facility Process Flow Diagram attached to the application shows the facility as having separate wet process and dry process equipment ahead of the rotary kiln. It also shows an Optional Preheater/Precalciner or an Optional Preheater as part of the Dry Process. Based on information obtained during a site visit, the facility is using only a dry process (i.e., there is no wet process equipment) and is equipped with a preheater/precaciner as part of the dry process. Please resubmit the Facility Process Flow Diagram correcting/clarifying the items noted above, and making any other corrections/clarifications needed to accurately represent the facility process flow as it was actually built and is being operated.

Response:

Facility Process Flow Diagrams have been attached to show actual processes. See attachment 2 for details.

2. NSPS Subpart F Applicable Requirements - NSPS 40 CFR 60 Subpart F as amended in the September 9, 2010 Federal Register (effective date of November 8, 2010 , which will be prior to the effective date of the initial Title V operation permit for this facility) has additional requirements for kilns and clinker coolers for which construction

commenced after June 16, 2008. In order to confirm whether these requirements are applicable to this facility, please provide the date(s) of commencement of construction for the kiln and for the clinker cooler and the basis for these dates.

Response:

The actual commencement of construction date for the Kiln is March 13, 2007; Gantt Chart line 417 for Preheater Foundations.

The actual commencement of construction date for the Cooler is July 9, 2007; Gant Chart line 510 for Cooler/Burner Building Foundations.

See attachment 3 for details.

3. Subpart OOO Applicable Requirements - NSPS 40 CFR 60 Subpart OOO (Standards of Performance for Nonmetallic Mineral Processing Plants) is applicable to EU 001 (Raw Material Quarrying, Crushing and Storage). This is not reflected in the application, as an identification of applicable requirements attachment was not provided for EU 001. Please provide such attachment. (See also Note below item 4. below.) Subpart OOO, as amended in the April 29, 2009 Federal Register, has additional requirements for mineral processing equipment for which construction commenced on or after April 22, 2008. In order to confirm whether these requirements are applicable to any of the non-metallic mineral processing equipment at this facility, please provide the date(s) of commencement of construction for the limestone processing, storage, and handling equipment at this facility and the basis for these dates.

Response:

The actual commencement of construction date for the Raw Material Storage is February 12, 2007; Gantt Chart line 197 for Raw Material Building excavation.

The commencement of construction date for the Quarry is not specified, but the Request for Change Order dated October 18, 2007 with attached schedule shows active construction in the Quarry.

See attachment 4 for details.

4. Subpart Y Applicable Requirements - NSPS 40 CFR 60 Subpart Y (Standards of Performance for Coal Preparation and Processing Plants) is applicable to the coal processing and conveying equipment at this facility (EU 007), including coal crushers/grinders, and coal storage, transfer and loading systems. This is not reflected in the application attachment Identification of Applicable Requirements – EU 007 (*see Subpart LLL 40 CFR 63-1356 note below). Different Subpart Y requirements apply to equipment that commenced construction on or before April 28, 2008, equipment that commenced construction after April 28 and on or before May 27, 2009, and equipment that commenced construction after May 27, 2009. In order to confirm whether these requirements are applicable to this facility, please provide the date(s) of commencement of construction for the coal processing, storage and conveying equipment at this facility and the basis for these dates.

JAN 06 2011

Southwest District

(* Note - NESHAP Subpart LLL 40 CFR 63.1356 as amended on September 9, 2010 (effective date of November 8, 2010, which will be prior to the effective date of the initial Title V operation permit for this facility) was completely revised such that the previous subject caption of “Exemption from new source performance standards” has now been changed to read “Sources with multiple emission limits or monitoring requirements”. It no longer contains direct references to the applicability or non –applicability of NSPS 40 CFR 60 Subparts F, Y or OOO. Instead of those references, it is now states that where there are other requirements under another regulation in Title 40, the affected facility must comply with the most stringent limit and is exempt from the less stringent requirements.)

Response:

The actual commencement of construction date for the Coal Storage Building is January 9, 2007; Gantt Chart line 819 for Foundations for Coal Storage Building.

The actual commencement of construction date for the Coal Conveyor is February 15, 2007; Gantt Chart line 826 for Coal Conveyor Foundation.

The actual commencement of construction date for the Coal Grinding December 3, 2007; Gantt Chart line 825 for Coal Grinding Foundation.

See attachment 5 for details.

5. Hg Monitor Installation Requirement – Specific Condition No. 21.b of Construction Permit 1190042-001-AC, as amended by Construction Permit 190042-006-AC, requires that a mercury (Hg) CEMS be installed within 240 days following the first year of operation, with the first year of operation defined as 365 calendar days after the first day the kiln produces clinker. Please provide the date of the first kiln clinker production, and the resulting deadline date for installation of the Hg CEMS. Please also provide the status of Hg CEMS procurement and installation, and an anticipated schedule for CEMS certification (required by the above permit condition to be completed 90 days after CEMS installation).

Response:

The first clinker was produced on May 17, 2009.

The deadline for the Hg-CEMS installation is January 12, 2011.

The Hg-CEMS will be delivered beginning the week of December 27, 2010.

Installation will begin the week of January 3, 2011.

The CEMS certification is scheduled to be performed within 90 days of the installation date.

See attachment 6 for details.

6. CAM Applicability for Baghouses DC-1 and DC-2 – In the CAM Applicability Analysis and CAM Plan attachment to the application, under the section labeled Units Not Subject to CAM Requirements, Baghouse ID No. DC-1 and DC-2 are shown in the list of five baghouses to which it was determined that CAM did not apply. While a basis for this determination was supplied for three of the listed baghouses, it was not provided for Baghouses DC- and DC-2. These two baghouses also appear in the list on the following page under Compliance Assurance Monitoring Plan: Fabric Filters for PM Control. Please indicate whether these two baghouse should be removed from the list of baghouses for which CAM does not apply, or provide a basis for why it does not apply.

(Note – As indicated in the section labeled Inherent Process Equipment in the above CAM attachment, in order for a piece of equipment to be considered as inherent to the operation rather than strictly a control device, three questions need to be answered in the affirmative. 1.) Is the primary purpose of the equipment other than to control emissions to comply with the applicable PM emissions limit (e.g., product recovery, worker safety)/ 2.) Would the equipment be installed if there were no applicable emissions limit in place for this emissions unit? 3.) Is the efficiency at which the equipment is designed to be operated above that which would be required to assure compliance with the applicable emissions limit (e.g., a significant margin of compliance)?)

Response:

The spreadsheet in the attachment 7 shows the CAM Plan applicability of the baghouses. CAM applies to DC-1 and DC-2.

7. Justification for Indicator Operating Ranges in CAM Plan for Baghouse PM Control Devices - The proposed Compliance Assurance Monitoring (CAM) Plan for the eighteen (18) baghouses at this facility to which the application indicated that CAM did apply included the same monitoring primary indicator of baghouse pressure drop, with the same indicator operating range of 2-8' w.g. The justification for this generic indicator range is not sufficient. The indicator range needs to be established and justified separately for each baghouse (or manufacturer/model number of baghouse where common equipment was installed). For those baghouses for which PM compliance stack testing was done (e.g., Main Baghouse (EU 003), and Baghouse ID N-93 (EU 005)), the indicator range should be based in part on the observed baghouse pressure drop range during the compliance test(s) (see 40 CFR 64.4(c)). (It can also include data from other emissions testing done on the stack.) For baghouses without stack testing data, as well as those with stack test data, other information may be considered in selecting the indicator operating ranges such as: data from tests performed on similar units at similar facilities; control device manufacturers data, guarantees and recommendations; empirical information concerning the assessment of control technology performance (e.g., empirical performance information from a control technology handbook); and theoretical considerations based on generally accepted engineering practices (i.e., engineering judgment and assessment). (Note – the above was taken from the EPA CAM Technical Guidance Document - 8/98.)

Please submit a baghouse pressure drop indicator operating range for each baghouse (or group of baghouses that are the same manufacturer and model number), along with a justification for each that demonstrates to the Department that operation of the baghouse within this range will provide reasonable assurance of ongoing compliance with the applicable PM/PM10 emission standards (0.01 gr/dscf and 0.007 gr/dscf, except

for EU 003 (different form of limit), and EU 005 Finish Mill Air Separator (0.007 gr/dscf for both PM & PM10)).

Response:

Information received from facility personnel indicating manufacturer's specification of the ideal operating pressure ranges of the baghouses in question are listed in the attachment 8.

For the EU 003 Main Baghouse, the response also needs to address the secondary indicator of change in duct opacity as measured by the continuous emissions monitoring (COMS) system. The proposed indicator range of "any sudden and sustained step-change (increase) in opacity documented by the trend of the 6-minute averages seems too vague and imprecise to be practical for the plant operators, or verifiable/reviewable for the Department. More specific levels/time periods should be established and justified based on analysis of available COMS data during testing periods and normal operation of the plant.

Response:

The COMS data is captured in the DAS from which 6-minute averages are continuously and historically reported. The Visible Emission limit is 10% opacity for a 6-minute averaging period. The CAM Plan will be implemented for the Main Baghouse when there are five (5) consecutive 6-minute averaging periods of Opacity above 5%. See attachment 8 for details.

8. D/F Compliance/Performance Testing - D/F compliance/performance testing using coke and tires as supplemental fuel was conducted beginning on September 15, 2010. In accordance with Rule 62-297.310(8), F.A.C., test reports are required to be submitted no later than 45 days after the completion of testing. Prior to issuance of an Intent to Issue and Draft Title V operation permit, the Department must receive compliance test report showing compliance with the D/F standard, using these supplemental fuels, in both the raw mill on and raw mill off operating modes. The permit application will be considered incomplete until such test report is received. Please submit a schedule for submittal of the required compliance test report.

Response:

The report was submitted on October 25, 2010. Related correspondences are provided in attachment 9.

Requested in a separate email: Revised OM plan – Provide a revised version of the O&M Plan of the facility

Response:

A revised OM plan is provided in the attachment 10.

**Requested in a separate email: RICE Inventory and Applicability Determination -
Include the facility stationary RICE inventory and applicability determination as part of
the RAI response.**

Response:

The RICE inventory and applicability determination is provided in the attachment 11.

If you have any questions concerning this matter please call me at (352) 377-5822.

Sincerely,



Zhang, Qi
Project Engineer
Koogler and Associates, Inc.

Attachments:


| | |
|---------------|---|
| Attachment 1 | RO & PE Certification Statements |
| Attachment 2 | Process Flow Diagram |
| Attachment 3 | Kiln and Cooler Construction Date |
| Attachment 4 | Quarry and Raw Material Storage Construction Date |
| Attachment 5 | Coal Mill and Coal Storage Construction Date |
| Attachment 6 | Hg Monitor Installation Requirement |
| Attachment 7 | CAM Applicability |
| Attachment 8 | Indicator Ranges |
| Attachment 9 | D/F Test Report Submission |
| Attachment 10 | O&M Plan Revision |
| Attachment 11 | RICE Inventory and Applicability Determination |

ATTACHMENT 1
RO & PE CERTIFICATION STATEMENTS

APPLICATION INFORMATION


Application Responsible Official Certification

Complete if applying for an initial, revised, or renewal Title V air operation permit or concurrent processing of an air construction permit and revised or renewal Title V air operation permit. If there are multiple responsible officials, the "application responsible official" need not be the "primary responsible official."

| |
|--|
| 1. Application Responsible Official Name: Cary O. Cohrs – President |
| 2. Application Responsible Official Qualification (Check one or more of the following options, as applicable): <input checked="" type="checkbox"/> For a corporation, the president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation, or a duly authorized representative of such person if the representative is responsible for the overall operation of one or more manufacturing, production, or operating facilities applying for or subject to a permit under Chapter 62-213, F.A.C. <input type="checkbox"/> For a partnership or sole proprietorship, a general partner or the proprietor, respectively. <input type="checkbox"/> For a municipality, county, state, federal, or other public agency, either a principal executive officer or ranking elected official. <input type="checkbox"/> The designated representative at an Acid Rain source, CAIR source, or Hg Budget source. |
| 3. Application Responsible Official Mailing Address... Organization/Firm: American Cement Company, L.L.C. Street Address: 4750 E CR 470, P. O. BOX 445 City: Sumterville State: FL Zip Code: 33585 |
| 4. Application Responsible Official Telephone Numbers... Telephone: (352) 569 - 5393 ext. Fax: (352) 569 - 5397 |
| 5. Application Responsible Official E-mail Address: ccohrs@americacementcompany.com |
| 6. Application Responsible Official Certification: <p><i>I, the undersigned, am a responsible official of the Title V source addressed in this air permit application. I hereby certify, based on information and belief formed after reasonable inquiry, that the statements made in this application are true, accurate and complete and that, to the best of my knowledge, any estimates of emissions reported in this application are based upon reasonable techniques for calculating emissions. The air pollutant emissions units and air pollution control equipment described in this application will be operated and maintained so as to comply with all applicable standards for control of air pollutant emissions found in the statutes of the State of Florida and rules of the Department of Environmental Protection and revisions thereof and all other applicable requirements identified in this application to which the Title V source is subject. I understand that a permit, if granted by the department, cannot be transferred without authorization from the department, and I will promptly notify the department upon sale or legal transfer of the facility or any permitted emissions unit. Finally, I certify that the facility and each emissions unit are in compliance with all applicable requirements to which they are subject, except as identified in compliance plan(s) submitted with this application.</i></p> <p> _____ Signature</p> <p><u>1/5/11</u> _____ Date</p> |

APPLICATION INFORMATION

Professional Engineer Certification

| |
|---|
| 1. Professional Engineer Name: Steven C. Cullen, P.E. Registration Number: 45188 |
| 2. Professional Engineer Mailing Address... Organization/Firm: Koogler and Associates, Inc. Street Address: 4014 NW 13th Street City: Gainesville State: Florida Zip Code: 32609 |
| 3. Professional Engineer Telephone Numbers... Telephone: (352) 377-5822 ext. Fax: (352) 377-7158 |
| 4. Professional Engineer E-mail Address: SCullen@kooglerassociates.com |
| 5. Professional Engineer Statement: <i>I, the undersigned, hereby certify, except as particularly noted herein*, that:</i> <i>(1) To the best of my knowledge, there is reasonable assurance that the air pollutant emissions unit(s) and the air pollution control equipment described in this application for air permit, when properly operated and maintained, will comply with all applicable standards for control of air pollutant emissions found in the Florida Statutes and rules of the Department of Environmental Protection; and</i> <i>(2) To the best of my knowledge, any emission estimates reported or relied on in this application are true, accurate, and complete and are either based upon reasonable techniques available for calculating emissions or, for emission estimates of hazardous air pollutants not regulated for an emissions unit addressed in this application, based solely upon the materials, information and calculations submitted with this application.</i> <i>(3) If the purpose of this application is to obtain a Title V air operation permit (check here <input checked="" type="checkbox"/> , if so), I further certify that each emissions unit described in this application for air permit, when properly operated and maintained, will comply with the applicable requirements identified in this application to which the unit is subject, except those emissions units for which a compliance plan and schedule is submitted with this application.</i> <i>(4) If the purpose of this application is to obtain an air construction permit (check here <input type="checkbox"/> , if so) or concurrently process and obtain an air construction permit and a Title V air operation permit revision or renewal for one or more proposed new or modified emissions units (check here <input type="checkbox"/> , if so), I further certify that the engineering features of each such emissions unit described in this application have been designed or examined by me or individuals under my direct supervision and found to be in conformity with sound engineering principles applicable to the control of emissions of the air pollutants characterized in this application.</i> <i>(5) If the purpose of this application is to obtain an initial air operation permit or operation permit revision or renewal for one or more newly constructed or modified emissions units (check here <input checked="" type="checkbox"/> , if so), I further certify that, with the exception of any changes detailed as part of this application, each such emissions unit has been constructed or modified in substantial accordance with the information given in the corresponding application for air construction permit and with all provisions contained in such permit.</i>  _____ Signature _____ Date 1/3/2011 |

* Attach any exception to certification statement.

**ATTACHMENT 2
PROCESS FLOW DIAGRAM**

Process Flow Diagrams


1. Facility Process Flow Diagram Attachment - The Facility Process Flow Diagram attached to the application shows the facility as having separate wet process and dry process equipment ahead of the rotary kiln. It also shows an Optional Preheater/Precalciner or an Optional Preheater as part of the Dry Process. Based on information obtained during a site visit, the facility is using only a dry process (i.e., there is no wet process equipment) and is equipped with a preheater/precalciner as part of the dry process. Please resubmit the Facility Process Flow Diagram correcting/clarifying the items noted above, and making any other corrections/clarifications needed to accurately represent the facility process flow as it was actually built and is being operated.

- The Facility Process Flow Diagram has been revised to show actual processes.

DRAWING LEGEND

| Elec. File No. | Drawing No. | Process | EU | Baghouse | Item |
|----------------|----------------|--------------------------------|-----|----------|------|
| 5501010001 | 110.59.55-0101 | Plot Plan | | | |
| 5500022001 | 110.59.55-0002 | Quarry / RMS | 001 | | |
| 5500032001 | 110.59.55-0003 | Raw Grinding System | 002 | | |
| 5500052001 | 110.59.55-0005 | Raw Meal Transport | 002 | F-10 | A |
| | | | 002 | G-07 | B |
| 5500062001 | 110.59.55-0006 | Raw Meal Blending | 002 | G-07 | B |
| | | | 002 | G-10 | C |
| 5500071001 | 110.59.55-0007 | Kiln Feed | 002 | H-08 | E |
| 5500042001 | 110.59.55-0004 | Main Baghouse & Dust Transport | 002 | E-38 | D |
| | | | 003 | E-19 | F |
| 5500082001 | 110.59.55-0008 | Preheater & Calciner | 003 | | |
| 5500092001 | 110.59.55-0009 | Kiln & Tertiary Air Duct | 003 | | |
| 5500102001 | 110.59.55-0010 | Clinker Cooler | 004 | L-03 | G |
| 5500112001 | 110.59.55-0011 | Clinker & Additive Storage | 004 | L-03 | G |
| | | | 004 | L-06 | H |
| | | | 004 | M-08 | I |
| 5500122001 | 110.59.55-0012 | Clinker & Additive Transport | 004 | DC-1 | J |
| | | | 004 | DC-2 | K |
| 5500142001 | 110.59.55-0014 | Cement Grinding System | 005 | N-94 | M |
| | | | 006 | N-91 | N |
| 5500152001 | 110.59.55-0015 | Cement Grinding Sepol Vent | 005 | N-93 | L |
| 5500182001 | 110.59.55-0018 | Cement Storage & Truck Loading | 006 | Q-25 | O |
| | | | 006 | Q-26 | P |
| | | | 006 | Q-14 | Q |
| | | | 006 | Q-17 | R |
| 550019F001 | 110.59.55-0019 | Packing Plant | 006 | R-12A | S |
| 5500200001 | 110.59.55-0020 | Coal Grinding Vertical Mill | 007 | | |
| 5500210001 | 110.59.55-0021 | Coal Grinding System | 007 | S-22 | T |
| | | | | S-26 | U |

File No. 5501010001



LEGEND

- | | | |
|----------------------------|--|--|
| 1. RAW MATERIAL STORAGE | 14. COOLER VERT EXHAUST FAN | 27. COMPRESSOR ROOM No.1 (FOR PLANT AIR COMPRESSORS) |
| 2. ROLLER MILL | 15. CLINKER CONVEYOR TO SILOS | 28. COMPRESSOR ROOM No.2 (FOR PLANT AIR AND SCREW PUMP COMPRESSORS) |
| 3. ROLLER MILL EXHAUST FAN | 16. CLINKER STORAGE SILOS | 29. COMPRESSOR ROOM No.3 (FOR HOMOGENIZING SLD and AEROPOL BLOWERS, BELOW SLD) |
| 4. KILN / MILL BAGHOUSE | 17. GYPSUM STORAGE BUILDING | 30. ELECTRICAL ROOM #1 RAW MATERIAL STORAGE BUILDING |
| 5. BAGHOUSE EXHAUST FAN | 18. FRESH MILL | 31. ELECTRICAL ROOM #2 ROLLER MILL |
| 6. MAIN EXHAUST STACK | 19. FRESH MILL EXHAUST STACK | 32. ELECTRICAL ROOM #3 PREHEATER |
| 7. HOMOGENIZING SLD | 20. SEPOL EXHAUST STACK | 33. ELECTRICAL ROOM #4 STAND-BY GENERATOR |
| 8. PREHEATER | 21. CEMENT STORAGE SILOS & BLOWER ROOM | 34. ELECTRICAL ROOM #5 CLINKER COOLER |
| 9. GAS CONDITIONING TOWER | 22. PACKING PLANT | 35. ELECTRICAL ROOM #6 FRESH MILL |
| 10. KILN ID FAN | 23. COAL STORAGE BUILDING | 36. ELECTRICAL ROOM #7 CEMENT SILOS / PACKING PLANT |
| 11. ROTARY KILN | 24. RAW COAL SILOS | 37. ELECTRICAL ROOM #8 MAINTENANCE BUILDING |
| 12. BURDER BUILDING | 25. COAL MILL | 38. COMPRESSOR ROOM No.4 (FOR PLANT AIR COMPRESSORS) |
| 13. COOLER VERT DE-DUSTING | 26. CROSS-BELT ANALYER | 39. OFFICE |
| | | 40. SHOR TANK AND PUMP SKID |

NOVEMBER 9, 2007

CERTIFIED
THIS DRAWING IS
CORRECT FOR
EQUIPMENT INSTALLATION

AMERICAN CEMENT COMPANY
SANTERVILLE, FLORIDA




PLANT LAYOUT
PLAN VIEW
NEW 3000 STPD KILN LINE

E 110.59.55-0101

| NO. | DATE | BY | CHKD | REVISION |
|-----|----------|----|------|-----------------------------------|
| 1 | 11-09-07 | | | ISSUED FOR PERMITTING |
| 2 | 11-09-07 | | | ISSUED FOR CONSTRUCTION |
| 3 | 11-09-07 | | | ISSUED FOR EQUIPMENT INSTALLATION |

File No. 550022001



PLANT ELEVATION: 76 FT.

| LEGEND | | |
|--------|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG; 108°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

| LEGEND | |
|----------------|-----------------------|
| 1 | INSULATION & CLADDING |
| 2 | REFRACTORY/BRICKS |
| 3 | A.R. STEEL LINERS |
| 4 | DENSIT LINING |
| 5 | CERAMIC TILES |
| 6 | CASTABLES |
| SUPPLY INSTALL | |
| A | C C |
| B | P P |
| C | P C |
| C = CONTRACTOR | |
| P = POLYSIUS | |

NOVEMBER 16, 2007
CERTIFIED THIS DRAWING IS CORRECT FOR EQUIPMENT INSTALLATION

| Rev | Description | Rev | Date | Rev | Date | Rev | Date |
|-----|-------------|-----|----------|-----|----------|-----|----------|
| 2 | CERTIFIED | PPC | 11/14/07 | LEL | 11/14/07 | UR | 11/14/07 |
| 1 | CERTIFIED | PPC | 7/13/07 | LEL | 7/13/07 | UR | 7/13/07 |
| 0 | CERTIFIED | PPC | 5/2/07 | LEL | 5/2/07 | UR | 5/2/07 |

AMERICAN CEMENT COMPANY
SUMTERVILLE, FLORIDA

POLYSIUS

Project No. AMERATA Contract No. 7401-7758

MECHANICAL PROCESS FLOW SHEET
RAW MATERIAL CRUSHING & STORAGE
3000 STPD CLINKER

D 110.59.55-0002


Scale: NONE Sheet: 001 of 001

B 7 6 5 4 3 2 1

LEGEND

| | |
|-----|-----------------------|
| [1] | INSULATION & CLADDING |
| [2] | REFRACTORY/BRICKS |
| [3] | A.R. STEEL LINERS |
| [4] | DENSIT LINING |
| [5] | CERAMIC TILES |
| [6] | CASTABLES |
| [A] | SUPPLY INSTALL |
| [B] | C |
| [C] | P |
| [D] | P |
| [E] | C |
| [F] | P |
| [G] | P |
| [H] | C |
| [I] | P |
| [J] | C |

C = CONTRACTOR
P = POLYSIUS



File No. 5500032001

PLANT ELEVATION: 76 FT.

LEGEND

| | | |
|----|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | 'F | TEMPERATURE |
| TP | 'F | DEW POINT |
| UT | 'F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 108°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

NOVEMBER 14, 2007
CERTIFIED THIS DRAWING IS CORRECT FOR EQUIPMENT INSTALLATION

| Rev | Description | Rev | Date | Rev | Date | Rev | Date | Rev | Date |
|-----|-------------|-----|----------|-----|----------|-----|----------|-----|------|
| 2 | CERTIFIED | PPC | 11/14/07 | LEL | 11/14/07 | UR | 11/14/07 | | |
| 1 | CERTIFIED | PPC | 7/13/07 | LEL | 7/13/07 | UR | 7/13/07 | | |
| 0 | CERTIFIED | PPC | 5/3/07 | LEL | 5/7/07 | UR | 5/7/07 | | |

AMERICAN CEMENT COMPANY
SUMTHERVILLE, FLORIDA

POLYSIUS

MECHANICAL PROCESS FLOW SHEET
RAW GRINDING SYSTEM
3000 STPD CLINKER

Project No: 110.59.55-0003
Revision: NONE
Sheet: 001 of 001

EU-003 (F) Main Baghouse, E-19

EU-002 (D) E-38

File No. 5500042001

PLANT ELEVATION: 76 FT.

LEGEND

| | | |
|----|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SO | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: WINTER 32°F MIN; 59°F AVG. SUMMER 102°F MAX; 96-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

LEGEND

- INSULATION & CLADDING
 - ▣ REFRACTORY/BRICKS
 - ▤ A.R. STEEL LINERS
 - ▥ DENSIT LINING
 - ▧ CERAMIC TILES
 - ▨ CASTABLES
- SUPPLY INSTALL**
- Ⓐ C C
 - Ⓑ P P
 - Ⓒ P C
- C = CONTRACTOR
P = POLYSIUS

NOVEMBER 16, 2007

**CERTIFIED
THIS DRAWING IS
CORRECT FOR
EQUIPMENT INSTALLATION**


| Rev | Description | Rev | Date | Rev | Date | Rev | Date | Rev | Date |
|-----|-------------|-----|----------|-----|----------|-----|----------|-----|------|
| 2 | CERTIFIED | PPC | 11/14/07 | LEL | 11/14/07 | UR | 11/14/07 | | |
| 1 | CERTIFIED | PPC | 7/13/07 | LEL | 7/13/07 | UR | 7/13/07 | | |
| 0 | CERTIFIED | PPC | 5/3/07 | LEL | 5/7/07 | UR | 5/7/07 | | |

AMERICAN CEMENT COMPANY
SUMTERVILLE, FLORIDA

POLYSIUS

MECHANICAL PROCESS FLOW SHEET
MAIN BAGHOUSE & DUST TRANSPORT
3000 STPD CLINKER

Project No. 7401-7756
Rev No. 2
Date 1/11/07
Scale NONE
Sheet 001 of 001



OPERATING DESIGN

| | | |
|---|------|------|
| G | 23 | 28 |
| H | <0.5 | <0.5 |

MINIMUM NORMAL MAXIMUM

| | | | |
|---|---|-----|----|
| G | 3 | 6-9 | 25 |
|---|---|-----|----|

FAN DESIGN


| | |
|----|---------|
| P | -15 |
| T | 354 |
| VB | 494,525 |

D 12.8
HEIGHT 350

Revisions

| Rev | Date | Rev | Date | Rev | Date | Rev | Date |
|-----|----------|-----|---------|-----|--------|-----|------|
| 2 | 11/14/07 | 1 | 7/13/07 | 0 | 5/3/07 | | |

File No. 5500052001



PLANT ELEVATION: 76 FT.

| LEGEND | | |
|--------|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: WINTER 32°F MIN; 50°F AVG. SUMMER 100°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ² /S | GAS FLOW |


| LEGEND | |
|----------------|-----------------------|
| 1 | INSULATION & CLADDING |
| 2 | REFRACTORY/BRICKS |
| 3 | A.R. STEEL LINERS |
| 4 | DENSIT LINING |
| 5 | CERAMIC TILES |
| 6 | CASTABLES |
| SUPPLY INSTALL | |
| A | C C |
| B | P P |
| C | P C |
| C = CONTRACTOR | |
| P = POLYSIUS | |

NOVEMBER 16, 2007
CERTIFIED
 THIS DRAWING IS
 CORRECT FOR
 EQUIPMENT INSTALLATION

| Rev | Description | Rev | Date | Rev | Date | Rev | Date | Rev | Date |
|-----|-------------|-----|----------|-----|----------|-----|----------|-----|------|
| 2 | CERTIFIED | PPC | 11/14/07 | LEL | 11/14/07 | UR | 11/14/07 | | |
| 1 | CERTIFIED | PPC | 7/13/07 | LEL | 7/13/07 | UR | 7/13/07 | | |
| 0 | CERTIFIED | PPC | 5/3/07 | LEL | 5/7/07 | UR | 5/7/07 | | |

| | | | | |
|----------------------------|--|---|--|---|
| | | AMERICAN CEMENT COMPANY SUMTERVILLE, FLORIDA | | General Information to the Engineer Please Reference to the Notes, Specs & Schedule, Drawings, and the Contract Documents. |
| | | Project Name: AMERNA Drawing No: 7401-7750 | | Project Location: SUMTERVILLE, FLORIDA Project No: 110.59.55-0005 |
| Project No: 110.59.55-0005 | | Drawing Title: MECHANICAL PROCESS FLOW SHEET RAW MEAL TRANSPORT 3000 STPD CLINKER | | Scale: NONE Sheet No: 001 of 001 |

File No. 5500062001



Dept. Of Environmental Protection
 JAN 06 2011
 Southwest District


| LEGEND | | |
|--------|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 108°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

| LEGEND | |
|--------------------------------|-----------------------|
| 1 | INSULATION & CLADDING |
| 2 | REFRACTORY/BRICKS |
| 3 | A.R. STEEL LINERS |
| 4 | DENSIT LINING |
| 5 | CERAMIC TILES |
| 6 | CASTABLES |
| SUPPLY INSTALL | |
| A | C C |
| B | P P |
| C | P C |
| C = CONTRACTOR P = POLYSIUS | |

NOVEMBER 16, 2007
**CERTIFIED
 THIS DRAWING IS
 CORRECT FOR
 EQUIPMENT INSTALLATION**

| Rev | Description | Rev | Date | Rev | Date | Rev | Date |
|-----|-------------|-----|----------|-----|----------|-----|----------|
| 2 | CORRECTED | PRC | 11/14/07 | LDL | 11/14/07 | UR | 11/14/07 |
| 1 | CORRECTED | PRC | 7/13/07 | LDL | 7/13/07 | UR | 7/13/07 |
| 0 | CORRECTED | PRC | 5/3/07 | LDL | 5/2/07 | UR | 5/7/07 |

| | | |
|--|--------------------|--|
| AMERICAN CEMENT COMPANY SUMTERVILLE, FLORIDA | | <small> General Reference to all Division Drawings shall be to the 1000 Series - unless otherwise noted. For 1000 Series - see Division 10 - Mechanical, Section 10-0100 - Mechanical Drawings. For 1000 Series - see Division 10 - Mechanical, Section 10-0100 - Mechanical Drawings. For 1000 Series - see Division 10 - Mechanical, Section 10-0100 - Mechanical Drawings. </small> |
| | | <small> Project No. 7401-7726 Date 1/11/07 </small> |
| MECHANICAL PROCESS FLOW SHEET RAW MEAL BLENDING 3000 STPD CLINKER | | |
| Drawing No. D 110.59.55-0006 | Sheet No. 2 | Scale 1/11/07 |



PLANT ELEVATION: 76 FT.

LEGEND

| | | |
|----|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 108°F MAX; 96-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

LEGEND

- 1 INSULATION & CLADDING
 - 2 REFRACTORY/BRICKS
 - 3 A.R. STEEL LINERS
 - 4 DENSIT LINING
 - 5 CERAMIC TILES
 - 6 CASTABLES
- SUPPLY INSTALL**
- A C C
 - B P P
 - C P C
- C = CONTRACTOR
P = POLYSIUS

NOVEMBER 16, 2007

**CERTIFIED
THIS DRAWING IS
CORRECT FOR
EQUIPMENT INSTALLATION**

| Rev | Description | Date | By | Check | Date | By | Check |
|-----|-------------|----------|-----|----------|------|----------|-------|
| 1 | CERTIFIED | 11/14/07 | LEL | 11/14/07 | UR | 11/14/07 | |
| 0 | CERTIFIED | 5/3/07 | LEL | 5/7/07 | UR | 5/7/07 | |

AMERICAN CEMENT COMPANY
SUMTERVILLE, FLORIDA

POLYSIUS

AMERANA 7401-7750

MECHANICAL PROCESS FLOW SHEET
KILN FEED
3000 STPD CLINKER


D 110.59.55-0007

Sheet 001 of 001

PLANT ELEVATION: 76 FT.

| LEGEND | | |
|--------|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | X | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 108°F MAX; 95-102°F AVG. RELATIVE HUMIDITY: 100% |
| | | WINTER SUMMER |
| V | X | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

| LEGEND | | |
|----------------|-----------------------|---|
| [1] | INSULATION & CLADDING | |
| [2] | REFRACTORY/BRICKS | |
| [3] | A.R. STEEL LINERS | |
| [4] | DENSIT LING | |
| [5] | CERAMIC TILES | |
| [6] | CASTABLES | |
| SUPPLY INSTALL | | |
| [A] | C | C |
| [B] | P | P |
| [C] | P | C |
| C = CONTRACTOR | | |
| P = POLYSIUS | | |



NOVEMBER 16, 2007
CERTIFIED
 THIS DRAWING IS
 CORRECT FOR
 EQUIPMENT INSTALLATION

| Rev | Description | Rev | Date | Chk | Date | Appr | Date |
|-----|-------------|-----|----------|-----|----------|------|----------|
| 2 | CERTIFIED | PPC | 11/14/07 | LEL | 11/14/07 | UR | 11/14/07 |
| 1 | CERTIFIED | PPC | 7/13/07 | LEL | 7/13/07 | UR | 7/13/07 |
| 0 | CERTIFIED | PPC | 5/3/07 | LEL | 5/7/07 | UR | 5/7/07 |


| | | | |
|--|----------------|--|---------|
| AMERICAN CEMENT COMPANY SUMTERVILLE, FLORIDA | | <small>Standard Reference to 500 Division Single Outlets to 500 5000, Series - Size and Flow to 500 5000 Size and Flow to 500 5000 Size and Flow to 500 5000</small> | |
| POLYSIUS | | Project Name: AMERATA Contract No: 7401-7750 Mechanical Process Flow Sheet KILN AND TERTIARY AIR DUCT 3000 STPD CLINKER | |
| Rev | Rev No | Rev | Rev No |
| D | 110.59.55-0009 | Rev | 2 |
| Chk | LEL | Date | 1/11/07 |
| Appr | UR | Date | 1/11/07 |
| Scale: NONE | | Sheet: 001 of 001 | |

PLANT ELEVATION: 76 FT.

| LEGEND | | |
|--------|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | 'F | TEMPERATURE |
| TP | 'F | DEW POINT |
| UT | 'F | AMBIENT TEMPERATURE: 32°F MIN; 50°F AVG. 100°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| | | WINTER SUMMER |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

LEGEND

- [1] INSULATION & CLADDING
 - [2] REFRACTORY/BRICKS
 - [3] A.R. STEEL LINERS
 - [4] DENSIT LINING
 - [5] CERAMIC TILES
 - [6] CASTABLES
- SUPPLY INSTALL
- [A] C C
 - [B] P P
 - [C] P C
- C = CONTRACTOR
P = POLYSIUS



NOVEMBER 16, 2007

CERTIFIED
THIS DRAWING IS
CORRECT FOR
EQUIPMENT INSTALLATION

| Rev | Description | Date | By | Appr | Check | Scale | Sheet | Total |
|-----|-------------|----------|-----|----------|-------|----------|-------|-------|
| 3 | CERTIFIED | 11/14/07 | PPC | 11/14/07 | UR | 11/14/07 | | |
| 1 | CERTIFIED | 7/13/07 | PPC | 7/13/07 | UR | 7/13/07 | | |
| 0 | CERTIFIED | 5/3/07 | PPC | 5/7/07 | UR | 5/7/07 | | |

AMERICAN CEMENT COMPANY
SUMTERTVILLE, FLORIDA

POLYSIUS


MECHANICAL PROCESS FLOW SHEET
CLINKER COOLER
3000 STPD CLINKER

Project No. 110.59.55-0010

Sheet No. 2

Scale: NONE

File No. 5500112001



OPERATING DESIGN

| | | |
|---|---------------|-----|
| G | 125 | 188 |
| T | 180 + AMBIENT | |

PLANT ELEVATION: 76 FT.

LEGEND

| | | |
|----|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SO | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN; 99°F AVG. 103°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

LEGEND

| | |
|----------------|-----------------------|
| 1 | INSULATION & CLADDING |
| 2 | REFRACTORY/BRICKS |
| 3 | A.R. STEEL LINERS |
| 4 | DENSIT LINING |
| 5 | CERAMIC TILES |
| 6 | CASTABLES |
| SUPPLY INSTALL | |
| A | C C |
| B | P P |
| C | P C |
| C = CONTRACTOR | |
| P = POLYSIUS | |

NOVEMBER 16, 2007

CERTIFIED
THIS DRAWING IS
CORRECT FOR
EQUIPMENT INSTALLATION

| Rev | Description | Rev | Date | Clad | Clad | Clad | Clad | Clad | Clad |
|-----|-------------|-----|----------|------|----------|------|----------|------|------|
| 2 | CERTIFIED | PPC | 11/14/07 | LEL | 11/14/07 | UR | 11/14/07 | | |
| 1 | CERTIFIED | PPC | 7/13/07 | LEL | 7/13/07 | UR | 7/13/07 | | |
| 0 | CERTIFIED | PPC | 5/3/07 | LEL | 5/7/07 | UR | 5/7/07 | | |

AMERICAN CEMENT COMPANY
SUMTERTVILLE, FLORIDA

POLYSIUS


MECHANICAL PROCESS FLOW SHEET
CLINKER AND ADDITIVE STORAGE
3000 STPD CLINKER

Project No. AMERAFRA Document No. 7401-7756

Rev No. **D** 110.59.55-0011

Scale NONE Sheet 001 of 001

File No. 5500122001



PLANT ELEVATION: 76 FT.

EU-004 (J) DC-1

EU-004 (K) DC-2

| LEGEND | | |
|--------|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 108°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

| LEGEND | | |
|----------------|-----------------------|---|
| (1) | INSULATION & CLADDING | |
| (2) | REFRACTORY/BRICKS | |
| (3) | A.R. STEEL LINERS | |
| (4) | DENSIT LINING | |
| (5) | CERAMIC TILES | |
| (6) | CASTABLES | |
| SUPPLY INSTALL | | |
| (A) | C | C |
| (B) | P | P |
| (C) | P | C |
| C = CONTRACTOR | | |
| P = POLYSIUS | | |


NOVEMBER 16, 2007

CERTIFIED
THIS DRAWING IS
CORRECT FOR
EQUIPMENT INSTALLATION

| Rev | Description | Rev | Date | Rev | Date | Rev | Date |
|-----|-------------|-----|----------|-----|----------|-----|----------|
| 2 | CERTIFIED | PPC | 11/14/07 | LED | 11/14/07 | UR | 11/14/07 |
| 1 | CERTIFIED | PPC | 7/13/07 | LED | 7/13/07 | UR | 7/13/07 |
| 0 | CERTIFIED | PPC | 5/3/07 | LED | 5/7/07 | UR | 5/7/07 |

| | | | |
|---|--|--|---|
| AMERICAN CEMENT COMPANY SUMTERVILLE, FLORIDA | | | <small>Standard Minimum to 500 STPD Design Capacity to 300 STPD. Capacity - may vary to other values. See spec. Material furnished to 500 STPD Design Capacity to 300 STPD. Design Capacity to 300 STPD. Design Capacity to 300 STPD.</small> |
| Project Name: AMERANA Project No: 7401-7750 | | | |
| MECHANICAL PROCESS FLOW SHEET CLINKER AND ADDITIVE TRANSPORT 3000 STPD CLINKER | | | Scale: 1" = 10'-0" Date: 1/11/07 Sheet: 2 of 2 |

File No. 5500142001



PLANT ELEVATION: 76 FT.

| LEGEND | | |
|--------|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAY PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/TT ³ | BULK DENSITY |
| T | 'F | TEMPERATURE |
| TP | 'F | DEW POINT |
| UT | 'F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 108°F MAX; 95-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |


| LEGEND | |
|----------------|-----------------------|
| 1 | INSULATION & CLADDING |
| 2 | REFRACTORY/BRICKS |
| 3 | A.R. STEEL LINERS |
| 4 | DENSIT LINING |
| 5 | CERAMIC TILES |
| 6 | CASTABLES |
| SUPPLY INSTALL | |
| A | C C |
| B | P P |
| C | P C |
| C = CONTRACTOR | |
| P = POLYSIUS | |

NOVEMBER 16, 2007
CERTIFIED
 THIS DRAWING IS
 CORRECT FOR
 EQUIPMENT INSTALLATION

| Rev | Description | Date | By | Check | Appr | Date |
|-----|-------------|----------|-----|----------|------|----------|
| 2 | CERTIFIED | 11/14/07 | LDL | 11/14/07 | UR | 11/14/07 |
| 1 | CERTIFIED | 7/13/07 | LDL | 7/13/07 | UR | 7/13/07 |
| 0 | CERTIFIED | 5/7/07 | LDL | 5/7/07 | UR | 5/7/07 |

| | | |
|--|--------------------------|---|
| AMERICAN CEMENT COMPANY SUMTERVILLE, FLORIDA | | <small>General Information to Bid 2/2006 Plans Checked by Mr. S.M. Brown Plans Approved by Mr. S.M. Brown Plans Issued by Mr. S.M. Brown</small> |
| | | <small>Project Information to Bid 2/2006 Project Name: 3000 STPD CLINKER Project No.: 110.59.55-0014 Bid No.: 001 of 001</small> |
| Project Name: AMERLATA Project No.: 7401-7750 | | MECHANICAL PROCESS FLOW SHEET CEMENT GRINDING SYSTEM 3000 STPD CLINKER |
| Date: 11/11/07 By: UR | Date: 9/22/06 By: LEL | Date: 1/11/07 By: UR |

File No. 5500152001



PLANT ELEVATION: 76 FT.

LEGEND

| | | |
|----|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | 'F | TEMPERATURE |
| TP | 'F | DEW POINT |
| UT | 'F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 100°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

LEGEND

- [] INSULATION & CLADDING
 - [] REFRACTORY/BRICKS
 - [] A.R. STEEL LINERS
 - [] DENSIT LINING
 - [] CERAMIC TILES
 - [] CASTABLES
- SUPPLY INSTALL**
- | | | |
|-----|---|---|
| [A] | C | C |
| [P] | P | P |
| [C] | P | C |
- C = CONTRACTOR
P = POLYSIUS

NOVEMBER 16, 2007

**CERTIFIED
THIS DRAWING IS
CORRECT FOR
EQUIPMENT INSTALLATION**

| Rev | Description | Rev | Date | Rev | Date | Rev | Date | Rev | Date |
|-----|-------------|-----|----------|-----|----------|-----|----------|-----|------|
| 2 | CERTIFIED | PRC | 11/14/07 | LEL | 11/14/07 | UR | 11/14/07 | | |
| 1 | CERTIFIED | PRC | 7/13/07 | LEL | 7/13/07 | UR | 7/13/07 | | |
| 0 | CERTIFIED | PRC | 5/2/07 | LEL | 5/7/07 | UR | 5/7/07 | | |

AMERICAN CEMENT COMPANY
SUMTERVILLE, FLORIDA

POLYSIUS

MECHANICAL PROCESS FLOW SHEET
CEMENT GRINDING SEPO VENT
3000 STPD CLINKER

Project No. 110.59.55-0015

Sheet No. 2

Date 1/11/07

8 7 6 5 4 3 2 1

File No. 5500182001

EU-006 (P) Q-26

EU-006 (O) Q-25

EU-006 (Q) Q-14

EU-006 (R) Q-17

PLANT ELEVATION: 76 FT.

SK1.EV01
Capacity: 900 lbs.

LEGEND

| | | |
|----|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | X | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | X | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 100°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

SEPTEMBER 14, 2007

**CERTIFIED
THIS DRAWING IS
CORRECT FOR
EQUIPMENT INSTALLATION**

| Rev | Description | Rev | Date | Rev | Date | Rev | Date | Rev | Date |
|-----|-------------|-----|---------|-----|---------|-----|---------|-----|------|
| 2 | CERTIFIED | DR | 9/14/07 | LEL | 9/14/07 | UR | 9/14/07 | | |
| 1 | CERTIFIED | PPC | 7/13/07 | LEL | 7/13/07 | UR | 7/13/07 | | |
| 0 | CERTIFIED | PPC | 5/3/07 | LEL | 5/7/07 | UR | 5/7/07 | | |



AMERICAN CEMENT COMPANY
SUMTERTVILLE, FLORIDA

POLYSIUS

MECHANICAL PROCESS FLOW SHEET
CEMENT STORAGE & TRUCK LOADING
3000 STPD CLINKER

Drawing No. **110.59.55-0018**

Sheet **001** of **001**



File No. 550019F001

EU-006 (S) R-12A


FROM 6C1.TC05
DWG-001B

PLANT ELEVATION: 76 FT.

LEGEND


| | | |
|----|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| Q | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200 MESH |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SO | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN; 59°F AVG. 105°F MAX; 98-102°F AVG. RELATIVE HUMIDITY: 100% |
| W | % | WINTER |
| | | SUMMER |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

FROM CEMENT STORAGE SILOS
DWG-001B



5 ST

1 ST



NOVEMBER 16, 2007

**FOR APPROVAL
DRAWING IN PROGRESS
ISSUED FOR CLIENT
APPROVAL**

| | | | | | | | |
|-----|----------------------------|-----|----------|-----|----------|-----|----------|
| E | FOR APPROVAL | ED | 11/14/07 | LED | 11/14/07 | UR | 11/14/07 |
| E | FOR APPROVAL | ED | 9/14/07 | LED | 9/14/07 | UR | 9/14/07 |
| D | ADDED CHUTES/DUCTS NUMBERS | PFC | 3/2/07 | LED | 3/2/07 | UR | 3/2/07 |
| C | FOR APPROVAL | PFC | 1/11/07 | LED | 1/11/07 | UR | 1/11/07 |
| B | ADDED SAP NUMBERS | PFC | 11/10/06 | --- | --- | --- | --- |
| Rev | Description | Rev | Date | Chg | By | App | Date |
| 1 | | | | | | | |

AMERICAN CEMENT COMPANY
SUMTERVILLE, FLORIDA


POLYSIUS

Project Name: AMERAFIA
Drawing No: 7401-7750

MECHANICAL PROCESS FLOW SHEET
3000 STPD CLINKER

Rev: D
Date: 1/11/07
Scale: NONE
Sheet: 001 of 001

File No. 550020001



PLANT ELEVATION: 76 FT.

LEGEND

| | | |
|----|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200m |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | °F | TEMPERATURE |
| TP | °F | DEW POINT |
| UT | °F | AMBIENT TEMPERATURE: 32°F MIN, 50°F AVG. 100°F MAX; 95-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

NOTE: COAL MILL, DUCTS, COAL DUST BIN AND BAGFILTERS ARE DESIGNED FOR 50 PSIG.

LEGEND

| | |
|-----|-----------------------|
| [] | INSULATION & CLADDING |
| [] | REFRACTORY/BRICKS |
| [] | A.R. STEEL LINERS |
| [] | DENSIT LINING |
| [] | CERAMIC TILES |
| [] | CASTABLES |
| [] | SUPPLY INSTALL |
| [A] | C |
| [B] | P |
| [C] | P |
| C | CONTRACTOR |
| P | POLYSIUS |

MAY 11, 2007
CERTIFIED THIS DRAWING IS CORRECT FOR EQUIPMENT INSTALLATION

| WINTER | | SUMMER | |
|--------|--------|--------|--------|
| T | 161 | T | 167 |
| VB | 17,657 | VB | 19,485 |
| VN | 14,974 | VN | 16,368 |
| D | 2'-6" | D | 2'-6" |

| WINTER | | SUMMER | |
|--------|-------|--------|-------|
| G | 21.75 | G | 21.75 |
| H | 8 | H | 8 |

| WINTER | | SUMMER | |
|----------------|--------|----------------|--------|
| O ₂ | 3.5 | O ₂ | 3.5 |
| Q | 5.19 | Q | 3.94 |
| T | 680 | T | 680 |
| VB | 14,503 | VB | 11,018 |
| VN | 6,701 | VN | 5,091 |

| WINTER | | SUMMER | |
|--------|--------|--------|--------|
| T | 332 | T | 298 |
| VB | 32,577 | VB | 30,862 |
| VN | 21,675 | VN | 21,439 |
| D | 3'-3" | D | 3'-3" |

AMERICAN CEMENT COMPANY
 SUMTERVILLE, FLORIDA

POLYSIUS
 A Division of American Cement Company

Customer Name: AMERAFRA Contract No: 7401-7758


MECHANICAL PROCESS FLOW SHEET
COAL GRINDING VERTICAL MILL
3000 STPD CLINKER

Rev: 0 Date: 1/11/07 Rev: 1 Date: 1/11/07

Project No: 110.59.55-0020

Scale: NONE Sheet: 001 of 001

File No. 550021001



| | | |
|----|--------|--------|
| T | 161 | 167 |
| VB | 13,943 | 12,114 |
| VN | 11,824 | 11,176 |

| | | |
|----------------|--------|--------|
| | WINTER | SUMMER |
| O ₂ | 9.1 | 9.7 |
| P | -36 | -36 |
| T | 161 | 167 |
| TP | 122 | 128 |
| VB | 34,700 | 34,700 |
| VN | 26,798 | 26,544 |

PLANT ELEVATION: 76 FT.

| LEGEND | | |
|--------|--------------------|--|
| B | LB/H | COMBUSTIBLE FLOW |
| D | FT | DIAMETER |
| G | ST/H | MATERIAL FLOW |
| H | % | MATERIAL MOISTURE |
| HU | BTU/LB | NET CALOR VALUE |
| K | IN | GRAIN SIZE |
| KB | CM ² /G | BLAINE |
| KR | % | RESIDUAL 200m |
| M | HP | MOTOR POWER |
| N | RPM | SPEED |
| P | INWG | STAT PRESSURE |
| Q | MBTU/H | HEAT QUANTITY |
| QS | BTU/LB | HEAT QUANTITY |
| S | G/FT ³ | DUST CONTENT |
| SG | LB/FT ³ | BULK DENSITY |
| T | 'F | TEMPERATURE |
| TP | 'F | DEW POINT |
| UT | 'F | AMBIENT TEMPERATURE: WINTER 32°F MIN; 59°F AVG. SUMMER 108°F MAX; 96-102°F AVG. RELATIVE HUMIDITY: 100% |
| V | % | VOLATILE MATTER |
| VB | ACFM | GAS FLOW |
| VN | SCFM | GAS FLOW |
| VS | SCF/LB | GAS FLOW |
| VV | FT ³ /S | GAS FLOW |

| LEGEND | | |
|----------------|-----------------------|---|
| [I] | INSULATION & CLADDING | |
| [R] | REFRACTORY/BRICKS | |
| [A.R.] | A.R. STEEL LINERS | |
| [D] | DENSIT LINING | |
| [C] | CERAMIC TILES | |
| [B] | CASTABLES | |
| SUPPLY INSTALL | | |
| [A] | C | C |
| [P] | P | P |
| [C] | P | C |
| C = CONTRACTOR | | |
| P = POLYSIUS | | |

NOTE: COAL MILL, DUCTS, COAL DUST BIN AND BAGFILTERS ARE DESIGNED FOR 50 PSIG.

MAY 11, 2007
CERTIFIED
 THIS DRAWING IS
 CORRECT FOR
 EQUIPMENT INSTALLATION

| REV | DESCRIPTION | DATE | BY | CHKD | APPD | DATE | BY | CHKD | APPD |
|-----|-------------|--------|----|------|------|--------|----|------|------|
| 0 | CERTIFIED | 5/3/07 | | | | 5/7/07 | | | |

AMERICAN CEMENT COMPANY
SUMTHERVILLE, FLORIDA

Project: AMERAFRA
 Mechanical Process Flow Sheet
 COAL GRINDING SYSTEM
 3000 STPD CLINKER

Revision: 0
 Date: 5/3/07
 By: [Blank]
 Check: [Blank]
 Appr: [Blank]

Sheet No: 110.59.55-0021
 Total Sheets: 001 of 001

Approved: [Blank]
 Date: [Blank]
 Title: [Blank]

RICE Inventory and Applicability Determination

Please include this facility stationary RICE inventory and applicability determination as part of the RAI response.

- The RICE inventory and applicability determination is attached here.

STATIONARY RECIPROCATING INTERNAL COMBUSTION ENGINE (RICE) INVENTORY and NESHAP 40 CFR 63 SUBPART ZZZZ APPLICABLE REQUIREMENTS
(Facility Name and ARMS ID No.) (Date of inventory)

| Stationary Reciprocating Internal Combustion Engine (RICE) Information | | | | | | | | | | 40 CFR 63 Subpart ZZZZ Applicable Requirements <i>(list all applicable subsections)</i> | | | | | |
|--|----------------------|---------------------|--------------|--------------------------------|-------------|--------|----------|------------------------------|---------------------------------------|---|--|---|---|------------------------------|-------------------------------------|
| Engine Description/Location | Engine Serial Number | Engine Manufacturer | Model Number | Date of Construction/Reconstr. | Power (bhp) | Fuel | CI or SI | SI Type (4SLB, 2SLB or 4SRB) | Indicate if Emergency or Limited Use* | Emission Standards (from 63.6603, & Tables 2b & 2d) | Operation/Maintenance Standards (from 63.6603, & Table 2d) | Performance Testing (from 63.6612, 63.6615 & Table 3) | Monitoring (from 63.6625) & Contin. Compl. (from 63.6640 & Table 6) | Recordkeeping (from 63.6655) | Reporting (from 63.6650, & Table 7) |
| Emergency Generator Powerplant Location: Adjacent ER#4 | SYC01962 | Caterpillar | C32 | 2007 | 1505 | Diesel | CI | N/A | Emergency | N/A | N/A | N/A | N/A | N/A | N/A |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |

NOTES:
 CI = Compression Ignition; SI = Spark Ignition

* State specifically whether the engine is an emergency RICE or a limited use RICE. See 40 CFR 63.6675 for definitions of Emergency Stationary RICE, and Limited Use Stationary RICE (operates < 100 hours/year)

Initial Notification of Applicability

National Emission Standards for Hazardous Air Pollutants:
Stationary Reciprocating Internal Combustion Engines
40 CFR Part 63 Subpart ZZZZ

Yes, I am subject to 40 CFR Part 63 subpart ZZZZ National Emission Standards for
Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines

NAICS code(s): 327310

Compliance Date: Existing source: May 3, 2013 New/reconstructed source: upon initial startup

Note: The May 3, 2013 compliance date for existing sources applies to the following engine types:

- Existing non-emergency compression ignition (CI) stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions
- Existing stationary CI RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions
- Existing stationary CI RICE located at an area source of HAP emissions

Company name: American Cement Company, LLC

Facility name (if different): _____

Facility (physical location) address: 4750 East CR 470, Sumterville, FL 33585

My facility is a (please choose one): Major source Area source

Owner name/title: Cary Cohrs, President

Owner/company address: P. O. Box 445 Sumterville, FL 33585

Owner telephone number: (352-569-5393)

Owner email address (if available): _____

ATTACHMENT 3
KILN & COOLER CONSTRUCTION DATE


Kiln and Cooler Construction Date

2. NSPS Subpart F Applicable Requirements - NSPS 40 CFR 60 Subpart F as amended in the September 9, 2010 Federal Register (effective date of November 8, 2010 , which will be prior to the effective date of the initial Title V operation permit for this facility) has additional requirements for kilns and clinker coolers for which construction commenced after June 16, 2008. In order to confirm whether these requirements are applicable to this facility, please provide the date(s) of commencement of construction for the kiln and for the clinker cooler and the basis for these dates.

The actual commencement of construction date for the Kiln is March 13, 2007; Gantt Chart line 417 for Preheater Foundations.

The actual commencement of construction date for the Cooler is July 9, 2007; Gant Chart line 510 for Cooler/Burner Building Foundations.

Gantt Chart Line 510 for Cooler/Burner Building Foundations



ATTACHMENT 4
QUARRY & RAW MATERIAL STORAGE CONSTRUCTION DATE


Quarry and Raw Material Storage Construction Date

3. Subpart 000 Applicable Requirements - NSPS 40 CFR 60 Subpart 000 (Standards of Performance for Nonmetallic Mineral Processing Plants) is applicable to EU 001 (Raw Material Quarrying, Crushing and Storage). This is not reflected in the application, as an identification of applicable requirements attachment was not provided for EU 001. Please provide such attachment. (*See also Note below item 4. below.*) Subpart 000, as amended in the April 29, 2009 Federal Register, has additional requirements for mineral processing equipment for which construction commenced on or after April 22, 2008. In order to confirm whether these requirements are applicable to any of the non-metallic mineral processing equipment at this facility, please provide the date(s) of commencement of construction for the limestone processing, storage, and handling equipment at this facility and the basis for these dates

The actual commencement of construction date for the Raw Material Storage is February 12, 2007; Gantt Chart line 197 for Raw Material Building excavation.

The commencement of construction date for the Quarry is not specified, but the Request for Change Order dated October 18, 2007 with attached schedule shows active construction in the Quarry.

Gantt Chart Line 197 for Raw Material Building Excavation



ATTACHMENT 5
COAL MILL & COAL STORAGE CONSTRUCTION DATE

Coal Mill and Coal Storage Construction Date

4. Subpart Y Applicable Requirements - NSPS 40 CFR 60 Subpart Y (Standards of Performance for Coal Preparation and Processing Plants) is applicable to the coal processing and conveying equipment at this facility (EU 007), including coal crushers/grinders, and coal storage, transfer and loading systems. This is not reflected in the application attachment Identification of Applicable Requirements - EU 007 (*see Subpart LLL 40 CFR 63-1356 note below). Different Subpart Y requirements apply to equipment that commenced construction on or before April 28, 2008, equipment that commenced construction after April 28 and on or before May 27, 2009, and equipment that commenced construction after May 27, 2009. In order to confirm whether these requirements are applicable to this facility, please provide the date(s) of commencement of construction for the coal processing, storage and conveying equipment at this facility and the basis for these dates.

The actual commencement of construction date for the Coal Storage Building is January 9, 2007; Gantt Chart line 819 for Foundations for Coal Storage Building.

The actual commencement of construction date for the Coal Conveyor is February 15, 2007; Gantt Chart line 826 for Coal Conveyor Foundation.

The actual commencement of construction date for the Coal Grinding is December 3, 2007; Gantt Chart line 825 for Coal Grinding Foundation.

Request for Change Order

D. B. Construction Services, Inc
4309 Raleigh Street Tampa Florida 33619
Phone: (813)248-6258 Fax: (813)248-5201

Client: American Cement

Date 10/18/2007

Client P.O. #:

Project Number: 061-088

Project: Quarry

Cost Code: _____

Change order No.: 001

Contact: Alexander Smeets

THE CONTRACT IS CHANGED AS FOLLOWS:

The following items resulted in production loss during the weeks ending 10/23/07 and 10/30/07:

1. Delay in site preparation; Owner to strip and bring site up to elevation. After being informed that site was ready, DBCS Mobilized crew. It was found that the Storage & MCC building site was not large enough nor was it at the correct elevation. This was discovered early on the first day. Owner was notified immediately.
2. Incorrect control points and drawing co-ordinate locations resulted in additional layout work.

(See attachment 1)

*ALL OTHER CONTRACTUAL OBLIGATIONS REMAIN UNCHANGED

| | | |
|---|-------------|---------------|
| *The original Contract Sum was..... | | \$ 475,000.00 |
| *Net change by previously authorized Change Orders..... | \$ _____ | |
| *The Contract Sum prior to this Change Order was..... | | \$ 475,000.00 |
| *The Contract Sum will be increased by this Change Order in the Amount of..... | \$ 5,395.00 | |
| *The new Contract Sum including this Change Order will be..... | | \$ 480,395.00 |

*The Contract Time will be increased by _____ 8 Days

*The date of Substantial Completion as of the date of this Change Order therefore is: _____ n/a

Client _____

D. B. CONSTRUCTION SERVICES INC.

Contractor

Address _____

4309 Raleigh Street

Address

By: _____

By: _____

Date: _____

Date: _____

SEPTEMBER 2007

| Monday | | | | Tuesday | | | | Wednesday | | | | Thursday | | | | Friday | | | |
|--------------------------------|----------------|----------------|---------------|-------------------------------|----------------|----------------|---------------|-------------------------------|----------------|----------------|---------------|-------------------------------|----------------|----------------|---------------|--------------|----------------|----------------|---------------|
| 17-Sep | | | | 18-Sep | | | | 19-Sep | | | | 20-Sep | | | | 21-Sep | | | |
| 3 men x 8 hours (of 10) lost. | | | | 3 men x 8 hours (of 10) lost. | | | | RAIN OUT | | | | 3 men x 5 hours (of 10) lost. | | | | No Work | | | |
| INCOMPLETE SITE PREP | | | | | | | | | | | | | | | | | | | |
| <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> | <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> | <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> | <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> | <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> |
| Supt | \$ 45.00 | 8 | \$ 360.00 | Supt | \$ 45.00 | 8 | \$ 360.00 | | | | | Supt | \$ 45.00 | 5 | \$ 225.00 | | | | |
| Carp | \$ 35.00 | 16 | \$ 560.00 | Carp | \$ 35.00 | 16 | \$ 560.00 | | | | | Carp | \$ 35.00 | 10 | \$ 350.00 | | | | |
| \$920.00 | | | | \$920.00 | | | | \$0.00 | | | | \$575.00 | | | | \$0.00 | | | |
| 24-Sep | | | | 25-Sep | | | | 26-Sep | | | | 27-Sep | | | | 28-Sep | | | |
| 4 men x 10 hours (of 10) lost. | | | | 3 men x 7 hours (of 10) lost. | | | | 3 men x 5 hours (of 10) lost. | | | | | | | | | | | |
| RE-LAYOUT | | | | | | | | | | | | | | | | | | | |
| INCOMPLETE SITE PREP | | | | | | | | | | | | | | | | | | | |
| <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> | <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> | <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> | <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> | <u>Craft</u> | <u>Hr Rate</u> | <u>No. hrs</u> | <u>Amount</u> |
| Supt | \$ 45.00 | 20 | \$ 900.00 | Supt | \$ 45.00 | 7 | \$ 315.00 | Supt | 45 | 5 | \$ 225.00 | | | | | | | | |
| Carp | \$ 35.00 | 20 | \$ 700.00 | Carp | \$ 35.00 | 14 | \$ 490.00 | Carp | 35 | 10 | \$ 350.00 | | | | | | | | |
| \$1,600.00 | | | | \$805.00 | | | | \$575.00 | | | | \$0.00 | | | | \$0.00 | | | |

ATTACHMENT 6
MERCURY MONITOR INSTALLATION REQUIREMENT

Hg Monitor Installation Requirement

5. Hg Monitor Installation Requirement – Specific Condition No. 21.b of Construction Permit 1190042-001-AC, as amended by Construction Permit 190042-006-AC, requires that a mercury (Hg) CEMS be installed within 240 days following the first year of operation, with the first year of operation defined as 365 calendar days after the first day the kiln produces clinker. Please provide the date of the first kiln clinker production, and the resulting deadline date for installation of the Hg CEMS. Please also provide the status of Hg CEMS procurement and installation, and an anticipated schedule for CEMS certification (required by the above permit condition to be completed 90 days after CEMS installation).

The first clinker was produced on May 17, 2009.

The deadline for the Hg-CEMS installation is January 12, 2011.

The Hg-CEMS will be delivered beginning the week of December 27, 2010.

Installation will begin the week of January 3, 2011.

The CEMS certification is scheduled to be performed within 90 days of the installation date.

ATTACHMENT 7
CAM APPLICABILITY

CAM Applicability

6. CAM Applicability for Baghouses DC-1 and DC-2 – In the CAM Applicability Analysis and CAM Plan attachment to the application, under the section labeled Units Not Subject to CAM Requirements, Baghouse ID No. DC-1 and DC-2 are shown in the list of five baghouses to which it was determined that CAM did not apply. While a basis for this determination was supplied for three of the listed baghouses, it was not provided for Baghouses DC- and DC-2. These two baghouses also appear in the list on the following page under Compliance Assurance Monitoring Plan: Fabric Filters for PM Control. Please indicate whether these two baghouse should be removed from the list of baghouses for which CAM does not apply, or provide a basis for why it does not apply.

(Note – As indicated in the section labeled Inherent Process Equipment in the above CAM attachment, in order for a piece of equipment to be considered as inherent to the operation rather than strictly a control device, three questions need to be answered in the affirmative. 1.) Is the primary purpose of the equipment other than to control emissions to comply with the applicable PM emissions limit (e.g., product recovery, worker safety)/ 2.) Would the equipment be installed if there were no applicable emissions limit in place for this emissions unit? 3.) Is the efficiency at which the equipment is designed to be operated above that which would be required to assure compliance with the applicable emissions limit (e.g., a significant margin of compliance)?)

- The attached spreadsheet shows the CAM Plan applicability of the baghouses. CAM applies to DC-1 and DC-2.

| CAM APPLICABILITY | | | | | | | |
|----------------------------|------------------------------|---|--|--|---|--|-------------------|
| EU | Baghouse | Process | Purpose of Equip | Installation Use | Operating Efficiency vs. Compliance Limit | Potential Manufacturing % of \$\$ Loss | Applicable to CAM |
| 002 | F10 (3J1.BF01) | Raw meal transfer to air lift to homogenizing silo | Controlled pressure relief from air slide that would otherwise be forcing raw meal into the atmosphere by air pressure in the air slide transfer. | Maintain raw meal in process | Higher | 25% | Yes |
| | G07 (3K1.BF02) | Raw meal transfer to homogenizing silo | Controlled pressure relief from the air lift to silo transfer process that would otherwise be forcing raw meal into atmosphere through the silo vent | Maintain raw meal in process | Higher | 25% | Yes |
| | G10 (3K1.BF01) | Homogenizing silo bin vent | Controlled pressure relief from silo that would otherwise be forcing raw meal through vents into atmosphere as the silo fills. | Maintain raw meal in process | Higher | 25% | Yes |
| | E38 (4E1.BF01) | Filter dust surge bin | Controlled pressure relief for returned material air lift that would be forcing raw meal into the atmosphere through the silo vent | Maintain raw meal in process | Higher | 25% | Yes |
| | H08 (4C1.BF01) | Raw meal transfer from homogenizing silo | Controlled pressure relief from air slide that would otherwise be forcing raw meal into the atmosphere by air pressure in the air slide transfer. | Maintain raw meal in process | Higher | 25% | Yes |
| 003 | E19 (4E1.PB01) | Preheater/kiln/cooler/raw mill through main stack | Environmental control of material from various sources that are not otherwise controlled by process baghouses. | Maintain compliance with PM and PM10 emission limits exiting the main stack | Higher | N/A | Yes |
| 004 | L03 (4T1.BF01) | Clinker cooler discharge | Capture clinker dust from pan conveyor near discharge of cooler and place back into pan conveyor to clinker storage silos for further processing | Maintain clinker dust in process | Higher | 75% | Yes |
| | L06 (4T1.BF02) | Clinker transfer to clinker silo #1 | Capture clinker dust from transfer process and place into clinker storage silo #1 for further processing. Also, a controlled pressure relief for the silo. | Maintain clinker dust in process | Higher | 75% | Yes |
| | M08 (4T1.BF03) | Clinker transfer to clinker silo #2 | Capture clinker dust from transfer process and place into clinker storage silo #2 for further processing. Also, a controlled pressure relief for the silo. | Maintain clinker dust in process | Higher | 75% | Yes |
| | DC-1 (5E1.BF01) | Clinker transfer from Clinker Silo #1 | Capture clinker dust from transfer process and place into pan conveyor for further processing in finish mill | Maintain clinker dust in process | Higher | 75% | Yes |
| | DC-2 (5E1.BF02) | Clinker transfer from Clinker Silo #2 | Capture clinker dust from transfer process and place into pan conveyor for further processing in finish mill | Maintain clinker dust in process | Higher | 75% | Yes |
| 005 | N-93 (5F1.PB02) | Finish mill air separator | Separate fine cement for transfer to cement silos from course cement that goes back into finish mill for further grinding. | Designed for the process of separating fine from course cement | Higher | 100% | No, Inherent |
| | N-94 (5F1.PB01) | Finish mill sweep | Assists in pulling cement through finish mill and returns captured cement to air slide transfer to bucket elevator taking cement to separator | Designed for the process of capturing cement from finish mill to transfer to separator | Higher | 100% | Yes |
| 006 | N-91 (5F1.BF01) | Cement transfer from finish mill | Controlled pressure relief of bucket elevator being fed from an air slide that would otherwise be forcing cement into the atmosphere from the bucket elevator. | Maintain cement in process | Higher | 100% | Yes |
| | Q-25 (5K1.BF01) | Cement silos # 1,2,3,5 | Controlled pressure relief from silos that would otherwise be forcing cement through vents into atmosphere as the silo fills. | Maintain cement in silo for sales | Higher | 100% | Yes |
| | Q-26 (5K1.BF02) | Cement silo #4 | Controlled pressure relief from silo that would otherwise be forcing cement through vents into atmosphere as the silo fills. | Maintain cement in silo for sales | Higher | 100% | Yes |
| | Q-14 (6D1.BF01) | Truck Loadout #1 | Controlled pressure relief from transfer to customer truck that would otherwise be forcing cement from the truck as it fills. | Maintain cement in process to sell | Higher | 100% | Yes |
| | Q-17 (6D2.BF01) | Truck Loadout #2 | Controlled pressure relief from transfer to customer truck that would otherwise be forcing cement from the truck as it fills. | Maintain cement in process to sell | Higher | 100% | Yes |
| | R-12A (6G1.BF01) | Packhouse Bagging | Controlled pressure relief from air slides transferring cement to the bagging system and bucket elevator that would otherwise be forcing cement into the atmosphere. | Maintain cement in process to sell | Higher | 100% | Yes |
| 007 | S-22 (CR1.PB01) & (CR1.PB02) | Coal/Pet Coke Mill | Separate fine coal/pet coka for transfer to coal silos from course cement that goes back into coal mill for further grinding. | Designed for the process of separating fine coal for transfer to storage silo. | Higher | 100% | No, Inherent |
| | S-26 (CV1.BF01) | Coal Pet Coke Bin | Controlled Pressure relief from bin that would otherwise be released coal through vents into atmosphere as the silo fills. | Maintain coal in process for fuel | Higher | 100% | No, < 100 TPY |
| Process Design | | Pressure relief is an integral part of the process since if pressure were not released no transfer of material would be possible | | | | | |
| Business Financials | | Considering the value of the material being processed the uncontrolled release of the material could not be tolerated from a business perspective | | | | | |

**ATTACHMENT 8
INDICATOR RANGES**

Indicator Ranges

7. Justification for Indicator Operating Ranges in CAM Plan for Baghouse PM Control Devices - The proposed Compliance Assurance Monitoring (CAM) Plan for the eighteen (18) baghouses at this facility to which the application indicated that CAM did apply included the same monitoring primary indicator of baghouse pressure drop, with the same indicator operating range of 2-8' w.g. The justification for this generic indicator range is not sufficient. The indicator range needs to be established and justified separately for each baghouse (or manufacturer/model number of baghouse where common equipment was installed). For those baghouses for which PM compliance stack testing was done (e.g., Main Baghouse (EU 003), and Baghouse ID N-93 (EU 005)), the indicator range should be based in part on the observed baghouse pressure drop range during the compliance test(s) (see 40 CFR 64.4(c)). (It can also include data from other emissions testing done on the stack.) For baghouses without stack testing data, as well as those with stack test data, other information may be considered in selecting the indicator operating ranges such as: data from tests performed on similar units at similar facilities; control device manufacturers data, guarantees and recommendations; empirical information concerning the assessment of control technology performance (e.g., empirical performance information from a control technology handbook); and theoretical considerations based on generally accepted engineering practices (i.e., engineering judgment and assessment). *(Note - the above was taken from the EPA CAM Technical Guidance Document - 8/98.)*

Please submit a baghouse pressure drop indicator operating range for each baghouse (or group of baghouses that are the same manufacturer and model number), along with a justification for each that demonstrates to the Department that operation of the baghouse within this range will provide reasonable assurance of ongoing compliance with the applicable PM/PM10 emission standards (0.01 gr/dscf and 0.007 gr/dscf, except for EU 003 (different form of limit), and EU 005 Finish Mill Air Separator (0.007 gr/dscf for both PM & PM10)).

Information received from facility personnel indicating manufacturer's specification of the ideal operating pressure ranges of the baghouses in question are being submitted below:

| EU ID | ACC ID | Tag No. | Manufacturer | Indicator Range |
|-------|--------|----------|--------------|-----------------|
| 002 | F10 | 3J1.BF01 | CAMCORP | 4"-7" |
| 002 | G07 | 3K1.BF02 | CAMCORP | 4"-7" |
| 002 | G10 | 3K1.BF01 | CAMCORP | 4"-7" |
| 002 | E38 | 4E1.BF01 | CAMCORP | 4"-7" |
| 002 | H08 | 4C1.BF01 | CAMCORP | 4"-7" |
| 003 | E19 | 4E1.PB01 | CAMCORP | 4"-7" |
| 004 | L03 | 4T1.BF01 | CAMCORP | 4"-7" |
| 004 | L06 | 4T1.BF02 | CAMCORP | 4"-7" |
| 004 | M08 | 4T1.BF03 | CAMCORP | 4"-7" |
| 004 | DC-1 | 5E1.BF01 | DONALDSON | 4"-7" |
| 004 | DC-2 | 5E1.BF02 | DONALDSON | 4"-7" |
| 005 | N-94 | 5F1.PB01 | CAMCORP | 3"-5" |
| 006 | N-91 | 5F1.BF01 | CAMCORP | 4"-7" |
| 006 | Q-25 | 5K1.BF01 | CAMCORP | 4"-7" |
| 006 | Q-26 | 5K1.BF02 | CAMCORP | 4"-7" |
| 006 | Q-14 | 6D1.BF01 | CAMCORP | 4"-7" |
| 006 | Q-17 | 6D2.BF01 | CAMCORP | 4"-7" |
| 006 | R-12A | 6G1.BF01 | CAMCORP | 4"-7" |

JAN 06 2011

Southwest District

For the EU 003 Main Baghouse, the response also needs to address the secondary indicator of change in duct opacity as measured by the continuous emissions monitoring (COMS) system. The proposed indicator range of "any sudden and sustained step-change (increase) in opacity documented by the trend of the 6-minute averages seems too vague and imprecise to be practical for the plant operators, or verifiable/reviewable for the Department. More specific levels/time periods should be established and justified based on analysis of available COMS data during testing periods and normal operation of the plant.

- The COMS data is captured in the DAS from which 6-minute averages are continuously and historically reported. The Visible Emission limit is 10% opacity for a 6-minute averaging period. The CAM Plan will be implemented for the Main Baghouse when there are five (5) consecutive 6-minute averaging periods of Opacity above 5%.

ATTACHMENT 9
D/F TEST REPORT SUBMISSION

D/F Test Report Submission

8. D/F Compliance/Performance Testing - D/F compliance/performance testing using coke and tires as supplemental fuel was conducted beginning on September 15, 2010. In accordance with Rule 62-297.310(8), F.A.C., test reports are required to be submitted no later than 45 days after the completion of testing. Prior to issuance of an Intent to Issue and Draft Title V operation permit, the Department must receive compliance test report showing compliance with the D/F standard, using these supplemental fuels, in both the raw mill on and raw mill off operating modes. The permit application will be considered incomplete until such test report is received. Please submit a schedule for submittal of the required compliance test report.

- The report was submitted on October 25, 2010.

Charles Robertson

From: Charles Robertson [crobertson@americancementcompany.com]
Sent: Monday, October 25, 2010 4:36 PM
To: 'Danielle Osbrach'
Subject: RE: Thank you for delivering reports

Danielle:

Thank you for all your help.

Charlie

From: Danielle Osbrach [mailto:dosbrach@americancementcompany.com]
Sent: Monday, October 25, 2010 4:31 PM
To: Charles Robertson
Subject: Re: Thank you for delivering reports

All done. They stamped the received date and Rhonda will be giving it to Danielle.

Thanks,

Danielle Osbrach

On Oct 25, 2010, at 2:52 PM, "Charles Robertson" <crobertson@americancementcompany.com> wrote:

Danielle:

Ms. Henry's telephone number is

813-632-7600 x-104

Thank you,

Charlie

From: Danielle Osbrach [mailto:dosbrach@americancementcompany.com]
Sent: Monday, October 25, 2010 2:48 PM
To: 'Charles Robertson'
Subject: RE: Thank you for delivering reports

Do you happen to have Danielle's phone number just in case I have any trouble when I get down there?

From: Charles Robertson [mailto:crobertson@americancementcompany.com]
Sent: Monday, October 25, 2010 12:22 PM
To: 'Danielle Osbrach'
Subject: Thank you for delivering reports

Danielle:

Two (2) of the reports go to FDEP, Danielle Henry, or may be best to ask for Rhonda Hughes.

Two (2) of the reports are for ACC files.

Thank you making this delivery to FDEP.

Charlie

ATTACHMENT 10
O&M PLAN REVISION

O&M Plan Revision

...review of the O&M Plan based on the amended Subpart LLL requirements in 40 CFR 63.1347 and 63.1350(f) also finds that the plan is inadequate in addressing the following:

1. The requirements of 63.1347(a)(1) state that the O&M Plan must include “Procedures for proper operation and maintenance of the affected source and air pollution control devices in order to meet the emission limits and operating limits of §§63.1343 through 63.1348”. Procedures for operation and procedures for maintenance must be specified in the O&M Plan for each affected piece of process or emission control equipment. The O&M Plan as submitted does not include equipment specific operation and maintenance procedures as required.

2. The requirements of 63.1347 (a)(2) - “Corrective actions to be taken when required by paragraph §63.1350(f)(3)”. 63.1350(f)(3) states:

“Corrective actions. If visible emissions are observed during any Method 22 visible emissions test conducted under paragraphs (f)(1) or (f)(2) of this section, you must initiate, within one-hour, the corrective actions specified in the site specific operating and maintenance plan provisions in §63.1347.”

This requirement for corrective actions now applies to all affected process and control equipment, not just the raw mill or finish mill as was the case previously. The O&M plan must specify specific corrective actions for each affected piece of process or emission control equipment. The O&M Plan as submitted does not include equipment specific corrective actions as required.

40 CFR 63.1347(b) states - “Failure to comply with any provision of the operations and maintenance plan developed in accordance with this section is a violation of the standard.” In order to determine if the O&M Plan is being complied with in accordance with this requirement, the plan must contain specific provisions for all affected equipment for operation and maintenance procedures, and for corrective actions in the case of excess opacity observations.

Please revise the O&M Plan to address the above deficiencies.

Revised O&M Plan are attached here.

American Cement Company, LLC

Sumterville, FL

Operation & Maintenance Plan

Revision date: December 2010

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

| Section | Page No. |
|---|-----------------|
| 1.0 Introduction | 4 |
| 1.1. Plan Scope | 4 |
| 1.2. Facility Description | 4 |
| | |
| 2.0 Operation and Maintenance Plan | 4 |
| 2.1. Operational Procedures | 4 |
| 2.2. Maintenance Procedures | 5 |
| | |
| 3.0 Opacity Monitoring Procedures | 6 |
| 3.1. Monthly Visible Emission Monitoring | 6 |
| 3.2. Daily Visible Emission Monitoring | 6 |
| 3.3. Visible Emission Observation | 7 |
| | |
| 4.0 Corrective Action Measures | 8 |
| 4.1. Corrective Action | 8 |
| | |
| 5.0 Plan Implementation | 9 |
| 5.1. Implementation | 9 |
| Table 5-1 | 10 |

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

Attachments

Attachment 1 - APCD, Visible Emission Tests, & Corrective Actions.....11
Attachment 2 – Monthly 10-Minute VE Inspection Report.....13
Attachment 3 – Daily 6-Minute VE Inspection Report.....15
Attachment 4 – Corrective Action Report.....17

Appendices

Appendix 1 – Preventive Maintenance Protocols.....19
Appendix 2 – Annual Inspection of Combustion Systems.....23
Appendix 3 – 10-Minute VE Initial Responses.....26
Appendix 4 – Finish Mill 6-Minute Initial Response.....30
Appendix 5 – Camcorp Maintenance Documentation.....32
Appendix 6 – Donaldson Maintenance Documentation.....38
Appendix 7 – Redecam Maintenance Documentation.....44

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

1.0 Introduction

1.1. Scope of Plan

This operation and maintenance plan (“Plan”) has been prepared for compliance with the requirements of 40 CFR 63.1347 (a). Facilities that are subject to **40 CFR 63 Subpart LLL**, which is the MACT Standard for Portland Cement Plants, must prepare and comply with a written operations and maintenance plan for affected sources. The MACT standards are industry specific USEPA emission control standards and the cement industry standards are referred to as PCMACT. The Plan covers the entire facility, cement plant and quarry. The raw materials from the quarry typically contain sufficient moisture to maintain visible emission compliance with material crushing and transfer and handling visible emission standards. “Furthermore, the first conveyor transfer point subject to this subpart is the transfer point associated with the conveyor transferring material from the raw material storage to the raw mill, §63.1340 (c). Failure to comply with any provision of the operation and maintenance plan developed in accordance with paragraph (a) of this section shall be a violation of the standard”, §63.1347 (b).

1.2. Facility Description

This facility, which includes a Portland cement manufacturing plant and a surface mine, is owned and operated by American Cement Company, LLC (ACC).

The manufacture of Portland cement primarily involves the crushing, grinding, and blending of limestone, clays and other raw materials into a chemically proportioned mixture which is heated in a rotary kiln to extremely high temperatures to produce clinker nodules. The clinker is cooled and ground, with a small quantity of gypsum, to produce finished cement. ACC uses coal, whole scrap tires, diesel fuel and used oil as fuel sources for the kiln system. The primary/operating kiln fuel is pulverized coal. The air heater is fired with diesel fuel and used oil.

2.0 Operation & Maintenance Procedures

2.1. Operational Procedures

Facility operation shall be in accordance with the prescribed procedures of the equipment manufactures, suppliers and those typical for cement manufacturing facilities. The air pollution control devices are listed on the *APCD, Visible Emissions Tests and Corrective Actions* found as Attachment 1. The units included in this plan are incorporated into the plant equipment Management Plus preventative/predictive maintenance program. Equipment maintenance and inspections are scheduled and conducted routinely, throughout the year, in accordance with the PM program. Records of maintenance repair and inspection activities are captured in the work order section of the Maintenance Plus system. The equipment maintenance inspections will insure proper operation, and maintenance when needed, of all process and air pollution control

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

devices. Operations personnel will also routinely perform the required visible emissions inspection of the control devices that are not equipped with continuous opacity monitoring systems (COMS) and other affected sources.

The kiln system baghouse inlet temperature will be monitored according to § 63.1350 (4) (g). The continuous temperature monitors shall meet the requirements of 63.1350 (g)(1) through (g)(5) and monitor the 180 minute rolling average temperature. This thermocouple will be changed out on a quarterly basis using manufacturer calibrated thermocouples, or a thermocouple certified by a lab to NIST standards.

The kiln system baghouse exhaust is monitored by a continuous emission monitoring system, (CEMS) and continuous opacity monitoring system (COMS). The CEMS and COMS record and tabulate emissions and monitoring data which is reported to the regulatory agency as required by the Title V permit. Reasonable precautions will be taken to minimize fugitive emissions throughout the facility. All employees are trained and encouraged to be aware of fugitive sources of emissions, report them and to follow-up with corrective action measures as soon as practical; to abate the emissions.

2.2. Maintenance Procedures

An inspection and preventive maintenance (PM) program is established for all emission control units in the Manager Plus work order program. The periodic preventive maintenance protocols are located in Appendix 1, Preventive Maintenance) The preventive maintenance protocols are the established equipment inspection schedules, procedures implemented as a result of the ACC PM process and manufacturer's recommendations; wherein proper operation of process equipment and emission control devices is ensured via routine inspections and maintenance activities. Emission control device inspection include such items as inspection of air cleaning systems, checking the system for proper lubrication, damper or flop gate operation, cleaning cycles, dust removal and pressure drop indications. In addition to, routine preventive maintenance inspections, production personnel will conduct daily VE inspections, Method 22, on the dust collectors for the finish mill and finish mill separator and monthly Method 22 observations will be conducted for all other dust collectors, except the main baghouse which is monitored by a COMS; with a reduced frequency as provided in 40 CFR 63 Subpart LLL. Process dust collectors, in most cases, are interlocked with process they control and typically will start up prior to or as the process is started and to run a sufficient amount of time after process shut down or feed is discontinued. The process control system software is Polcid, a software package designed by Polysius; who designed the facility and provided all of the major process components. This software package provides the feed back from I/O points throughout the plant and these inputs provide information needed for process optimization to minimize process upsets and/or failures.

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

The plant maintains a supply of critical and consumable replacement spare parts for process equipment dust collectors; in operating inventory. Dust collector bags are included as spare parts.

Appendix 5 contains maintenance information for Camcorp, Donaldson, and Redecam baghouses. This information is specific to each manufacturer of baghouse used at this facility.

In accordance with 40 CFR 63.1350 (3), ACC will conduct an annual inspection of the combustion system components of the kiln and air heater system. The checklists located in Appendix 2, or similar documentation, will be utilized as a record of the annual combustion system inspection.

3.0 Visible Emission Monitoring Procedures

3.1. Monthly Visible Emission Monitoring

Once per calendar month visible emissions tests, Method 22, will be conducted on the required APCD shown in Attachment 1. Testing will be conducted during daylight hours with the source in normal operation. These reports shall be maintained on file for a minimum of five years. Monitoring frequency will be reduced as provided in §63.1350 (a) (1), (ii), (iii) and (iv).

See Attachment 2 for the *Monthly 10-Minute VE Inspection Report* which lists the APCD meeting this requirement. Appendix 3 contains the Camcorp and Donaldson Initial Response Directives to follow in case of a positive Method 22 test result. The results of each month's observations are recorded on a *Monthly 10-Minute VE Inspection Report* form. In accordance with the provision of the permit, the frequency of monitoring will be reduced as applicable to the successive negative (no visible emissions) monitoring events recorded for each source.

If a source has no visible emission, using Method 22, for six (6) consecutive months the testing frequency may be reduced from monthly to semi-annually. If no visible emissions are observed during the semi-annual observations; testing may be decreased to annually. A positive VE on any source requiring Method 22 observation will return that source to monthly observations requirements 40 CFR § 63.1350 (a) (1) (i).

3.2. Daily Visible Emission Monitoring

See Attachment 3 for the *Daily 6-Minute VE Inspection Report* which lists the Finish Mill APCD meeting this requirement. Appendix 4 contains the Camcorp Initial Response Directives to follow in case of a positive Method 22 test result. The results of each month's observations are recorded on a *Daily 6-Minute VE Emissions Report* form.

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

3.3 Visible Emission Observation

The opacity/visible emission (VE) allowable for all baghouses, other than the main baghouse, is five (5) percent. Opacity is essentially a measurement or indication of the amount of light obscured/scattered by particles in the exit gas stream and in the case of an observer, the amount of background obscured by the particles. The measurement of opacity is either made by an in stack-monitoring device or by the unaided human eye, for baghouse opacity determinations it will be the latter, except for the kiln system baghouses. Opacity is measured over a range of zero (0) to one hundred (100) percent. A certified observer can make opacity determinations over a wide percentage range. However, observations in the ten (10) percent and below range can be very subjective. Furthermore, when observing opacity in the lower, <10%, ranges; factors such as sunlight, background color, and the position of the observer relative to the source can greatly bias the results.

A baghouse system will usually lack sufficient moisture/water vapor to cause a steam/condensate plume, except for finish mill and the kiln system baghouse, when the correct atmospheric conditions exist. Otherwise a baghouse should have virtually no visible emissions (VE) from the discharge point. However, even with low moisture in a hot stack gas, there can be a detached steam plume during ambient conditions of cold temperature and sufficient humidity. Otherwise, the baghouse discharge will remain clear (no VE) unless there is a failure in the filter medium resulting in a leak between the clean and dirty sides of the unit. When there is a steam plume present the opacity, if any, should be read at a point after the steam has dissipated. With a detached plume, steam forms beyond the discharge point, if sufficient space is available between the discharge point and the steam plume you may read opacity at the point of discharge.

Compliance of a point source with an opacity standard is determined by Method 9 observation or a COMS; averaging readings over a six minute observation period. In the case of a Method 9 observation, a 30 minute or 60 minute observation period will allow the observer to detect potential changes in opacity due to process variations and/or bag cleaning events; particularly for pulse-jet baghouses. It is not out of the ordinary to see an increase in opacity after a cleaning event takes place even with the system in good condition. However, this increase sometimes may not be perceptible by an observer. Method 22 is used only to establish the presence of visible emissions, not the percent of opacity.

Method 22 is used only to determine the presence of visible emissions and not the percent opacity, therefore; observer certification is not required to conduct the Method 22 observations. An employee familiar with the process, the principles of baghouse operation and the Method 22 procedure can perform the observation. Prior to beginning the Method 22 observation, verify that the source to be observed is in operation; under normal conditions. As soon as possible after determining that the source is operating normally, begin conducting the 10-minute or 6-minute Method 22's.

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

The observer should position themselves a minimum of fifteen (15) feet from the emission point, when practical, and where the sun is not directly in the eyes of the observer and preferably within a 140 sector of the observers back when they is facing the emission point. It is best if the observer is perpendicular to the plume. Where this is not practical, keep the line of sight angle to 45 degrees or less. Read one plume at a time and do not attempt to read a plume through another plume or dust from other sources. Once in position, fill out the observation form and note the start time and then observe the emission point continuously for required period of time, 10-minute or 6-minutes, and note the end time of the observation. If there is break in the observation period, note the time of the break and a new start time when the observation starts again to complete the observation period, 10-minute or 6-minute. At the end of the observation, the observer will verify that all sources observed operated continuously during the observation period. If any of the sources stopped or shut down operation during the observation period, another Method 22 must be completed for the source after it re-starts. For operating purposes, if a unit operates for any portion of a day it is considered an operating day and the daily observation must be completed for the unit. The required VE observations must take place if the source operates for any portion of a day. You should try to get the observation completed as early in the operating day as possible; after sun rise. *No observations for Method 22 or Method 9 may be conducted during the nighttime hours.* The requirements for conducting the monthly 10-minute Method 22's does not apply to a "totally enclosed" conveying system transfer point. A totally enclosed transfer point is defined as "*a conveying system transfer point that is enclosed on all sides, top, and bottom*".

4.0 Corrective Action Procedures

4.1. Corrective Action

If visible emissions are observed during an inspection, the Corrective Action Log found as Attachment 4 shall be completed to document corrective actions; as needed to supplement the VE inspection forms. Any work orders resulting from the corrective action should be attached to the corrective action log and both should be submitted to the Environmental manager. The Corrective Action Log should be completed each time corrective action takes place.

4.2. Corrective Action Procedures

As mentioned in **Section 3.1 Monthly Visible Emission Monitoring** corrective actions are found in Appendix 3 and **Section 3.2 Daily Visible Emission Monitoring** the corrective action procedures are found in Appendix 4.

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

5.0 Plan Implementation

5.1. Implementation

This plan, as required by the Title V permit that incorporates 40 CFR 63 Subpart LLL, will be used to insure compliance with the relevant terms and condition of the permit. The plan must be submitted to the Administrator for approval. Prior to submitting the plan to the Administrator, the plan may be revised without the Administrator's review. If revised after submittal to the Administrator, the revised edition must be submitted to the administrator for review and approval.

If any part of this plan is found to be ineffective, inadequate or unnecessary, the plan may be modified. After any revision that makes changes to procedures or is required by process changes or practices; a revised plan may be submitted to the administrator for approval. If the Administrator approves the revised plan or takes no action within 90 days, ACC may implement the revised plan. Revisions will be documented in Table 5-1.

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

Attachment 1

Air Pollution Control Device

Visible Emissions Tests

Corrective Actions

**American Cement Company, LLC - Sumterville Cement Plant
APCD, Visible Emission Tests and Corrective Actions
Attachment 1**

| Emission Units | Process or Equipment | Process | Title V Control Device Number | ACC Control Device Equipment ID No. | Required Visible Emissions Observation | Opacity Limit | Corrective Action Procedure |
|-----------------------|------------------------------------|-------------------------------|--------------------------------------|--|---|----------------------------|------------------------------------|
| EU-002 | Raw Mill | Raw Mill | Main Baghouse | 4E1.PB01 | COMS | <10% | CAM |
| | | Raw Meal Airslide/Aeropol | F-10 | 3J1.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | Blending Silo | Homogenizing Silo - Top | G-07 | 3K1.BF02 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Kiln Feed Mixing Chamber | G-10 | 3K1.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Kiln Feed Airslide/Aeropole | H-08 | 4C1.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| EU-003 | Kiln System | Kiln | Main Baghouse | 4E1.PB01 | COMS | <10% | CAM |
| | | Top of Kiln Baghouse Dust Bin | E-38 | 4E1.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| EU-004 | Clinker Transport & Storage | Clinker Cooler | Main Baghouse | 4E1.PB01 | COMS | <10% | CAM |
| | | Cooler Discharge @ Conveyor | L-03 | 4T1.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Clinker Silo No. 1 - Top | L-06 | 4T1.BF02 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Clinker Silo No. 2 - Top | M-08 | 4T1.BF03 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Clinker Silo Tunnel No. 1 | DC-1 | 5E1.BF01 | Monthly 10 - minute | <5% | DONALDSON 10-Min VE Response |
| | | Clinker Silo Tunnel No. 2 | DC-2 | 5E1.BF02 | Monthly 10 - minute | <5% | DONALDSON 10-Min VE Response |
| EU-005 | Finish Mill | Finish Mill | N-94 | 5F1.PB01 | Daily 6 - minute | <5% | CAMCORP 6-Min VE Response |
| | | Finish Mill Separator | N-93 | 5F1.PB02 | Daily 6 - minute | <5% | CAMCORP 6-Min VE Response |
| EU-006 | Cement Handling, Storage & Packing | Finish Mill Cement Handling | N-91 | 5F1.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Cement Silos No. 1,2,3,5 | Q-25 | 5K1.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Masonry Cement Silo No. 4 | Q-26 | 5K1.BF02 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | Bulk Truck Loading | Truck Loadout - (1) East | Q-17 | 6D2.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Truck Loadout - (2) West | Q-14 | 6D2.BF02 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| Packing | Packhouse | R-12A | 6G.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response | |
| EU-007 | Coal / Coke Grinding | Fine Coal/Pet. Coke Transport | S-26 | CV1.BF01 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Coal/Pet. Coke Grinding No. 1 | S-22A | CR1.SF07 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |
| | | Coal/Pet. Coke Grinding No. 2 | S-22B | CR1.SF08 | Monthly 10 - minute | <5% | CAMCORP 10-Min VE Response |

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

Attachment 2

Monthly 10-Minute VE Inspection Report

**American Cement Company, LLC - Sumterville Cement Plant
Monthly 10-Minute VE Inspection Report
Attachment 2**

| Title V Air Quality Permit No.: 1190042-006-AC | | Date: _____ 10 - Minute Visible Emission Observations | | | | | | | | | | | | | |
|--|-----------------------|---|----|---------------|------|-------|------|-----------------------------------|-----|----|----------------|-----|-----|--------------------------|--|
| Baghouse Location | Emission Point ID No. | Normal Operation | | Military Time | | Wind | | 10 - Minute Method 22 Observation | | | Sky Conditions | | | Comments or Work Order # | |
| | | Yes | NO | Start | Stop | Speed | Dir. | POS | NEG | DN | CL | PC | OC | | |
| Finish Mill Cement Handling (EP-N91) | 5F1.BF01 | | | | | | | | | | | | | | |
| Masonry Silo No. 4 (North) (EP-Q25) | 5K1.BF01 | | | | | | | | | | | | | | |
| Cement Silo No. 1,2,3,5 (South) (EP-Q26) | 5K1.BF02 | | | | | | | | | | | | | | |
| Truck Loadout - (1) (West) (EP-Q14) | 6D2.BF01 | | | | | | N/A | N/A | | | | N/A | N/A | N/A | |
| Truck Loadout - (2) (East) (EP-Q17) | 6D2.BF02 | | | | | | N/A | N/A | | | | N/A | N/A | N/A | |
| Cement Packing - (EP-R12-A) | 6G1.BF01 | | | | | | | | | | | | | | |
| Coal/PetCoke Mill (S-22A & S-22B) | CR1.PB01 | | | | | | | | | | | | | | |
| Coal/PetCoke Bin (S-26) | CV1.BF01 | | | | | | | | | | | | | | |
| Clinker Cooler (L-03) | 4T1.BF01 | | | | | | | | | | | | | | |
| Clinker Silo #1 (L-06) | 4T1.BF02 | | | | | | | | | | | | | | |
| Clinker Silo #2 (M-08) | 4T1.BF03 | | | | | | | | | | | | | | |
| Clinker Silo #1 Discharge | 5E1.BF01 | | | | | | N/A | N/A | | | | N/A | N/A | N/A | |
| Clinker Silo #2 Discharge | 5E1.BF02 | | | | | | N/A | N/A | | | | N/A | N/A | N/A | |
| Raw Meal to Silo (West) (F-10) | 3J1.BF01 | | | | | | | | | | | | | | |
| Top of Homogenizing Silo (G-07) | 3K1.BF02 | | | | | | | | | | | | | | |
| Homogenizing Silo Bin Vents (G-10) | 3K1.BF01 | | | | | | | | | | | | | | |
| Raw Meal from Silo (H-08) | 4C1.BF01 | | | | | | | | | | | | | | |
| Filter Dust Surge Bin (E-38) | 4E1.BF01 | | | | | | | | | | | | | | |

Operating Condition: If "No" is checked, explain in comments

Observations: POS - Positive NEG - Negative DN - Operation Down

Comments:

| | |
|--|--|
| | |
|--|--|

Print Name

Signature

| |
|--|
| |
|--|

Date Completed

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

Attachment 3

Daily 6-Minute VE Inspection Report

**American Cement Company, LLC, Sumterville, FL
Daily 6-Minute Visible Emissions Inspection
Attachment 3**

Title V Air Quality Permit No.:
1190042-006-AC

Permit Condition: E9

| Equipment | ID No. | Normal Operation | | Observer's Name (Print) | Date | Military Time | | Time Min. | Observations | | | Work Order # |
|---|----------|------------------|----|-------------------------|------|---------------|------|-----------|--------------|-----|----|--------------|
| | | Yes | No | | | Start | Stop | | POS | NEG | DN | |
| Finish Mill Dust Collector EP-N94 | 5F1.PB01 | | | | | | | 6 | | | | |
| Finish Mill Separator Dust Collector EP-N93 | 5F1.PB02 | | | | | | | 6 | | | | |

Comments:

For "Operating Conditions" and "Observations" place a check or slash in the appropriate column

Operating Condition: If "No" is checked, explain in comments Observations: POS - Positive NEG - Negative DN - Operation Down

The source shall be observed for six minutes *continuously*. An observation time period must be indicated for all operating equipment.

If dusting conditions (Positive) are noted, corrective action must be initiated within one-hour of the time that the dusting was noted. Record work order number and document corrective action taken in comment section

If dusting conditions are noted for two consecutive days, contact Production Coordinator to conduct a 30 minute Method 9 observation on the second day. A copy of the Method 9 form must be attached to the second day's report. If the results of the Method 9 test is less than 5%, resume normal VE schedule. If the result of the Method is greater than 5%, continue corrective actions.

Observer: _____
Print Name

Signature

JAN 06 2011

Southwest District

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

Attachment 4

Corrective Action Report

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

Appendix 1

Preventive Maintenance Protocols

DAILY PREVENTIVE MAINTENANCE OF BAGHOUSES

The daily preventive maintenance functions are conducted by Production Personnel during their completion of the Daily Production System Checklist.

Each checklist contains the following baghouse inspection items:

- Magnehelic Reading _____ (4 w.c. to 7 w.c.)
- Air Pressure _____ (80 to 90 psi)
- Check for leaky diaphragms _____ (work order if problem found)
- Pulse off time _____ (seconds)
- Pulse on time _____ (fraction of second)
- Tipping Valves or Rotary Valves Operable _____ (work order if problem found)

Adjustments are made or a maintenance work order is written to address any problem found during the inspection.

MONTHLY PREVENTIVE MAINTENANCE OF BAGHOUSES

The monthly preventive maintenance functions are conducted by Production Personnel

Weekly functions:

- Drain moisture trap.
- Check magnehelic lines for plugging.

A maintenance work order is written to address any problem found.

ANNUAL PREVENTIVE MAINTENANCE OF BAGHOUSES

The annual preventive maintenance functions are conducted by Maintenance Personnel:

Annual inspection items:

- Open top of baghouse and inspect clean air chamber for:
 - Signs of bags leaking.
 - Inspect tubesheet for holes, cracks, deformation.
 - Corrosion in corners or sheetmetal connections.

- Open hopper to inspect for:
 - Material build-up.
 - Grizzly plugging.
 - Baffle wear.
 - Holes or tears in lower end of bags.
 - Inlet duct cleanliness.
 - Corrosion in corners or sheetmetal connections.

- Open Tipping Valves or Rotary Valve to inspect for:
 - Wear or material build-up on tipping valve surface.
 - Wear of material build-up in rotary valve vanes
 - Deformation of rotary valve vanes.
 - Material build-up.
 - Grease bearings.
 - Leaks through seals.

- Inspect exterior of baghouse for:
 - Corrosion.
 - Holes in sheetmetal.
 - Air piping corrosion.
 - Air piping and manifold connection air leaks.

Any build-up of material found is cleared from system.

A maintenance work order is issued to address any mechanical problem found.

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

Appendix 2

Annual Inspection of Combustion Systems

Annual Air Heater inspection of the components of the combustion system

Fan/Duct:

- Inlet screen free of dirt and debris.
- Inlet cone clean and proper clearances.
- Vibration free

Windbox Inspection:

- Slide damper is not bound and moves freely.
- Register louvers are clean and move freely.
- Check actual movement of slide damper and register louver matches COEN “AC” fuel control valve movement. (See Linkage Inspection below.)

Flame Scanner:

- Scanner lens inspected and cleaned.
- Scanner is positioned to pick up both pilot and main flame.

Pilot:

- Inspect pilot assembly.

Oil Firing:

- Oil nozzle clean.
- Guide pipe in correct position for oil firing.
- No lickback (fire licking behind spinner/shield)

Linkage Inspection:

- Full travel of COEN “AC” fuel control valves.
 - Check actual movement of slide damper and register louver matches control valve movement. (See Windbox Inspection above.)
 - Verify 4 to 20mA output equals 0% to 100% travel
- All threaded connections of drive rods are tight. Locknuts inspected for tightness.
- Rod end bearings in good condition.
- All drive levers in proper position and tight on drive shaft. Levers pinned to prevent slippage.
- Lost motion in linkage at absolute minimum.

Annual Kiln inspection of the components of the combustion system

Burner:

- Check the mouthpiece and the components exposed to coal dust for wear.
- Calibration of indicating instruments.

Flame Monitor:

- System is failsafe and self monitoring if failure occurs.

Primary Air Fan:

- General inspection of the fan for looseness, build-up on blades.
- Condition of hose connection.
- Vibration free.

Beck Actuator:

- Check for full travel of the valve.
- Check valve connection for tightness.
- Verify 4 – 20mA equals 0% to 100% travel.
- Verify damper matches Beck Actuator movement.

Cooling Air Fan:

- General inspection of the fan for looseness, build-up on blades.
- Vibration free.

Cooling Air Fan Valve:

- Check for full travel of the valve.
- Check valve connection for tightness.
- Verify 4 – 20mA equals 0% to 100% travel.
- Verify damper matches valve movement.

Annual Kiln inspection of the components of the combustion system

| Equipment # | Description | Task (s) |
|----------------------|-----------------------|--|
| <u>Burner</u> | | |
| 4K1. BU01 | Burner | Check the mouthpiece and the components exposed to coal dust for wear Calibration of indicating instruments |
| <u>Burner</u> | | |
| 4K1. BU01 | Flame Monitor | Inspect for proper functioning |
| <u>Burner</u> | | |
| 4K1.BU01.FNP01 | Primary Air Fan | General inspection on fan, check for looseness, build up, etc |
| <u>Burner</u> | | |
| 4K1. BU01 | Beck Actuator | General inspection on valve to ensure correct operation |
| <u>Burner</u> | | |
| 4K1.BU01.FNC01 | Cooling Air Fan | General inspection on fan, check for looseness, build up, etc |
| <u>Burner</u> | | |
| 4K1.BU01.TVJ01 | Cooling Air Fan Valve | General inspection on valve to ensure correct operation |

Operation & Maintenance Plan

American Cement Company, LLC, Sumterville, Florida

Last Revision: December 2010

Appendix 3

Camcorp and Donaldson

10-Minute VE Initial Response

CAMCORP 10-MINUTE VE INITIAL RESPONSE

If visible emissions are observed during a 10-minute Method-22 visible emissions test, initiate within one-hour these specified initial corrective actions for a CAMCORP Baghouse.

While at the unit, immediately make the following determinations:

Step 1: Is the magnehelic reading between 4" w.c. and 7" w.c.?

Step 2: Is the back-blast system pulsing?

Step 3: Is the back-blast air pressure between 80 psi and 90 psi?

Step 4: Is the fan damper set between 50% and 75% fully open?

Step 5: Is the hopper empty of material?

Possible meaning of the answers:

If the magnehelic reading is below 4" w.c. the back-blast time between pulses may be too quick and need to be lengthened.

If the magnehelic reading is higher than 7" w.c. the back-blast time between pulses may be too long and need to be shortened.

If there is no back-blast pulsing sound the timer system may be faulty.

If the back-blast air pressure is lower than 80 psi then adjust the regulator into the proper range. The bags may be too dirty with dust permeating through the bags.

If the back-blast air pressure is higher than 90 psi then adjust the regulator into the proper range. The high pressure may be opening the fabric enough to allow dust to permeate through the bags.

If the fan damper is over 75% open there may be too much air flow through the baghouse revealed by a high magnehelic reading. Close the damper to 50% initially.

If nothing accomplished above stops the visible emissions then remove the hopper inspection door by following these instructions:

Step 1: Turn off the back-blaster system.

Step 2: Allow 1 to 2 minutes for any compressed air to bleed off.

Step 3: Carefully open the inspection door.

Step 4: Inspect the interior of the hopper for material build-up, and the grizzly being plugged with material. Clean out as necessary. Also look up towards the bags to see if any apparent holes or tears are evident.

Step 5: Replace the inspection door making sure there is a good seal. If no air suction sound is heard around the door the seal is good. Repair seal as necessary to achieve a good seal.

Perform a 30-minute Method-9 Visible Emission Test to determine the actual average opacity.

If the opacity is above 5%:

- Make a work order on the Manager Plus system for Maintenance to make further inspections and repairs as necessary.
- Complete an incident report for submission to FDEP.

DONALDSON 10-MINUTE VE INITIAL VE RESPONSE

If visible emissions are observed during a 10-minute Method-22 visible emissions test, initiate within one-hour these specified initial corrective actions for a Donaldson dust collector.

While at the unit, immediately make the following determinations:

Step 1: Is the manometric reading between 4" w.c. and 7" w.c.?

Step 2: Is the back-blast system pulsing?

Step 3: Is the back-blast air pressure between 80 psi and 90 psi?

Possible meaning of the answers:

If the manometric reading is below 4" w.c. the back-blast time between pulses may be too quick and need to be lengthened.

If the manometric reading is higher than 7" w.c. the back-blast time between pulses may be too long and need to be shortened.

If there is no back-blast pulsing sound the timer system may be faulty.

If the back-blast air pressure is lower than 80 psi then adjust the regulator into the proper range. The bags may be too dirty with dust permeating through the bags.

If the back-blast air pressure is higher than 90 psi then adjust the regulator into the proper range. The high pressure may be opening the fabric enough to allow dust to permeate through the bags.

Perform a 30-minute Method-9 visible emission test to determine the actual average opacity.

If the opacity is above 5%:

- Make a work order on the Manager Plus system for Maintenance to make further inspections and repairs as necessary.
- Complete an incident report for submission to FDEP.

Operations & Maintenance Plan

American Cement Company, LLC, Sumterville, FL

Last Revision: December 2010

Appendix 4

Finish Mill 6-Minute Initial Response

CAMCORP FINISH MILL 6-MINUTE VE INITIAL RESPONSE

If visible emissions are observed during a 6-minute Method-22 visible emissions test, initiate within one-hour these specified initial corrective actions for a CAMCORP Baghouse.

Make the following determinations:

Step 1: Is the magnehelic reading between 3" w.c. and 5" w.c.?

Step 2: Is the back-blast system pulsing?

Step 3: Is the back-blast air pressure between 80 psi and 90 psi?

Possible meaning of the answers:

If the magnehelic reading is below 3" w.c. the back-blast time between pulses may be too quick and need to be lengthened.

If the magnehelic reading is higher than 5" w.c. the back-blast time between pulses may be too long and need to be shortened.

If there is no back-blast pulsing sound the timer system may be faulty.

If the back-blast air pressure is lower than 80 psi then adjust the regulator into the proper range. The bags may be too dirty with dust permeating through the bags.

If the back-blast air pressure is higher than 90 psi then adjust the regulator into the proper range. The high pressure may be opening the fabric enough to allow dust to permeate through the bags.

Within 24-hours of the initial positive Method-22 visible emission test result perform a follow-up test.

If the Method-22 visible emission test is positive during the follow-up test then within 1-hour of the positive result perform a 30-minute Method-9 Visible Emission Test to determine the actual average opacity.

If the opacity average is above 5%:

- Make a work order on the Manager Plus system for Maintenance to make further inspections and repairs as necessary.
- Complete an incident report for submission to FDEP.

Operations & Maintenance Plan


American Cement Company, LLC, Sumterville, FL

Last Revision: December 2010

Appendix 5

CAMCORP MAINTENANCE DOCUMENTATION

Operation Camcorp Baghouse



Operating Principle

- A. Solids laden air or gases enter the unit at the hopper or housing inlet.
- B. Air passes through the filter media.
- C. Solids are retained on the filter media surface.
- D. Cleaning cycle consists of a momentary blast of 90-100 psig compressed air:
 1. Momentarily taking a row of bags off stream through pressure reversal.
 2. Flexing filter bags.
 3. Solids are released to fall towards hopper and through rotary valve or other discharge equipment.

Troubleshooting Camcorp Baghouses

Excessive Pressure Drop Across Filter Bags

The differential pressure gauge (Magnehelic) on your baghouse should read 7" w.g. or less. Higher readings and/or steadily increasing readings are an indication that the main airflow through the dust collector may be restricted and a potential process problem such as poor suction at duct pickup points may exist. In extreme cases (over 17" w.g.) filter bags will be damaged. Check the following:

Pressure Gauge

Check the differential pressure gauge (Magnehelic) and the tubing leading to the dust collector for proper operation. Disconnect the lines at the gauge or manometer and clear with compressed air. Look for loose fittings, cracked, broken or pinched tubing.

Compressed Air System

Inspect the compressed air system as follows to make sure that all of the filter bags are being cleaned:

If none of the solenoid valves are operating check the timer using the "Troubleshooting the Timer" section.

Check the air pressure at the compressed air manifold. It should recover to 80-90 psig before each pulse. If not, check to make sure that the compressed air supply system is in good operating condition, correctly sized, and supply lines are not too small or restricted. Listen for the sound of compressed air flowing continuously through one or more diaphragm valves. This is an indication of a valve or valves "stuck" in the pulsing position. The usual causes for this condition are either a leak in the tubing between the solenoid and diaphragm valves or dirt in the solenoid and/or diaphragm valves.

Check to see that all solenoid valves are firing by holding a finger over each solenoid exhaust port as described in the following paragraph.

With the compressed air system operating, energize the timer board to begin pulsing. Check to see that all solenoids are firing by placing a finger over the exhaust port of one of the solenoid valves. When the solenoid valve being checked is energized by an electrical pulse from the timer board the finger at the exhaust port should feel a short blast of air. Quickly move to the next solenoid valve in the firing order noting any valves that do not fire or are stuck open causing a continuous airflow out

of the exhaust port of the valve. At this time note the quality of the compressed air. It should be clean, dry, and oil free.

Bags Loaded with Dust

This is a condition known as blinding. If the dust is dry see the next four paragraphs below. If the dust is wet see the paragraphs below on "Water Leaks" and "Condensation".

1. Dust Not Discharging from the Hopper

Check hopper for over-loading or bridging across the dust discharge. To open the hopper turn off the back blasting system, and open the hopper door slowly. Correct by clearing material from hopper and cleaning "grizzly" for free flow of material out of hopper. To close hopper carefully replace door making sure the seal is good. If air suction is heard reset the door or check gasket and repair as necessary to assure a good seal. Turn on the back blasting system.

2. Air Flow Too High

If the main airflow is too high to allow dust to drop off of the filter bags, an excessive pressure drop across the dust collector will result and dust will build up in the system. In many cases this high pressure drop in turn leads to a reduction in the main air flow so that it is necessary to remove the dust accumulation from the filter bags (and the rest of the system) before measuring the main air flow volume.

Visually inspect the bags for heavy caking. See notes above on proper opening of discharge hopper for inspection. If caking is evident see the note below and take the necessary action to clean the bags. Next, measure the main airflow with a pitot tube or equivalent device and compare with the original volume for which the unit was designed. If the flow is too high, cut back the main fan to prevent a recurrence of the problem.

3. Particle Size and Dust Load

If possible, compare the dust particle size and loading with the original design specifications. Finer dust may cause a higher pressure drop. High free lime 2.1+ will cause finer dust particles so call the lab to determine the free lime results to determine if this is a factor with high pressure drop.

4. Bags Too Tight

Bags that have shrunk on their cages may not flex sufficiently during the compressed air pulse to loosen caked dust. If the bags were cleaned or laundered pull a bag tight around its cage. You should be able to "gather" a small fold of material between your fingers.

Water Leaks

Inspect the dust collector housing and ductwork for holes, cracks or loose gasketing where water could enter the collector.

Condensation

If moisture has been condensing inside the collector check the dew point temperature of the incoming air stream. It may be necessary to insulate the collector and/or the ductwork leading to the collector to keep surface temperatures above the dew point and prevent condensation inside the dust collector.

NOTE: Collectors that have blinded bags can possibly be put into service by running the pulsing air system for 15 to 30 minutes with a 10 second "off time" and without the main fan or blower running. If the pressure drop is not lower when the main fan is started again remove the filter bags from the collector and replace. Make sure the timer "off time" has been reset to specifications prior to re-start. Information pertaining to filter bag cleaning may be obtained by calling your CAMCORP sales representative.

Extremely Low Pressure Drop**Differential Pressure Gauge**

Check the differential pressure gauge or manometer and the tubing leading to the dust collector.

Holes in Filter Bags or Bags Incorrectly Installed

Inspect the filter bags for holes, rips, tears or excessive wear. Assure that the filter bags were installed correctly according to the "Bag & Cage Installation" section.

Ductwork and Dampers

Inspect the ductwork to and from the dust collector for air leaks or blockage. Assure that any dampers in the system are correctly positioned to allow for proper air flow through the dust collector.

Leaks in the Housing

Check the tube sheet (flat steel sheets from which the filter bags are suspended) and the dust collector housing for holes, cracks or loose gasketing that would permit air to bypass the dust collector or filter bags.

Continuous Flow of Dust in the Clean Air Exhaust (Primary Dusting)

Holes in the tube sheets

Check the tube sheet for holes, cracks or loose bolts that would permit dusty air to bypass the filter bags.

Puff of dust in the clean air exhaust after each pulse (Secondary Dusting)

Compressed air manifold pressure too high

Check compressed air manifold pressure gauge. If the pulsing air pressure is over 90 psig the filter bags may flex excessively and allow fine dust to pass through the bag material.

Worn filter bags

Inspect the filter bags for wear. Thin worn bags may not stop fine dust when flexed by a compressed air pulse.

Residual dust

If dust has migrated into the clean air plenum because of a dropped filter bag, torn filter bag or a hole in tube sheet, etc., the pulsing air may stir up the dust and allow it to escape into the clean air exhaust after each pulse. Residual dust may also be driven down inside the filter bags by the pulsing air. If the filter bags are filled with several inches of dust clean both the clean air plenum and the filter bags to avoid further problems.

Operations & Maintenance Plan

American Cement Company, LLC, Sumterville, FL

Last Revision: December 2010

APPENDIX 6

DONALDSON MAINTENANCE

DOCUMENTATION




OPERATION

Principle of operation

Dust-laden air is ducted into the chamber containing the filter elements, where it impinges on all their outer surfaces. A layer of dust builds up on the outside of the elements as the air itself penetrates the fabric (see Fig. 14a). The clean air emerges from the outlet header of each filter element into the cleaned air chamber and from there it is discharged, normally via the fan, to atmosphere.

At regular intervals, governed by the controller, each element in turn receives a short burst of compressed air from its respective jet tube (see Fig. 14b). The jet tube has a series of small-diameter jet orifices positioned adjacent to the outlet header of each filter element (see Figs. 14 and 17). These orifices are of an optimum size and distance from the filter element, ensuring that a large volume of air is induced by each injection of compressed air. This causes a brief, powerful reversal of airflow through the filter element, flexing the fabric outwards and effectively dislodging the dust layer.

In this way the pressure drop across the whole filter is kept at a virtually constant level, enabling the Dalamatic to operate continuously, twenty-four hours a day.





MAINTENANCE



A platform should be used when carrying out maintenance where the position of the technician's feet is greater or equal to 2 metres above ground level.



Always isolate the electrical supply before servicing.

Routine inspection

To maintain the optimum performance of any Dalamic filter, a routine inspection should be made to minimise down-time in the event of equipment malfunction, particularly on continuous performance applications and to ensure the equipment is maintained to its original supply condition.

Any abnormal change in pressure absorbed across the filter elements indicates a change in operating conditions and a fault to be rectified. For example, a prolonged stoppage of compressed air will cause an excessive build-up of dust on the elements, resulting in a greatly increased pressure drop.

After the fault has been rectified, resumption of compressed air cleaning will usually return the filter to normal efficiency. However, it is advisable to operate the controller in still-air conditions for a short period to dislodge any accumulated dust before putting the Dalamic filter into operation.

Filter resistance can be checked by connecting a U-tube manometer or differential-type pressure gauge to tapping points on the filter body and equipment being served (see Fig. 1). This will give a continuous indication of the state of the filter. Once running, the operating resistance will be relatively stable, the actual value depending on the air volume and the characteristics of the dust being handled.



To fit manometer connection to tapping point position, remove hexagon head set screw, nut and washers which blank-off tapping point hole located in base side panel. If exit header is fitted, access may be gained by removing the header cover. Fit a suitable manometer connection in place of the hexagon head set screw etc., ensuring it is capped when not in use. If requested, Donaldson can supply the recommended parts to enable connection to measuring equipment.

It is recommended to periodically inspect the general casing integrity.



Do not operate above recommended compressed air pressure. Excessive pressure will reduce the working life of components.



Dalamic housings or upstands fitted with explosion relief should be inspected weekly to ensure that the bursting panels are intact and clear of obstruction. During winter, particular care must be taken to prevent build-up of snow or ice on explosion panels.

MAINTENANCE

Servicing schedule

A record of all pressure checks should be kept in a log book to aid the speedy diagnosis of faulty operation.

Weekly


- 1 Open the valve at the bottom of the moisture separator bowl and allow the collected water to drain off, then close the valve.
- 2 Connect a manometer to tapping points (refer to Routine inspection) and measure the pressure drop across the filter.

Monthly

Check operation of solenoid and diaphragm valves. If it is found necessary to replace a diaphragm, use the following procedure (see Fig. 15):

Use service kit available from Donaldson.

- 1 Remove 6mm diameter nylon tube (A) by pulling out from valve.
- 2 Remove the hexagon head set screws and shakeproof washers securing the valve bonnet (B).
- 3 The diaphragm and spring (if fitted) can now be replaced, first ensuring the 'bleed' hole pin is not blocked.
- 4 Ensure that diaphragm fits over 'bleed' hole pin and that the nylon sealing washer is inside throat of valve.
- 5 Position spring (if fitted) inside bonnet recess.





Installation, Operation and Maintenance Manual

Dalamatic Insertable Dust Filters – Series DLM V

MAINTENANCE

- 6 Refit bonnet ensuring spring (if fitted) locates over diaphragm disc shoulder and bonnet locates over 'bleed' hole pin.
- 7 Refit and tighten the hexagonal head set screws and shakeproof washers.
- 8 Push-fit 6mm diameter nylon tube back into valve.

Annually

- 1 Moisture separator – Isolate the compressed air supply; remove and clean the filter element.
- 2 Air manifold – Having isolated the compressed air supply, remove the drain plug and air inlet connections and clean out any accumulated sludge and inspect to any current local legislation.



It may be necessary to remove a diaphragm valve for internal inspection purposes.

- 3 Doors – Check the dust seals on all access doors for damage or ageing and ensure that they are properly seated to prevent entry of water. This is particularly important where the filter is located outside or in a wet atmosphere.



Faulty seals must be replaced.

- 4 Filter elements (inserts and pads) – Remove the jet tubes then remove each filter element and check the general condition of the pad. Clean each pad using a vacuum cleaner. If the dust is of an abrasive nature it is advisable to examine the elements more frequently.



Pads showing holes must be replaced.



When refitting filter elements, do not over-tighten. If elements are horizontally mounted, tighten bottom clamp first. (Recommended maximum torque 20 ft-lbs f or 27 Nm.)

- 5 Jet Tubes – Check that the jet tubes are clean and that the jet orifices are clear.
- 6 Flameproof maintenance – It is important that all flameproof enclosures, motors and cable glands are inspected for corrosion and tightness on an annual basis.



In particularly aggressive environments, this period should be more frequent.



MAINTENANCE

TABLE 1 — FAULT LOCATION

| Symptom | Possible cause | Action |
|---|--|--|
| 1 Part loss of suction (excessive pressure differential). | 1.1 Compressed air malfunction. | a If compressor stopped, rectify compressor fault; check interlocks; check motor and supply; check drive. b If compressor OK, check pulses at manifold pressure gauge. c Clean filters, dismantle and clean moisture separator. d Check for excessive water or oil in compressed air supply, and possible accumulation in manifold. |
| | 1.2 No pulses of air to valves. | a Refer to 'Fault location' table in controller manual supplied with dust collector. |
| | 1.3 Filter blocked. | a Check that emptying device or equipment being served is working. Check starter overloads, fuses and interlocks. b Run filter clear*, then remove each element in turn and vacuum-clean all its outer surfaces. Renew any filter pads that are damaged. |
| | 1.4 Motor speed low. | a Check line voltage, phases, fan motor connections. For Star/Delta applications, check motor is in Delta. |
| | 1.5 Incorrect fan motor rotation. | a Check electrical connections and transpose if necessary. |
| 2 Total loss of suction. | 2.1 Fan motor stopped. | a Check motor supply overloads, fuses and interlocks (if fitted). b Check motor connections and windings. |
| | 2.2 Filter blocked. | a Check that emptying device or discharge equipment is working. Check starter overloads, fuses and interlocks. b Run filter clear*, then remove each element in turn and vacuum-clean all its outer surfaces. Renew any filter pads that are damaged. |
| | 2.3 Ducting blocked. | a Check throughout and clear. |
| 3 Visible effluent in clean air outlet. | 3.1 Filter elements not properly sealed. | a Tighten element retaining bolts to ensure compression of sealing rings. |
| | 3.2 Damaged filter pad. | a Damaged filter pad can be identified by the dust present in clean air chamber. Withdraw element and renew pad. |

*To run filter clear, switch off main fan only and allow the controller to perform several complete cleaning cycles before switching off compressor etc.

Operations & Maintenance Plan

American Cement Company, LLC, Sumterville, FL

Last Revision: December 2010

APPENDIX 7

REDECAM MAINTENANCE DOCUMENTATION

Redecam Handbook

1. DESCRIPTION OF FILTER

The Bi-Get bag filter is a device designed to clean dust-laden gases. The gas to be dedusted travels from the source to the inlet of the filter through a ducting system; a fan downstream from the filter provides the necessary draught to draw the gas through the complete system and exhausts the cleaned gas to atmosphere. The bag filter is made up of two distinct chambers, a “dusty” one and a “clean” one; to get from the former to the latter, the gas must pass through a porous filter medium (usually needlefelt) which retains the dust and allows the gas pass through.

The porous filter medium is made up of cylindrical bags, supported on iron wire “cages”; a drilled sheet (tube sheet), physically separates the two chambers and supports the filtering bags; the bags are inserted through the tube sheet from the clean plenum and penetrate for their full length into the dusty chamber. A sealing system between bags and tube sheets ensures that dust cannot flow from the dusty side to the clean one.

To prevent bags clogging as dust builds up on the dirty side, they must be periodically cleaned (in this way the permeability of the filter medium is kept within acceptable values). The cleaning, which is carried out automatically, is achieved by injecting into the bags the correct amount of compressed air. Dust removed from the bags during the cleaning cycle falls by gravity into the hopper below the dirty air chamber and is transported away by the dust disposal system.

2. MAINTENANCE



Instructions to carry out maintenance of filter within safety conditions and to train the staff, are shown in section USE OF FILTER WITHIN SAFETY CONDITIONS

2.1. ROUTINE MAINTENANCE

The filter has no parts subject to wear and the only items which must be periodically replaced are the filtering bags. Anyway, even in case that no particular fault has shown, it is advisable after a year's operation to carry out a thorough inspection, in order to eliminate any possible fault and cause of damage, allowing the system to work properly during bags' lifetime. The inspection consists of the following operations:

- Check of filtering efficiency
- Check of cleaning system efficiency
- Check of parts subject to wear

2.1.1. Check of filtering efficiency

'On-line' check

Sometimes, if the number of damaged bags is limited, it is possible to detect the row of bags containing the faulty one without stopping the filter. As a matter of facts, in some cases the punctured bag fills up with dust, so the compressed air shot causes a clearly visible dust "gust" at the stack; the smaller the filter and the shorter the ducts, the more evident is this effect. The "gust" has the same frequency as the cleaning cycle (normally about 1 every 5 min.). In this case, proceed as follows:



shut off, one by one, all sections, to detect the one containing the faulty bag



shut off, one by one, all air receivers, to detect the one which feeds the faulty bag



once detected the air receiver, set the cleaning control panel to "manual mode", then energise the pilot solenoid valves one by one, keeping an eye on the stack, until the one which causes the dust "gust" is detected



disconnect the pertinent solenoid valve, to eliminate the trouble until it is possible to carry out the inside inspection



If the control panel is equipped with the automatic detection system LVD, the above operation is performed automatically. For further details see the relevant instructions

The LVD system, as for said above, is not very efficient in case of large process filters and so its installation on such installations is not advisable.

'Off-line' check



Take all precautions mentioned in section USE OF FILTER WITHIN SAFETY CONDITIONS



Stop the I.D. fan or, if possible (sectional-type filters), shutoff the section to inspect



Open the sections acting either on the doors or the upper lids, as the case may be. If necessary, arrange for light up of plenum



inspect the state of the tube sheet:

- if it is clean or (after a long time of operation) it is covered with a thin veil of dust, the filter medium can be regarded as efficient
- if the tube sheet is covered with a thick veil of dust (≥ 5 mm), clean thoroughly the section, re-start the filter and repeat the inspection after a short while (depending upon dust load)
- if there are dust heaps or “gusts”, which origin is well detectable, remove, following the relevant directions, the damaged bags. Find out the cause of the trouble, re-start the system and repeat the inspection to verify the effectiveness of the intervention
- if the dust heaps are found along the edges of the tube sheet, remove the dust and check the welds. Find and eliminate the cause then re-start the system and repeat the inspection to verify the effectiveness of the intervention



If some damaged bags were found on checking and no spare parts would be immediately available, plug each faulty bag by placing a mill ball wrapped in a rag (possibly greased) on its secondary Venturi.

2.1.2. Check of cleaning system efficiency

To verify the efficiency of the cleaning system, proceed as follows:

- Check for compressed air net (pressure must be within stated range)
- Set the cleaning control panel to “automatic mode”



The panel starts energising the solenoid valves according to the pre-set sequence: the compressed air shot is characterised by a sharp noise, which should remain unchanged for all valves. At the end of the cycle the drain solenoid valve (if installed) is open, in accordance with relevant specifications.



In case of control panel failure, see the relevant operating handbook



In case of solenoid valves failure (anomalous opening/closing, suspect noises), go on as shown in section MAINTENANCE TO CORRECT FAILURES AND REMEDIES

2.1.3. Parts subject to wear

Other parts subject to long-term wear are:

- . pilot solenoid valve gaskets
- . pneumatic valve diaphragms
- . access door gaskets

The lifetime of the above-mentioned items depends on site and operating conditions (ambient temperature, no. of cleaning cycles, compressed air quality, working negative pressure, nature of treated gas); even if no faults are detected, it is advisable to run routine checks (frequency of checks depending on the type of installation).

If the filter is equipped with shutoff valves, they must undergo normal maintenance procedures for this kind of mechanical items (check and greasing of bearings); depending on the nature of the treated gas, the closing blades and the valve seats may be affected by wear; in this case, replace them.



In the long run, compressed air fittings may lose tightness; so, in order to avoid increasing of consumption and loss of efficiency, it is necessary to test periodically the tightness along the whole net.

2.1.4. Filtering bags' lifetime

Bags' lifetime depends upon type of installation, nature of dust, dust load. In most cases, by necessity, the guaranteed lifetime is a contractual period which cannot bind the supplier too long. Actually, the "expected" lifetime is much longer than the contractual one. So, it is not necessary to replace the bags at the end of the warranty period, but it is better to consider the following operating parameters:



bags pressure loss, as an absolute value and as a trend:

the maximum pressure loss which is normally regarded as a threshold limit to allow proper cleaning of bags is 150 mm w.g.; beyond such value, it is advisable to replace all bags. Usually, when this value is reached, filter operation becomes unsteady; this leads to a rapid increase of Δp itself and the system is not manageable any more.

In some particular conditions, the filter may be forced to run with a Δp higher than normal; in this case, which is anyway a sign of failure caused usually by cleaning or process troubles, it is advisable to get in touch with Redecam to carry out the proper checks.

In any case, the decision to replace the bags must keep into account operating conditions and, above all, I.D. fan draught capacity and system management economy.

If one of the above-mentioned conditions occur and there is the will of replacing the bags, it is necessary to replace all bags: in case of partial replacement, as a matter of fact, the brand-new bags, because of their higher permeability, are subject to an anomalous dust load which causes a quick deterioration.



dust at the stack:

the increase of dust emissions at the stack may be caused by a local or a generalised trouble. In the first case, the dust is found in well defined zones, normally along the edges of the sections; this occurs when, owing to failures of various nature, some bags are stressed much more than the others, so that the wearing action of the dust damages them very quickly. In this case, it is possible to replace only the damaged bags; instead, when the deterioration is generalised, it is necessary to replace all bags. Anyway, it is always advisable to get in touch with Redecam for a technical advice.

2.1.5. Inspection after commissioning



After commissioning, in order to verify design and assembling of gas distribution system, it is advisable to perform a first inspection. The inspection must be performed after a short time of operation (from 1 to 2 weeks, depending on operating conditions); it will consist mainly of a check of the filtering efficiency, as above described, and of a check of interior corrosion



To carry out filter internal inspection, take all precautions described in section USE OF FILTER WITHIN SAFETY CONDITIONS. Then enter the hoppers and the filter distribution ducts, providing the lighting, where necessary.



Verify the state of the sheets, remarking if there are zones in which the painting has been taken away by wear. In such zones it is necessary to install anti-wear sheets; the area of such protections must be much wider than the area of the damaged zones. If large corroded zones are found, it is advisable to get in touch with Redecam.



A following inspection is advisable, to verify the effectiveness of the remedy.

2.2. MAINTENANCE TO CORRECT FAILURES AND REMEDIES

The troubles which may require unforeseen maintenance and the pertinent remedies are the following:

- increased dust at the stack



go on as described in section CHECK OF FILTERING EFFICIENCY

- increased filter pressure loss
for a bag filter a gradual increase of bags Δp is perfectly normal; in some cases, anyway, that could be a sign of failures. In particular, in case of sudden increase and also in “suspicious” cases
 - check for correct positioning of shutoff devices (if any)



go on as described in section CHECK OF CLEANING EFFICIENCY



if the check is successful, measure the gas flow to the filter: if the measured value is higher than the design value, get in touch with Redecam to analyse the compatibility



if the measured value is within the design parameters, check the state of the bags as shown in section FILTERING BAGS' LIFETIME



in case of bags' lifetime shorter than expected, get in touch with Redecam

2.2.1. Remedies for other troubles

The compressed air pressure decreases or cannot rise

The fault is caused by a leakage somewhere in the net. Find and fix it.



shut off all air receivers:

- if pressure still does not increase, the leakage is either on the feeding net or on the pressure regulator; carry out necessary checks, consulting, if the case, the specific documentation.
- if pressure rises, reaching the proper value, open, one by one, the manual shutoff valves of the air receivers; in this way, the faulty one will be detected



when the faulty air receiver has been detected, re-open its manual shutoff valve and find out, by judging the noise, the cause of the leakage.

- If the trouble is due to a pneumatic valve, proceed as described in point 'A pneumatic valve does not open or does not close'
- If the trouble is due to a drain valve, try to fix it and, if the case, remove and replace it.
- For other problems get in touch with Redecam.

All pneumatic valves on one air receiver does not work



Verify that the shutoff valve of the air receiver is open.



Check the compressed air feeding pressure; if the case, set it again to design value.



Check the control panel for proper working, check consents to operation from PLC (if any), check power supply to solenoid valves



If all above checks are successful and the trouble persists, get in touch with Redecam.

A pneumatic valve does not open or does not close



Check power supply to solenoid valve.



Check connection between pneumatic valve and solenoid valve: the least leakage may cause a failure.



If a revolving union leaks, cut off some millimetres of the plastic hose and re-connect it. For detailed description of the operation, see handbook

MS-BF-04 - COMPRESSED AIR RECEIVERS
USE AND MAINTENANCE



Verify manually that the piston of the solenoid valve can move:

- if the test is successful, re-energise the solenoid valve
- if the operation is not successful or if the system is not working anyway, remove the piston and check the cylinder for foreign matters inside; verify also that the return spring is properly mounted.

- if the result is still unsuccessful, disassemble the pneumatic valve following the instructions shown in the handbook

**MS-BF-04 - COMPRESSED AIR RECEIVERS
USE AND MAINTENANCE**

and verify that all its parts are clean.



If all above-mentioned operations are successful and the failure persists, get in touch with Redecam.

Other troubles



In case of problems differing from those described in this section, or in case the above-mentioned interventions are unsuccessful, get in touch with Redecam.

2.3. EXTENDED STOP

Before stopping the plant for a long time, in order to preserve best the filter, it is advisable to perform the following operations:



Ventilate the filter with clean air (1/2 h - doors upstream the filter open) and reduced fan capacity (50% of nominal value) for a long period of time, in order to remove any trace of acidity from the plenum (to avoid interior corrosion).



In order to remove the dust from the bags, stop the I.D. fan and let the cleaning system run (1 h)



Let the dust disposal system work for other 15 min. after that the cleaning system has been stopped.



Grease all movable parts, especially dampers, door hinges, lid lifting devices (if any).



Before re-starting the plant after an extended stop, it is advisable to follow, fully or partially (that being dependant on type of installation and stop time), the directions stated in section PREPARING TO OPERATION.



In case of traces of corrosion inside or outside the sheets, before resuming operation, it is advisable to measure their thickness and consult Redecam about what to do.

ATTACHMENT 11
RICE INVENTORY & APPLICABILITY DETERMINATION